Attachment D.

Geologic Reconnaissance and Slope Stability Analysis

CHJ Consultants
1355 E. Cooley Drive, Suite C, Colton, CA 92324 • Phone (909) 824-7311 • Fax (909) 503-1136
15345 Anacapa Road, Suite D, Victorville, CA 92392 • Phone (760) 243-0506 • Fax (760) 243-1225
77-564A Country Club Drive, Suite 122, Palm Desert, CA 92211 • Phone (760) 772-8234 • Fax (909) 503-1136

June 21, 2018

El Monte Nature Preserve, LLC
1335 San Lucas Court
Solana Beach, California 92075
Attention: Mr. Bill Adams

Job No. 15383-8

Dear Mr. Adams:

This letter transmits two copies of our slope stability investigation report, prepared for the proposed El Monte Sand Mining project, located at 13964 El Monte Road in Lakeside, California.

We appreciate this opportunity to provide geotechnical services for this project. If you have questions or comments concerning this report, please contact us at your convenience.

Respectfully submitted,
CHJ CONSULTANTS

Jay J. Martin, E.G.
Vice President

JJM:lb

Distribution: El Monte Nature Preserve, LLC (2 and electronic)

SLOPE STABILITY INVESTIGATION
PROPOSED EL MONTE SAND MINING PROJECT
LAKESIDE, CALIFORNIA
PREPARED FOR
EL MONTE NATURE PRESERVE, LLC
JOB NO. 15383-8

June 21, 2018

El Monte Nature Preserve, LLC
1335 San Lucas Court
Solana Beach, California 92075
Attention: Mr. Bill Adams

Job No. 15383-8

Dear Mr. Adams:

Attached herewith is the report of slope stability investigation prepared for the proposed El Monte Sand Mining project, located at 13964 El Monte Road in Lakeside, California.

This report was based upon a scope of services generally outlined in our proposal dated June 24, 2015, and other written and verbal communications.

We appreciate this opportunity to provide geotechnical services for this project. If you have questions or comments concerning this report, please contact us at your convenience.

Respectfully submitted,
CHJ CONSULTANTS

Jay J. Martin, E.G.
Vice President

JJM:lb

TABLE OF CONTENTS

PAGE

INTRODUCTION 1

SCOPE OF SERVICES 2

PROJECT CONSIDERATIONS 3

SITE DESCRIPTION 4

PREVIOUS INVESTIGATIONS 5

FIELD INVESTIGATION 6

LABORATORY ANALYSIS 7

SITE GEOLOGY 7
- Geologic Units 8
- Geologic Structure 11

FAULTING AND SEISMICITY 12
- Regional Faults 12
- Regional Seismicity 13

GROUND-SHAKING HAZARD 14

GROUNDWATER 15

SLOPE STABILITY 17

SLOPE STABILITY EVALUATION 17
- Global Stability Calculations 18
- Surficial Stability Calculations 20
- Slope Stability Conclusions 20

LIQUEFACTION POTENTIAL AND SEISMIC SETTLEMENT 21

CONCLUSIONS 25

RECOMMENDATIONS 26
- Compacted Fills 26
- Fill Slope Construction 26
- Slope Protection 26

LIMITATIONS 26

CLOSURE 29

REFERENCES 30

AERIAL PHOTOGRAPHS EXAMINED 32

TABLE OF APPENDICES

APPENDIX A—MAPS AND CROSS SECTIONS

APPENDIX B—BORING LOGS

APPENDIX C—LABORATORY TEST RESULTS

APPENDIX D—GLOBAL STABILITY CALCULATIONS

APPENDIX E—GEOTECHNICAL CALCULATIONS

SLOPE STABILITY INVESTIGATION
PROPOSED EL MONTE SAND MINING
PROJECT
LAKESIDE, CALIFORNIA
PREPARED FOR
EL MONTE NATURE PRESERVE, LLC
JOB NO. 15383-8

INTRODUCTION

During August and September of 2015, this firm conducted exploratory drilling, laboratory testing and slope stability analysis for the proposed El Monte Sand Mining project that includes sand mining operations. A revised reclamation plan was evaluated during January 2016. The purposes of this investigation were to explore and evaluate the engineering geologic conditions at the subject site and to provide slope stability analysis for the mining and reclamation plan.

To orient our investigation, several documents and maps were provided for our use. These include the following:

- Project description for the El Monte Sand Mining and Nature Preserve project by EnviroMINE revised January 2016
- Reclaimed Bench Configuration Diagram dated January 20, 2016
- Reclamation Plan Set (6 sheets), dated January 24, 2016
- Preliminary Geotechnical Evaluation, El Monte Mining, Reclamation and Groundwater Recharge Project, by Ninyo & Moore, dated July 18, 2011
- Compendium Report of Geotechnical Investigations, El Capital Golf Course, Lakeside, California, by Shepardson Engineering Associates, Inc., dated July 28, 2003
- Attachment 1 of the Scope for Geotechnical Investigation document dated June 18, 2015

The approximate location of the site excavation area is shown on the attached Location Map (Enclosure A-1).

The results of our investigation, together with our conclusions and recommendations, are presented in this report.

SCOPE OF SERVICES

The scope of services provided during this investigation included the following:

- Review of published and unpublished literature and maps including geologic mapping by Todd (2004) and Tan (2002)
- Examination of aerial imagery dated 1953, 1964, 1966, 1968, 1971, 1980, 1981, 1989, 1994, 1996, 2002, 2004, 2005, 2006, 2010, 2011, 2012 and 2015
- Review of studies by prior consultants
- Geologic mapping of the site and adjacent area
- Marking of the exploration locations and notification of Underground Service Alert
- Coordination with County of San Diego Department of Environmental Health to obtain a waiver for grouting of the geotechnical borings
- Drilling and sampling four hollow-stem auger borings in the excavation area
- Laboratory testing of selected samples retrieved from the borings
- Slope stability calculations (limit equilibrium and surficial) for the proposed slopes under static and seismic conditions
- Evaluation of potential geologic hazards to the project including seismic shaking hazard

PROJECT CONSIDERATIONS

The project description indicates that the site will produce approximately 12.5 million tons of construction aggregate/sand material over a 12-year production period, followed by four years of reclamation. The project will include disturbance and reclamation of approximately 262 acres of a 479.5-acre site. Total reclaimed slope heights will be approximately 36 feet. A prior study considered deeper pit elevations; therefore, geotechnical borings up to 100 feet deep are available for the project. The purpose of the slope stability investigation is to provide reclaimed slope configurations consistent with the requirements of the Surface Mining and Reclamation Act, County of San Diego, and the Office of Mine Reclamation. This report addresses the items included in the County's "Scope for Geotechnical Investigation" dated June 18, 2015. That document includes requirements to address future groundwater levels as a result of an upstream dam breach, the stability of temporary slopes, and compaction of fill.

According to the Reclamation Plan (EnviroMINE, 2016), the project will be developed in four phases working from east to west. A drop structure to mitigate erosion by surface flows entering the pit along the upstream portion is planned at the east end. Wash fines will be used in backfilling excavations from water features (ponds) associated with a former golf course project. Wash fines will also be distributed on disturbed site areas. Excavations are not planned below the groundwater table. Reclamation of each phase area is planned to commence at the start of the subsequent phase.

A maximum pit depth of approximately 36 to 41 feet is anticipated based on proposed bottom elevations that range from 399 feet to 434 feet above mean sea level (amsl) and existing surfaces ranging from 438 feet amsl to 450 feet amsl at the west and east ends of the excavation area, respectively. Slopes are planned at 3 horizontal (h) to 1 vertical (v) inclination with an intervening bench. Excavation is not proposed beneath the groundwater table.

Our slope stability calculations for the proposed reclaimed slopes are based on configurations consistent with the Reclamation Plan. We modeled and evaluated a typical slope proposed for

development of the excavation area. Slopes flatter than 2(h) to 1(v) in alluvial materials situated above the groundwater table are typically considered stable. For completeness, we include engineering calculations of the gross stability of the proposed slope configuration under static and seismic conditions.

SITE DESCRIPTION

The site consists of an elongate area of undeveloped land within the margins of the San Diego River floodplain bounded by unpaved Willow Road to the north and paved El Monte Road to the south. The vegetated channel of the San Diego River trends roughly east to west as it bisects the site. A mine pit with surface water is adjacent to the site on the west, and residences are located near the southeast boundary. Land marginal to the floodplain is elevated above the active river channel forming terrace risers or benches north and south of the channel area. These benches were generally undeveloped at the time of our investigation. Site elevations range from approximately 450 feet amsl at the northeast limit of the proposed excavation area to 430 feet amsl at the western limit. Vegetation on the benches generally consists of a low growth of dried annual grasses and weeds with few large trees. The river channel includes a dense growth of trees. Bedrock slopes are locally bouldery north and south of the river floodplain. The eastern portion of the site includes areas formerly graded for an uncompleted golf course project that produced undulatory terrain and areas of fill.

Examination of aerial imagery indicates that the bench areas have previously been utilized for borrow material, material processing and equipment storage. Small structures were located in the northwest corner and southwest portion of the site as early as 1989. A covered open-sided structure remains in the northwest corner. No structures remain in the southwest portion of the site. Equipment and/or materials were stored in cleared areas adjacent to Willow Road and north of El Monte Road in the western portion of the site between 2005 and 2006. Materials processing areas were located in the western and northeastern portions of the site between 2005 and 2006 and included use of heavy equipment and sorting/stacking equipment. Grading for the golf course project in the eastern portion

of the site is visible in imagery dated May 2005. Changes to the site do not appear in aerial imagery since 2012 when equipment/materials were removed from an extensive fenced area in the southwest portion of the site.

Evidence of geologic hazards including landsliding or surface faulting was not observed in the aerial imagery examined.

The proposed reclamation configuration including the excavation area boundary and slope geometries is depicted on Enclosure A-2. Geologic cross sections are presented on Enclosures A-4.2 and A-4.4.

PREVIOUS INVESTIGATIONS

Several reports documenting geologic mapping, subsurface explorations and sampling, and groundwater monitoring for projects at and adjacent to the site were examined (Shepardson, 2003; Ninyo & Moore, 2011). Subsurface information and groundwater data from these investigations were utilized in our evaluation. Findings include:

- Alluvial soils up to 106 feet thick overlie granitic and metavolcanic bedrock along the floodplain axis.
- Groundwater occurs at elevations ranging from approximately 420 feet amsl on the east to 391 feet amsl on the west (Ninyo & Moore, 2011).
- Cut slopes at 2(h) to 1(v) should be grossly stable against deep-seated failure.
- Materials should be excavatable with standard heavy equipment; well drilling (depending on depth) may encounter hard bedrock formation below the alluvium.
- The site is subject to liquefaction.
- Faulting is not anticipated within the project area.
- Unprotected site soils are susceptible to erosion.

FIELD INVESTIGATION

Four hollow-stem auger borings were drilled to depths up to 100 feet below the existing ground surface (bgs) in the excavation area during August 2015 to supplement prior exploration by others. Existing roads were utilized and no access improvements were required. Drilling was performed using a CME 75 truck-mounted drilling rig equipped for soil sampling. The eastern portion of the project was added to the proposed excavation area after our field program was completed; therefore, we utilized prior explorations by others to characterize the subsurface conditions in the eastern portion of the project. The approximate locations of our exploratory borings are indicated on the attached Site Plan (Enclosure A-2).

Both a standard penetration test (SPT) sampler (2-inch outer diameter and 1-3/8-inch inner diameter) and a modified California ring sampler (3-inch outer diameter and 2.42-inch inner diameter) were utilized in our investigation. The penetration resistance was recorded on the boring logs as the number of hammer blows used to advance the sampler in 6-inch increments (or less if noted). The sampler was driven with an automatic hammer that drops a 140-pound weight 30 inches for each blow. After the required seating, samplers are advanced up to 18 inches, providing up to three sets of blowcounts at each sampling interval. The recorded blows are raw numbers without any corrections for hammer type (automatic vs. manual cathead) or sampler size (ring sampler vs. standard penetration test sampler). Both relatively undisturbed and bulk samples of typical soil types obtained were returned to the laboratory in sealed containers for testing and evaluation.

Exploratory boring logs, together with the uncorrected blowcount data and in-place density data, are presented in Appendix B. The stratification lines presented on the boring logs represent approximate boundaries between soil types, which may include gradual transitions.

At the completion of drilling, all borings were backfilled to the initial grade of the boring with soil drill cuttings and tamped using the drilling equipment augers. This backfilling operation is expected to compact the boring to a density approximating that of the existing soils. It is possible that some settlement of the backfilled material may occur. Our firm will not monitor boring locations for any settlement. This is deemed to be, and is accepted to be, the responsibility of our client.

Exploratory borings reported for prior investigations are included in Appendix B for reference.

A Site Plan indicating current and prior exploration locations, proposed slopes and the limits of proposed excavation is provided as Enclosure A-2.

LABORATORY ANALYSIS

Included in our laboratory testing program were field moisture content tests on all samples returned to the laboratory and field dry density tests on all relatively undisturbed samples. The results are included on the boring logs. Direct shear testing was performed on selected relatively undisturbed samples and one remolded sample in order to provide shear strength parameters for slope stability evaluations. Sieve analyses were performed on selected samples as an aid to classification.

Laboratory test results are presented in Appendix C. Soil classifications provided are in accordance with the Unified Soil Classification System (USCS).

SITE GEOLOGY

The site is located near the community of Lakeside in unincorporated San Diego County, east of Highway 67 and north of Interstate Highway 8. The site is situated in a broad river valley formed in bedrock terrain of the Peninsular Ranges geomorphic province. The Peninsular Ranges include plutonic and metamorphic crystalline rocks of Cretaceous and older age. The crystalline basement rocks are locally mantled by residual soils and capped by isolated alluvial/sedimentary remnants.

Valley bottoms are typically alluviated. Geologic units in the area include metavolcanic rocks likely coeval with the plutonic rocks of the Peninsular Ranges batholith, intrusive granitics and alluvial sediments deposited in the San Diego River floodplain.

GEOLOGIC UNITS:

The site was mapped on a topographic base using the geologic nomenclature of Todd (2004) for bedrock units, and alluvial nomenclature established for this investigation based on relative landscape position above the river channel. A Site Plan and Geologic Map is presented as Enclosure A-4.1. Cross sections are presented as Enclosures A-4.2 through A-4.4. The units designated for this investigation are described below. Structural examination of bedrock units was not included in the field investigation as excavations are not proposed within the bedrock materials and planned slope angles are very flat relative to the strength and ability of bedrock units to stand at steep angles.

Fill (f)

Fill associated with prior site use as a borrow area, dirt roads/tracks and pond/river channel embankments are derived from local materials including sand, silt and gravel from alluvium and soil. The eastern portion of the proposed excavation area includes fill and disturbed native soils associated with an uncompleted golf course project. Based on examination of aerial imagery, the entire bench area above the active river channel has previously been disturbed by ploughing or disking. The entire site should be considered disturbed ground based on its history of ploughing/disking and use for materials storage, borrow and processing. Larger areas of fill are shown on the Site Plan and Geologic Map (Enclosure A-4.1). Minor areas of fill occur within the Qya unit, primarily within the northeastern area of the future excavation area that was graded for the golf course project. All fill materials are considered undocumented and unsuitable for support of engineered improvements.

Recent Wash Deposits (Qw)

Wash deposits consisting of sand, silt and gravel are present in the active San Diego River channel. These sediments are unconsolidated, include clasts of the more durable bedrock types in the larger size fraction and incise the Qya unit. A dense growth of trees is present within these sediments.

Young Alluvium (Qya)

Alluvium consisting of unconsolidated sand and silt with gravel forms the elevated bench area adjacent to the river channel. The upper surface of these sediments is commonly a gray-brown, fine-grained sand and micaceous silt that is compressible and soft. This surface is heavily disturbed by burrowing and plant growth. This unit was mapped as young alluvium (Qya) by Todd (2004). These sediments are derived from weathering and erosion of adjacent bedrock hillsides that include granitic and metavolcanic rock types and reflect the color and mineral composition of the parent materials. Over bank deposits of fine-grained sand and silt deposited during river flooding are also present locally.

Older Alluvium (Qoa)

An isolated remnant of older alluvium may occur northwest of the excavation area; however field relations suggest that a portion of these materials is either disturbed or imported. These materials consist of strong reddish-brown silty sands that form a bench elevated relative to the Qya surfaces. Geomorphic relations and soil color suggest that these are older than Qya and represent an old land surface preserved above the active modern floodplain; however, the southern margin of the bench includes abundant concrete and metavolcanic debris/clasts that are inconsistent with granitic outcrops nearby. Concrete debris was observed to be buried within/beneath the reddish materials along the margin of the bench, and pedogenic soil development (clay coating, prismatic structure) was lacking in soils exposed at the margin. Aerial imagery indicates that this area was ploughed/furrowed in 1994, fallow in 2002 and cleared/graded in 2005 with equipment stored on a flattened surface. Several large trees visible since imagery dated 1953 remain near the margin of the deposit and are rooted in the Qya surface. The reddish-brown materials terminate near the trees as if placed to avoid burying the trunks. For purposes of this investigation, we interpret the Qoa unit to consist of a

natural terrace deposit (reddish-brown sediments) that was partially altered by clearing and placement of a fill derived from the Qoa surface along the unit margin that incorporates imported debris and rock fragments. The alternative interpretation is that these materials were imported from an offsite area, end-dumped and spread/flattened with equipment. Explorations are not available to make a more definitive conclusion as to the source of the unit designated Qoa. This unit is not within the proposed excavations area.

Granitic Bedrock (Kgr)

As described by Todd (2004), these rocks consist of undivided tonalite and granodiorite of early Cretaceous age, most lithologically similar to tonalite of Alpine (Ka), Japatul Valley Tonalite (Kjv), and Corte Madera Monzogranite (Kcm). Includes lesser gabbro and metavolcanic rocks. This unit forms bouldery hillsides along the northwest margin of the proposed excavation area and is interpreted to underlie the site at depth. Clasts of this unit were observed as rounded cobbles in the Qya unit.

Metavolcanic Rocks (Kmv)

As described by Todd (2004), these rocks consist of amphibolite-facies tuff, tuffbreccia and volcanic flow rock of andesitic, dacitic and basaltic composition of early Cretaceous age. Also includes rare feldspathic metaquartzite, pelitic schist and granitoid-cobble metaconglomerate. Typically forms screens between and within plutons in the western part of the El Cajon quadrangle. These rocks form a more subdued topography along the southern boundary of the proposed excavation area, are exposed in rock cuts along El Monte Road and stand at very steep to vertical angles where cut. Clasts of this unit were observed as sub-rounded to angular clasts in the Qya unit and include boulder of angular breccia in a finer groundmass.

Chiquito Peak Monzogranite (Kcp)

As described by Todd (2004), these rocks consist of hornblende-biotite monzogranite and granodiorite and lesser tonalite, leucogranite, alaskite and pegmatite of early Cretaceous age. Forms lenticular plutons and narrow, sheet-like bodies. Medium grained; moderately to strongly foliated. Variable from one body to another; partly dependent on lithology of nearby units. These rocks are exposed in road cuts along El Monte Road at the southeastern portion of the proposed excavation area.

Consolidated Sediment

As encountered in geotechnical explorations, cemented sediments occur within the alluvial column at elevations below approximately 360 feet amsl. These materials are gray to dark gray, coarse-grained sand and silty sand with clay and gravel. The density of and clay content in these materials suggest possible weathered bedrock.

GEOLOGIC STRUCTURE:

The alluvial sediments of the San Diego River valley are anticipated to be crudely bedded and stratified due to deposition by alluvial processes. As encountered in subsurface explorations, alluvial units include thickly bedded silty sand and sand beds with gravel, and gravel lenses. Sands are locally coarse-grained where gravel content is higher. Few silt layers where encountered at intermediate and deeper depths in the borings. Individual units are anticipated to be discontinuous due to depositional processes that include channel meander, braided stream flow and variable transport energy. For slope stability, the alluvial units are anticipated to act as homogenous, relatively flat-lying layers that are not prone to slide on steep contacts or bedding planes.

FAULTING AND SEISMICITY

Regional seismic sources and historic earthquakes were assessed to determine ground motion conditions for evaluation of potential seismic effects on stability of proposed finished slopes. We calculated deterministic peak ground accelerations for the regional seismic sources. These data are presented in the following sections.

REGIONAL FAULTS:

The tectonics of Southern California are dominated by the interaction of the North American and Pacific tectonic plates, which slide past each other in transform motion. Although some motion may be accommodated by rotation of crustal blocks such as the western Transverse Ranges (Dickinson, 1996), the San Andreas fault zone is the major surface expression of the tectonic boundary and accommodates most transform slip between the Pacific and North American Plates. The Rose Canyon – Newport-Inglewood, Elsinore and other offshore transform faults also accommodate strain between the Pacific and North American plates. Recent seismic activity in the greater San Diego region includes the magnitude 7.2 El Mayor – Cucapah earthquake of April 2010. This event occurred on the Laguna Salada fault zone at an epicentral distance of 165 kilometers (102 miles) from the site and was felt over a wide region.

Rose Canyon Fault Zone

The coastal San Diego region is traversed by a broad zone of faulting associated with the Rose Canyon fault zone (RCFZ), a system of faults that accommodates motion between the Pacific and North American tectonic plates. The RCFZ is considered a southern extension of the offshore Newport-Inglewood fault zone. North of downtown San Diego, the RCFZ diverges southward into three named strands—the Coronado, Silver Strand and Spanish Bight faults. The RCFZ is located approximately 30 kilometers (19 miles) southwest of the site.

Elsinore Fault Zone

The Julian segment of the Elsinore fault zone is located about 37 kilometers (23 miles) northeast of the site. The Elsinore fault zone is typified by multiple en echelon and diverging faults. To the north, the Elsinore zone splays into the Whittier and Chino faults. The Elsinore is primarily a strike-slip fault zone; however, transtentional features such as the graben of the Elsinore and Temecula Valleys also occur. Most Elsinore fault traces are demonstrably active (Holocene) as documented by Saul (1978), Rockwell and others (1986) and Wills (1988).

Coronado Bank Fault Zone

The Coronado Bank fault is located approximately 55 kilometers (35 miles) southwest of the site in the offshore region of San Diego. The Coronado Bank fault zone is a system of strike-slip and normal fault that trends north-northwest in the offshore region. The fault trend is reflected in alignment of bathymetric features including the Coronado Escarpment, Lasuen Knoll, and connection with the Palos Verdes fault zone is postulated.

San Jacinto Fault Zone

The Borrego segment of the San Jacinto fault zone (SJFZ) is located approximately 70 kilometers (43 miles) northeast of the site. The SJFZ is a system of northwest-trending, right-lateral, strike-slip faults that roughly parallels the trend of the southern San Andrea fault zone. More large historic earthquakes have occurred on the San Jacinto fault than any other fault in Southern California (Working Group on California Earthquake Probabilities, 1988).

REGIONAL SEISMICITY:

A map of recorded earthquake epicenters is included as Enclosure A-5 (Epi Software, 2000). The epicenters and magnitudes are based on data from the California Institute of Technology - Southern California Earthquake Data Center catalog. This enclosure presents circles as epicenters of earthquakes with magnitude equal to or greater than magnitude 4.0 recorded from 1932 through 2012.

The most significant fault with regard to generation of ground shaking is the Rose Canyon zone, about 30 kilometers (19 miles) to the southwest.

GROUND-SHAKING HAZARD

The ground-shaking hazard at the site was evaluated from a deterministic standpoint for use as a guide to formulate an appropriate seismic coefficient for use in slope stability analyses.

A deterministic evaluation of seismic hazard was performed for the Rose Canyon fault and other regional faults using the attenuation relations of Boore and Atkinson (2008), Campbell and Bozorgnia (2008) and Chiou and Youngs (2008). The deterministic evaluation considers the magnitude, distance and attenuation characteristics of the site based on soil conditions. These data are summarized in the following table.

Table 1: Summary of Seismic Sources

Fault Name	Distance (kilometers)	Direction	Magnitude	PGA (g)
Rose Canyon	30	SW	6.9	0.14
Elsinore (Julian)	37	NE	7.6	0.16
Coronado Bank	53	SW	7.4	0.11
San Jacinto (Borrego)	72	NE	7.4	0.09

We utilized $K_h = 0.12$ to model the psuedostatic condition for slope stability calculations, consistent with conservative application of methods described by Seed (1979). Seed (1979) considered the size of a sliding mass and earthquake magnitude in selection of K_h. For large slopes, Seed suggested $K_h = 0.15$ for sites near faults capable of generating magnitude 8.5 earthquakes. The closest fault to

the site, the Rose Canyon fault, is assigned a characteristic magnitude of 6.9. Based on the method of Seed (1979), selection of $K_h = 0.12$ is conservative based on the seismic setting of the site.

GROUNDWATER

The site is located in the San Diego River Valley groundwater basin and is underlain by an alluvial aquifer with variable recharge based on seasonal climatic conditions. Groundwater data compiled by State of California Department of Water Resources (2015) for Helix Water District observation well HWD-2 are summarized in the following table. This well is located in the north-central portion of the future excavation area.

Table 2.1: Summary of Water Level Data – HWD-2

Date of Measurement	Reference Point Elevation (feet amsl)	Water Surface Elevation (feet amsl)	Depth to Water at Well (feet bgs)
4/27/2012	447.24	414.61	32.63
10/9/2012		414.81	32.43
4/24/2013		414.62	33.62
6/6/2014		410.98	36.26
10/17/2014		409.74	34.50

Groundwater data from exploratory borings and monitoring wells that encountered groundwater utilized for site investigations is summarized in the following table.

Table 2.2: Summary of Groundwater Data from Explorations and Monitoring Wells			
Data ID	**Reference Point Elevation (feet amsl)**	**Water Surface Elevation (feet amsl)**	**Depth to Water at Well (feet bgs)**
CHJ (2015)			
B-1	435	394.9	40.1
B-2	440	397.7	42.3
B-3	448	405.7	42.3
B-4	443	406.3	36.7
Ninyo & Moore (2011)			
B-2	438	397	41
B-3	440	401	39
B-4	442	407	35
B-5	450	407	43
B-6	455	420	35
B-7	453	423	30
B-8	456	416	40
B-9	460	425	35
B-10	475	431	44
B-15	436	391	45
B-19	444	409	35
B-23	455	420	35
B-24	453	413	40
B-26	469	424	45
Shepardson (2003)			
B-7	465	444	21
B-8	455	440	15
B-9	457	434	23
B-10	455	436	19
B-11	453	434.4	18.6
B-12	449	432.2	16.8
B-14	447	428.2	18.8
B-16	447	418.8	28.2
EarthTech (1998)			
MW-1	450	435	15
MW-2	465	446	19
MW-5	458	445	13
MW-6	450	440	10

The water surface elevation (WSE) encountered in Boring No. 1 (current investigation) is consistent with the WSE (depicted on the topographic contour map dated April 21, 2013) in the existing pit adjacent to the western boundary of the site. The quarry bottom is planned at elevations between 394 and 434 feet amsl at the west and east ends, respectively. Surface water is not anticipated to occur in the final pit except during times of high flow in the San Diego River. Water elevation in the subsurface mimics the surface topography so that depth to water is relatively consistent along the river axis through the excavation area. For evaluation of liquefaction effects and slope stability, we have utilized a water surface elevation at 420 feet amsl based on an anticipated high groundwater surface and in consideration of potential flooding events.

SLOPE STABILITY

The term "landslide", as used in this report, refers to deep-seated slope failures that involve mine pit-scale features that have the potential to reduce the long-term stability of finished quarry reclamation slopes. Surficial failures refer to shallow failures within approximately 4 feet of the surface that may result in localized raveling of soil material.

The susceptibility of a geologic unit to landsliding is dependent upon various factors, primarily: 1) the presence and orientation of weak structures, such as fractures, faults or clay beds and degree of cementation of the material; 2) the height and steepness of the natural or cut slope; 3) the presence and quantity of groundwater and 4) the occurrence of strong seismic shaking. The primary influences on the stability of mine and reclaimed slopes are anticipated to be slope geometry and material strengths of native alluvial and planned fill units.

SLOPE STABILITY EVALUATION

We evaluated the global slope and surficial stability of the proposed slopes for representative material types. Material strength properties for stability calculations were modeled using Mohr-Coulomb criteria and the ultimate mining depth (tallest slopes) anticipated for the mine pit and reclaimed

geometries. We analyzed the reclamation configuration. Discussion and summary of these analyses are presented below. Slope stability data and calculations are presented in Appendix D.

GLOBAL STABILITY CALCULATIONS:

The global stability of future reclamation slopes, as depicted on the Mining and Reclamation Plan, was analyzed using Spencer's method under both static and seismic conditions for rotational and composite failure surfaces using the SLIDE computer program, version 6.038 (Rocscience, Inc., 2016). The materials strengths of the fill and native sedimentary units were determined by laboratory tests using samples from the current borings.

A representative slope, derived from the Mining and Reclamation Plan, was modeled as follows:

- 30-foot-high benched mine slope, cut into alluvium consisting of a 10-foot upper section and 20-foot lower section separated by a 20-foot-wide bench.

The seismic stability calculations were performed using a lateral pseudostatic coefficient "K_h" of 0.12, based on a very conservative interpretation of regional seismic conditions. Groundwater was not considered in the global stability evaluation as excavations will remain above the groundwater table.

Laboratory tests of samples collected from borings included sieve analysis and direct shear of relatively undisturbed samples and one remolded sample. The results of direct shear tests are summarized below and are based on saturated conditions.

Table 3: El Monte Sand Project—Shear Test Summary				
Sample	**Cohesion (psf)**		**ϕ (degrees)**	
	Peak	**Residual**	**Peak**	**Residual**
B-1 at 20 Feet (SP-SM)	134.0	57.5	36.8	33.6
B-1 at 90 Feet (SM)	362.2	229.9	40.7	36.2
B-2 at 45 Feet (SP-SM)	198.7	144.4	32.9	30.2
B-2 at 60 Feet (SM)	245.1	107.4	31.7	29.9
B-3 at 40 Feet (silt remolded to 80%)	214.2	250.0	29.8	28.1
B-4 at 15 Feet (SM)	117.0	108.6	30.0	30.1

The strength of sand and silty sand units in the Qya was taken as the average of the five results from Boring Nos. 1, 2 and 4 (residual cohesion = 129; residual ϕ = 32°). The silt sub-unit of Qya, represented by the sample from Boring No. 3, was modeled with cohesion = 220 pounds per square foot (psf); residual ϕ = 28°. Laboratory test results are included in Appendix C.

Bedrock units were not included in the model as mining is anticipated to terminate above the bedrock surface. Bedrock units under global stability conditions would exhibit infinite strength relative to alluvial and fill units.

The results of the global slope stability analyses are summarized below in Table 4. Details of stability calculations including material type boundaries, strength parameters and the minimum factor of safety and critical slip surface are included in Enclosures D-1.1 through D-1.3.

Table 4: Summary of Slope Stability Results—El Monte Sand Project			
Slope Configuration	**Static F.S.**	**Seismic F.S. (K_h=0.12)**	**Enclosure**
30-foot-High Cut Slope with 20-Foot-Wide Bench Separating Upper 3(h) to 1(v) and Lower 3(h):1(v) Sections	2.43	--	D-1.1
	--	1.73	D-1.2
Flooded Condition at 420 Feet Elevation	--	1.44	D-1.3

SURFICIAL STABILITY CALCULATIONS:

Surficial stability of reclamation slopes was modeled using the infinite slope model method as presented in Enclosure D-2. This model uses a saturated zone 4 feet thick extending downward from the slope surface. The factor of safety estimated by this model is 1.63.

SLOPE STABILITY CONCLUSIONS:

As indicated by calculation for global stability, a static factor of safety in excess of 1.5 and seismic factor of safety in excess of 1.1 were indicated for the modeled reclaimed slope configuration and satisfy Office of Mine Reclamation and County of San Diego criteria. The global slope configurations appear suitably stable for mining and reclamation of the proposed slopes according to regulatory requirements.

The surficial stability model indicates a suitably stable configuration for the proposed end use of the reclaimed mine slopes as open space. The proposed pit configuration and lack of structures within the future reclaimed pit preclude the potential for erosion or raveling to affect adjacent property or on-site improvements.

LIQUEFACTION POTENTIAL AND SEISMIC SETTLEMENT

Based on the groundwater, soil and seismic conditions of the site, the potential for liquefaction was evaluated. Liquefaction is a process in which strong ground shaking causes saturated soils to lose their strength and behave as a fluid (Matti and Carson, 1991). Ground failure associated with liquefaction can result in severe damage to structures. Soil types susceptible to liquefaction include sand, silty sand, sandy silt and silt, as well as soils having a plasticity index (PI) less than 7 (Boulanger and Idriss, 2006). Loose soils with a PI less than 12 and moisture content greater than 85 percent of the liquid limit are also susceptible to liquefaction (Bray and Sancio, 2006). For sandy soils, the geologic conditions for increased susceptibility to liquefaction are: 1) shallow groundwater (generally less than 50 feet in depth), 2) the presence of unconsolidated sandy alluvium, typically Holocene in age, and 3) strong ground shaking of sufficient duration. All three of these conditions must be present for liquefaction to occur.

Due to the potential for the presence of shallow groundwater beneath the site (34 feet), the liquefaction potential of site soils has been evaluated based on the SPT data obtained and using the simplified procedure described by Seed and Idriss (1982), Seed and others (1985), modified in the 1996 National Center for Earthquake Engineering Research (NCEER) and 1998 NCEER/National Science Foundation (NSF) workshops (Youd and Idriss, 2001) and recently summarized by Idriss and Boulanger (2008). The method of evaluating liquefaction potential consists of comparing the cyclic stress ratio (CSR) developed in the soil by the earthquake motion to cyclic resistance ratio (CRR), which will cause liquefaction of the soil for a given number of cycles. In the simplified procedure, the CSR developed in the soil is calculated from a formula that incorporates ground surface acceleration, total and effective stresses in the soil at different depths (which in turn are related to the location of the groundwater table), non-rigidity of the soil column and a number of simplifying assumptions.

For sandy soils, the CRR that will cause liquefaction is related to the relative density of the soil, expressed in terms of SPT blowcounts $(N_1)_{60}$ (Seed and Idriss, 1982; Seed and others, 1985; Youd and Idriss, 2001; Idriss and Boulanger, 2008), cone penetration resistance (q_{c1N}) (Robertson and Wride, 1998; Youd and Idriss, 2001; Idriss and Boulanger, 2008) or shear wave velocity (V_{s1}) (Andrus and Stokoe, 2000; Youd and Idriss, 2001; Andrus and others, 2004), all normalized for an effective overburden pressure of 1 ton per square foot and corrected to equivalent clean sand resistance. For clayey soils, the CRR is related to cyclic undrained shear strength ratio, s_u/σ_{vc}' (Idriss and Boulanger, 2008). For this investigation, SPT blowcounts were obtained and utilized in the analysis. A projected future depth to groundwater of 34 feet below the existing ground surface (bgs) was utilized to calculate the liquefaction potential in the area. A peak ground acceleration of 0.35g (geomean MCE level consistent with 2013 CBC) and a deaggregated earthquake magnitude of 6.2 were utilized as input into the liquefaction analysis program GeoSuite©, version 2.4 (Yi, 2015).

The procedures and corrections summarized by Idriss and Boulanger (2008) were utilized to evaluate the liquefaction potential of saturated sandy soils for SPT data. These methods were incorporated into a liquefaction and seismic settlement program, GeoSuite©, version 2.4 (Yi, 2015).

Liquefaction potential was evaluated for the soil profile encountered in Boring No. 3 with the SPT sampler. The results of liquefaction potential evaluations are shown in Enclosure E-1. Our calculation indicates that liquefaction could occur in layers at depths ranging from approximately 40 to 45 feet bgs and from approximately 70 to 75 feet bgs based on SPT data.

Ishihara (1985) published a paper containing observations on the protective effect that an upper layer of non-liquefied material had against the manifestation of liquefaction at the ground surface. The paper contained graphs that plotted thickness of the upper non-liquefied layer (H_1) and the thickness of underlying liquefied material (H_2). The maximum acceleration is 400 to 500 gal in Ishihara's graph. The term "surface manifestation" is utilized to describe liquefaction-induced surface damage.

A quantitative method using an index called the liquefaction potential index (LPI) was developed and presented by Iwasaki (1978, 1982). The LPI is defined as:

$$LPI = \int_0^{20} F_1 W(z) dz$$

where $W(z) = 10 - 0.5z$, $F_1 = 1 - FS$ for $FS < 1.0$, $F_1 = 0$ for $FS > 1.0$ and z is the depth below the ground surface in meters. The LPI presents the risk of liquefaction damage as a single value with the following indicators of liquefaction-induced damage:

Table 5: LPI Range and Damage

LPI Range	Damage
LPI = 0	Liquefaction risk is very low.
0 < LPI ≤ 5	Liquefaction risk is low.
5 < LPI ≤ 15	Liquefaction risk is high.
LPI > 15	Liquefaction risk is very high.

The most recent development for quantitative descriptions of liquefaction-induced surface damage, called "liquefaction vulnerability", was made by Tonlin & Taylor (2013) after the Christchurch, New Zealand earthquakes occurred between 2010 and 2011 and is based on field observations and analyses of approximately 7,500 cone penetrometer test (CPT) investigations. A new index, the liquefaction severity number (LSN), was proposed and defined as:

$$LSN = \int \frac{\varepsilon_v}{z} dz$$

where ε_v is the calculated volumetric densification strain in the subject layer from Zhang et al. (2002) and z is the depth to the layer of interest in meters below the ground surface. The typical behaviors of sites with a given LSN are summarized in following table.

Table 6: LSN Ranges and Observed Land Effects

LSN Range	Predominant Performance
0 – 10	Little to no expression of liquefaction, minor effects
10 – 20	Minor expression of liquefaction, some sand boils
20 – 30	Moderate expression of liquefaction, with sand boils and some structural damage
30 – 40	Moderate to severe expression of liquefaction, settlement can cause structural damage
40 – 50	Major expression of liquefaction, undulations and damage to ground surface, severe total and differential settlement of structures
>50	Severe damage, extensive evidence of liquefaction at surface, severe total and differential settlements affecting structures, damage to services

Both LPI and LSN indices were calculated. The results indicate that the liquefaction risk of the site is low as per the LPI index. The site exhibits little to minor expression of liquefaction as per the LSN index. A minor expression of liquefaction means that some sand boils may occur during or after earthquake shaking per Tonlin & Taylor (2013).

CONCLUSIONS

On the basis of our field investigation and slope stability analyses, it is the opinion of this firm that the proposed slope excavations and reclamation of the proposed mine slopes are feasible from geotechnical engineering and engineering geologic standpoints, provided the recommendations contained in this report are implemented during mining.

In general, it appears that the strength of the alluvial resource is sufficient to accommodate the proposed overall slope angles under static and seismic conditions. Transient flooding of the working pit is not anticipated to destabilize slopes cut to 3(h) to 1(v) or flatter.

Based on our analyses, the proposed overall reclamation slope configuration is suitably stable against gross failure for the anticipated long-term conditions, including the effects of seismic shaking and a flooded pit.

Adherence to an approved slope excavation plan and consideration/mitigation of newly exposed potentially adverse geologic features (if present) during mining can result in stable slopes after completion of reclamation.

Evidence of active faulting was not observed on the site during this investigation. The results of liquefaction analysis indicate that the risk of liquefaction effects to the proposed site end use/improvements is low.

Moderate seismic shaking of the site can be expected to occur during the lifetime of the proposed mining and reclamation. This potential has been considered in our analyses and evaluation of slope stability.

With time, natural processes during and after quarry operation will result in deposition of soil on benches and shallow slopes. This material can facilitate revegetation and lend a more natural appearance to the reclaimed slopes.

RECOMMENDATIONS

Overall final cut slopes in soil/alluvial materials should be no steeper than approximately 18-1/2 degrees [3(h) to 1(v)] up to the maximum proposed height (approximately 30 feet). The benching plan appears to be suitable for mining and reclamation.

Geotechnical evaluation and design, management of mine slope and bench geometry based on encountered conditions, or use of mechanical support systems can enhance the safety of or mitigate hazards in mining; however, monitoring of slope conditions for failure warning signs is the most important means for protecting mine workers (Girard and McHugh, 2000) as it can prevent exposure of personnel to potentially hazardous conditions. As is typical for any surface mining operation, we recommend periodic observation of mine benches above working areas for indications of potential instability during mine operations.

COMPACTED FILLS:

If engineered fills are needed, the on-site soils and sand production by products should provide adequate quality fill material provided they are free from organic matter and other deleterious materials. Fill should be inorganic, non-expansive granular soils.

Fill should be spread in near-horizontal layers, approximately 8 inches thick. Thicker lifts may be approved by the geotechnical engineer if testing indicates that the grading procedures are adequate to

achieve the required compaction. Each lift should be spread evenly, thoroughly mixed during spreading to attain uniformity of the material and moisture in each layer, brought to near optimum moisture content and compacted to a minimum relative compaction of 90 percent in accordance with ASTM D1557.

FILL SLOPE CONSTRUCTION:

Fill slopes should be constructed no steeper than 2(h):1(v). Fill slopes should be overfilled during construction and then cut back to expose fully compacted soil. A suitable alternative would be to compact the slopes during construction and then roll the final slopes to provide dense, erosion-resistant surfaces.

SLOPE PROTECTION:

Inasmuch as the native materials are susceptible to erosion by wind and running water, it is our recommendation that project slopes be protected from erosion by establishment of vegetation as soon as possible.

Slopes should be protected with drainage improvements such as berms and/or levees as necessary to prevent slope erosion.

LIMITATIONS

CHJ Consultants has striven to perform our services within the limits prescribed by our client, and in a manner consistent with the usual thoroughness and competence of reputable geotechnical engineers and engineering geologists practicing under similar circumstances. No other representation, express or implied, and no warranty or guarantee is included or intended by virtue of the services performed or reports, opinion, documents, or otherwise supplied.

This report reflects the testing conducted on the site as the site existed during the study, which is the subject of this report. However, changes in the conditions of a property can occur with the passage of time, due to natural processes or the works of man on this or adjacent properties. Changes in applicable or appropriate standards may also occur whether as a result of legislation, application, or the broadening of knowledge. Therefore, this report is indicative of only those conditions tested at the time of the subject study, and the findings of this report may be invalidated fully or partially by changes outside of the control of CHJ Consultants. This report is therefore subject to review and should not be relied upon after a period of one year.

The conclusions and recommendations in this report are based upon observations performed and data collected at separate locations, and interpolation between these locations, carried out for the project and the scope of services described. It is assumed and expected that the conditions between locations observed and/or sampled are similar to those encountered at the individual locations where observation and sampling was performed. However, conditions between these locations may vary significantly. Should conditions that appear different than those described herein be encountered in the field by the client, any firm performing services for the client or the client's assign, this firm should be contacted immediately in order that we might evaluate their effect.

If this report or portions thereof are provided to contractors or included in specifications, it should be understood by all parties that they are provided for information only and should be used as such.

The report and its contents resulting from this study are not intended or represented to be suitable for reuse on extensions or modifications of the project, or for use on any other project.

CLOSURE

We appreciate this opportunity to be of service and trust this report provides the information desired at this time. Should questions arise, please do not hesitate to contact this office.

Respectfully submitted,
CHJ CONSULTANTS

John S. McKeown, E.G. 2396
Project Geologist

Fred Yi, Ph.D., G.E. 2967
Chief Engineer

Jay J. Martin, E.G. 1529
Vice President

JSM/FY/JJM:lb

REFERENCES

Boore, D. M., and G. M. Atkinson, 2008, Ground-motion prediction equations for the average horizontal component of PGA, PGV, and 5%-damped PSA at spectral periods between 0.01s and 10.0s, Earthquake Spectra, Vol. 24, No. 1, p. 99-138.

California Department of Water Resources, 2015, water well data at web site http://wdl.water.ca.gov/gw.

Campbell, K. W., and Y Bozorgnia, 2008, NGA ground motion model for the geometric mean horizontal component of PGA, PGV, PGD and 5% damped linear elastic response spectra for periods ranging from 0.01 to 10 s, Earthquake Spectra, Vol. 24, No. 1, p. 139-171.

Chiou, B. S. J., and Youngs, R. R., 2008, Chiou-Youngs, NGA ground motion relations for the geometric mean horizontal component of peak and spectral ground motion parameters, Earthquake Spectra, v. 24, no 1 , pp. 173-215.

CHJ Incorporated, 2015, Slope Stability Investigation, Proposed El Monte Sand Mine and Nature Preserve Project, Lakeside, California, prepared for El Monte Nature Preserve, LLC, Job No. 15383-8.

Dickinson, W. R., 1996, Kinematics of transrotational tectonism in the California Transverse Ranges and its contribution to cumulative slip along the San Andreas transform fault system: Geological Society of America Special Paper 305, pp. 1-46.

Epi Software, 2000, Epicenter Plotting Program, compiled by Wes Reeder.

Ninyo & Moore, 2011, Preliminary Geotechnical Evaluation, El Monte Mining, Reclamation and Groundwater Recharge Project, dated July 18, 2011.

Petersen, Mark D., Frankel, Arthur D., Harmsen, Stephen C., Mueller, Charles S., Haller, Kathleen M., Wheeler, Russell L., Wesson, Robert L., Zeng, Yuehua, Boyd, Oliver S., Perkins, David M., Luco, Nicolas, Field, Edward H., Wills, Chris J., and Rukstales, Kenneth S., 2008, Documentation for the 2008 Update of the United States National Seismic Hazard Maps: U.S. Geological Survey Open-File Report 2008–1128, 61 p.

Rockwell, T. K., McElwain, R. S., Millman, D. E., and Lamar, D. L., 1986, Recurrent late Holocene faulting on the Glen Ivy North strand of the Elsinore fault at Glen Ivy marsh, in Ehlig, P. L., ed., Neotectonics and faulting in southern California: Geological Society of America, 82nd Annual Meeting of the Cordilleran Section, Guidebook and Volume, p. 167-175.

REFERENCES

Rocscience, Inc., 2015, SLIDE computer software program, ver. 6.036: 2D Limit equilibrium slope stability for soil and rock slopes.

Saul, R., 1978, Elsinore Fault Zone (South Riverside County Segment) with Description of the Murrieta Hot Springs Fault: California Division of Mines and Geology Fault Evaluation Report 76.

Seed, H. B., 1979, "Considerations in the Earthquake-Resistant Design of Earth and Rockfill Dams", Geotechnique, v. 29, no. 3, pp. 215-263.

Shepardson Engineering Associates, Inc., 2003, Compendium Report of Geotechnical Investigations, El Capital Golf Course, Lakeside, California, dated July 28, 2003.

Tan, Siang S., 2002, Geologic Map of the San Vicente Reservoir 7.5-minute quadrangle, San Diego County, California: a digital database, California Geological Survey, ftp://ftp.consrv.ca.gov/pub/dmg/rgmp/Prelim_geo_pdf/san_vicente_layout_highres.pdf.

Todd, V. R., 2004, Preliminary Geologic Map of the El Cajon 30' x 60' quadrangle, southern California, U.S. Geological Survey Open-File Report 2004-1361.

Wills, C. J., 1988, Ground Cracks in Wolf and Temecula Valleys, Riverside County: California Division of Mines and Geology Fault Evaluation Report 195.

Working Group on California Earthquake Probabilities, 1988, Probabilities of large earthquakes occurring in California on the San Andreas fault: U.S. Geological Survey Open-File Report 88-398.

AERIAL PHOTOGRAPHS EXAMINED

Google Earth software application, 2015, aerial photographs dated May 30, 1994; June 3, 1996; Ma 27, 2002; December 31, 2002; February 11, 2004; January 11, 2005; May 15, 2005; January 31, 2006; April 24, 2010; November 13, 2011; October 27, 2012; and January 57, 2015.

NETROLine Historical Aerial Imagery web-based software application, accessed September 2015; imagery dated 1953, 1964, 1966, 1968, 1971, 1980, 1981, 1989 and 1994.

APPENDIX A

MAPS AND CROSS SECTIONS

DRAFT



LOCATION MAP

FOR: EL MONTE NATURE PRESERVE, LLC	SLOPE STABILITY INVESTIGATION PROPOSED EL MONTE SAND MINE AND NATURE PRESERVE PROJECT LAKESIDE, CALIFORNIA	ENCLOSURE "A-1"
DATE: JANUARY 2016		JOB NUMBER 15383-8
		CHJ Consultants

LEGEND:

B-4
(407) — Exploratory Boring (Current Investigation)
Highest measured groundwater elevation (feet)

B-21
(407) — Exploration by Ninyo Moore, 2011
Highest measured groundwater elevation (feet)

B-24
(407) — Exploration by Shepardson, 2003
Highest measured groundwater elevation (feet)

MW-6
(407) — Monitoring Well by Earth Tech, 1998
Highest measured groundwater elevation (feet)



SITE PLAN

FOR: EL MONTE NATURE PRESERVE, LLC	SLOPE STABILITY INVESTIGATION PROPOSED EL MONTE SAND MINE AND NATURE PRESERVE PROJECT LAKESIDE, CALIFORNIA	ENCLOSURE "A-2"
DATE: JANUARY 2016		JOB NUMBER 15383-8

CHJ Consultants



(Base Map: Todd, 2004)

GEOLOGIC UNITS:

Qya - young alluvium
Kcp - Chiquito Peak monzogranite
Kjv - Japatul Valley tonalite
Ka - Tonalite of Alpine
Kgr - granitoid rocks
Kmv - metavolcanic rocks

geologic contact

DRAFT

N

SCALE: 1" = 4000'

GEOLOGIC INDEX MAP

FOR: EL MONTE NATURE PRESERVE, LLC	SLOPE STABILITY INVESTIGATION PROPOSED EL MONTE SAND MINE AND NATURE PRESERVE PROJECT LAKESIDE, CALIFORNIA	ENCLOSURE "A-3"
DATE: JANUARY 2016		JOB NUMBER 15383-8

CHJ Consultants

GEOLOGIC UNITS:

f - fill - Fill associated with prior site use as a borrow area, dirt roads/ tracks, pond/river channel embankments, and golf course development derived from local materials including sand, silt and gravel from young alluvium and topsoil.

Qw - active wash deposits of San Diego River Channel. Primarily medium-to coarse-grained sand with fine-grained sand, silt and gravel. Poorly consolidated.

Qya - young alluvium of San Diego River Valley. Includes sand, silt and gravel derived from granitic and metavolcanic sources of adjacent highlands. Surface locally mantled with brownish-gray micaceous sandy silt. Forms geomorphic bench elevated relative to river channel sediments.

Qoa - older alluvium of isolated terrace. Reddish-brown silty sand with gravel and cobbles forming terrace remnant elevated above Qya surface. Locally with fill and debris along southern margin.

Kmv - metavolcanic bedrock

Kgr - granitic bedrock

Kcp - Chiquito Peak monzogranite

LEGEND:

- B-4 — Exploratory Boring (Current Investigation)
- B-21 — Exploration by Ninyo Moore, 2011
- B-24 — Exploration by Shepardson, 2003
- MW-6 — Monitoring Well by Earth Tech, 1998
- Geologic Contact
- C C' — Geologic Cross Section
- Excavation Area Boundary



N

SCALE: 1" = 300'

0 300 600

GEOLOGIC MAP AND SITE PLAN

FOR: EL MONTE NATURE PRESERVE, LLC	SLOPE STABILITY INVESTIGATION PROPOSED EL MONTE SAND MINE AND NATURE PRESERVE PROJECT LAKESIDE, CALIFORNIA	ENCLOSURE "A-4.1"
DATE: JANUARY 2016		JOB NUMBER 15383-8

CHJ Consultants



DRAFT

ELEVATION OF GROUNDWATER IN BORING

NOTE: SECTION USES VERTICAL EXAGGERATION AT 2.5X

SCALE: V = 40'
H = 100'

GEOLOGIC CROSS SECTION A-A'

FOR: EL MONTE NATURE PRESERVE, LLC	SLOPE STABILITY INVESTIGATION PROPOSED EL MONTE SAND MINE AND NATURE PRESERVE 13964 EL MONTE ROAD LAKESIDE, CALIFORNIA	ENCLOSURE "A-4.2"
DATE: JANUARY 2016		JOB NUMBER 15383-8

CHJ Consultants



DRAFT

ELEVATION OF GROUNDWATER IN BORING

NOTE: SECTION USES VERTICAL EXAGGERATION AT 2.5X

SCALE: V = 40'
H = 100'

GEOLOGIC CROSS SECTION B-B'

FOR: EL MONTE NATURE PRESERVE, LLC	SLOPE STABILITY INVESTIGATION PROPOSED EL MONTE SAND MINE AND NATURE PRESERVE 13964 EL MONTE ROAD LAKESIDE, CALIFORNIA	ENCLOSURE "A-4.3"
DATE: JANUARY 2016		JOB NUMBER 15383-8

CHJ Consultants

C



C'



ELEVATION OF GROUNDWATER IN BORING

NOTE: SECTION USES VERTICAL EXAGGERATION AT 2.5X

SCALE: V = 40'
H = 100'

GEOLOGIC CROSS SECTION C-C'

FOR: EL MONTE NATURE PRESERVE, LLC	SLOPE STABILITY INVESTIGATION PROPOSED EL MONTE SAND MINE AND NATURE PRESERVE 13964 EL MONTE ROAD LAKESIDE, CALIFORNIA	ENCLOSURE "A-4.4"
DATE: JANUARY 2016		JOB NUMBER 15383-8

CHJ Consultants

DRAFT



DRAFT

SITE LOCATION: 32.8723 LAT. -116.8863 LONG.

MINIMUM LOCATION QUALITY: C

TOTAL # OF EVENTS ON PLOT: 1373

TOTAL # OF EVENTS WITHIN SEARCH RADIUS: 310

MAGNITUDE DISTRIBUTION OF SEARCH RADIUS EVENTS:

4.0- 4.9 : 283
5.0- 5.9 : 22
6.0- 6.9 : 5
7.0- 7.9 : 0
8.0- 8.9 : 0

0 50 100
KILOMETERS

CLOSEST EVENT: 4.2 ON WEDNESDAY, DECEMBER 04, 1991 LOCATED APPROX. 23 KILOMETERS NORTH OF THE SITE

LARGEST 5 EVENTS:

6.6 ON TUESDAY, NOVEMBER 24, 1987 LOCATED APPROX. 97 KILOMETERS EAST OF THE SITE
6.6 ON WEDNESDAY, OCTOBER 21, 1942 LOCATED APPROX. 83 KILOMETERS EAST OF THE SITE
6.5 ON TUESDAY, APRIL 09, 1968 LOCATED APPROX. 78 KILOMETERS NORTHEAST OF THE SITE
6.4 ON FRIDAY, MARCH 19, 1954 LOCATED APPROX. 79 KILOMETERS NORTHEAST OF THE SITE
6.0 ON THURSDAY, MARCH 25, 1937 LOCATED APPROX. 83 KILOMETERS NORTHEAST OF THE SITE

EARTHQUAKE EPICENTER MAP

FOR: EL MONTE NATURE PRESERVE, LLC	SLOPE STABILITY INVESTIGATION PROPOSED EL MONTE SAND MINE AND NATURE PRESERVE PROJECT LAKESIDE, CALIFORNIA	ENCLOSURE "A-5"
DATE: JANUARY 2016		JOB NUMBER 15383-8

CHJ Consultants

APPENDIX B

BORING LOGS

DRAFT

EXPLORATORY BORING NO. 1

Date Drilled: 8/17/15 Client: El Monte NP

Equipment: CME75 Truck Rig Driving Weight / Drop / Sampler Size: 140lbs./30in./3.0" O.D.

Surface Elevation(ft): 435 Logged by: VJR Measured Depth to Water(ft): 40.1

DEPTH (ft)	GRAPHIC LOG	VISUAL CLASSIFICATION	REMARKS	SAMPLES DRIVE	SAMPLES BULK	BLOWS/6 IN.	FIELD MOISTURE (%)	DRY UNIT WT. (pcf)	LAB/FIELD TESTS
		(SM) Silty Sand, fine to medium, few gravel to 2", dark brown	Native	X		8 8 8	2.4	Dist.	Ring
					▨		2.5		
		(SP-SM) Sand, fine to coarse, with silt and gravel to 2", dark brown	Auger Chatter	X		11 19 22	1.2	Dist.	Ring
5					▨		2.6		SA
10				X		7 9 14	2.5	117	Ring
15				X		6 10 14	4.5	104	Ring
20				X		11 11 15	2.1	108	DS, Ring
25		(SM) Silty Sand, fine to medium, dark grayish brown		X		3 7 13	8.0 23.9	117	Ring
30		(SP-SM) Sand, fine to coarse, with silt and few gravel to 1/2", light brownish gray	Iron Oxide Staining	X		6 11 15	2.8 4.1	106	Ring

DRAFT

10331-3 15383-8.GPJ CHJ.GDT 9/10/15

CHJ

SLOPE STABILITY INVESTIGATION
13964 EL MONTE ROAD, LAKESIDE, CALIFORNIA

Job No. 15383-8 Enclosure B-1a

EXPLORATORY BORING NO. 1

Date Drilled: 8/17/15 Client: El Monte NP

Equipment: CME75 Truck Rig Driving Weight / Drop / Sampler Size: 140lbs./30in./3.0" O.D.

Surface Elevation(ft): 435 Logged by: VJR Measured Depth to Water(ft): 40.1

DEPTH (ft)	GRAPHIC LOG	VISUAL CLASSIFICATION	REMARKS	SAMPLES DRIVE	SAMPLES BULK	BLOWS/6 IN.	FIELD MOISTURE (%)	DRY UNIT WT. (pcf)	LAB/FIELD TESTS
		(SP-SM) Sand, fine to coarse, with silt and few gravel to 1/2", light brownish gray		X		9 14 16	4.1	107	Ring
40		(SM) Silty Sand, fine to medium with coarse, grayish brown	▼ Groundwater	X		8 11 16	23.0 28.7	103	Ring
45			Sand Plug	X		5 6 9	25.7	97	Ring
50				X		4 9 21	24.7	99	Ring
55		(SP-SM) Sand, fine to coarse, with silt and gravel to 1", dark olive gray	Sand Plug	X		5 11 14	11.9	115	Ring
60				X		8 15 28	10.5 17.4	124	Ring
65				X		12 16 21	15.4	113	Ring

DRAFT

10331-3 15383-8.GPJ CHJ.GDT 9/10/15

CHJ

SLOPE STABILITY INVESTIGATION
13964 EL MONTE ROAD, LAKESIDE, CALIFORNIA

Job No. 15383-8 Enclosure B-1b

EXPLORATORY BORING NO. 1

Date Drilled: 8/17/15 Client: El Monte NP

Equipment: CME75 Truck Rig Driving Weight / Drop / Sampler Size: 140lbs./30in./3.0" O.D.

Surface Elevation(ft): 435 Logged by: VJR Measured Depth to Water(ft): 40.1

DEPTH (ft)	GRAPHIC LOG	VISUAL CLASSIFICATION	REMARKS	SAMPLES DRIVE	SAMPLES BULK	BLOWS/6 IN.	FIELD MOISTURE (%)	DRY UNIT WT. (pcf)	LAB/FIELD TESTS
		(SP-SM) Sand, fine to coarse, with silt and gravel to 1", dark olive gray		X		6 10 16	N.R.	N.R.	Ring
75		(SM) Silty Sand, fine to medium, with gravel to 2", black	Gravel lens	X	▨	8 17 25	14.4 21.3	118	Ring
80		(SP-SM) Sand, fine to coarse, with silt and gravel to 1", dark yellowish olive		X	▨	18 23 27	9.3 10.3	149	Ring
85		(SM) Silty Sand, fine to coarse, with clay and gravel to 2", gray [Consolidated Sediment]	Very Hard drilling, chatter	X		23 50/1"	17.9	110	Ring
90				X		17 38 50/3"	18.6	116	DS, Ring
95				X		50/5"	13.5	127	Ring
100		END OF BORING AT 105.25'		X		30 50/4"	21.6	115	Ring
		NO REFUSAL, NO FILL, NO BEDROCK MODERATE CAVING IN UPPER 10' GROUNDWATER AT 40'		X		50/2"	N.R.	N.R.	Ring

DRAFT

10331-3 15383-8.GPJ CHJ.GDT 9/10/15

CHJ

SLOPE STABILITY INVESTIGATION
13964 EL MONTE ROAD, LAKESIDE, CALIFORNIA

Job No. 15383-8 Enclosure B-1c

EXPLORATORY BORING NO. 2

Date Drilled: 8/19/15 Client: El Monte NP

Equipment: CME75 Truck Rig Driving Weight / Drop / Sampler Size: 140lbs./30in./3.0" O.D.

Surface Elevation(ft): 440 Logged by: VJR Measured Depth to Water(ft): 42.3

DEPTH (ft)	GRAPHIC LOG	VISUAL CLASSIFICATION	REMARKS	SAMPLES DRIVE	SAMPLES BULK	BLOWS/6 IN.	FIELD MOISTURE (%)	DRY UNIT WT. (pcf)	LAB/FIELD TESTS
		(SM) Silty Sand, fine with medium, brown	Native	X		2 3 3	2.1	92	Ring
					▨		2.8		
5		(SP-SM) Sand, fine to coarse, with silt and gravel to 1", light olive brown		X		4 8 8	1.5	Dist.	Ring
					▨		2.0		
10				X		5 9 13	5.3	98	Ring
15				X		6 8 11	3.3	101	Ring
20		(SM) Silty Sand, fine to medIum, dark grayish brown		X		4 6 7	18.0	97	Ring
					▨		12.4		SA
25				X		4 5 8	19.7	92	Ring
30		(SP-SM) Sand, fine to coarse, with silt, light olive brown		X		7 10 17	2.7	104	Ring
					▨		2.8		

DRAFT

10331-3 15383-8.GPJ CHJ.GDT 9/10/15

CHJ

SLOPE STABILITY INVESTIGATION
13964 EL MONTE ROAD, LAKESIDE, CALIFORNIA

Job No. 15383-8

Enclosure B-2a

EXPLORATORY BORING NO. 2

Date Drilled: 8/19/15 Client: El Monte NP

Equipment: CME75 Truck Rig Driving Weight / Drop / Sampler Size: 140lbs./30in./3.0" O.D.

Surface Elevation(ft): 440 Logged by: VJR Measured Depth to Water(ft): 42.3

DEPTH (ft)	GRAPHIC LOG	VISUAL CLASSIFICATION	REMARKS	SAMPLES DRIVE	SAMPLES BULK	BLOWS/6 IN.	FIELD MOISTURE (%)	DRY UNIT WT. (pcf)	LAB/FIELD TESTS
		(SM) Silty Sand, fine to medium, few clay, olive gray		X	▨	7 9 11	11.8 12.0	88	Ring
40				X		4 7 8	33.0	88	Ring
		(SP-SM) Sand, fine to coarse, with silt and gravel to 1", dark olive gray	▼ Groundwater Auger Chatter						
45				X	▨	6 11 15	21.0 19.5	100	DS, Ring
50		(SM) Silty Sand, fine to medium, few clay, gray		X	▨	2 7 14	27.4 27.2	95	Ring
55				X		3 6 7	35.1	87	Ring
60				X		3 7 12	30.5	91	DS, Ring
65				X		6 17 28	22.0	106	Ring
		(SP-SM) Sand, fine to coarse, with silt, dark gray							

DRAFT

10331-3 15383-8.GPJ CHJ.GDT 9/10/15

CHJ

SLOPE STABILITY INVESTIGATION
13964 EL MONTE ROAD, LAKESIDE, CALIFORNIA

Job No. 15383-8 Enclosure B-2b

EXPLORATORY BORING NO. 2

Date Drilled: 8/19/15 Client: El Monte NP

Equipment: CME75 Truck Rig Driving Weight / Drop / Sampler Size: 140lbs./30in./3.0" O.D.

Surface Elevation(ft): 440 Logged by: VJR Measured Depth to Water(ft): 42.3

DEPTH (ft)	GRAPHIC LOG	VISUAL CLASSIFICATION	REMARKS	SAMPLES DRIVE	SAMPLES BULK	BLOWS/6 IN.	FIELD MOISTURE (%)	DRY UNIT WT. (pcf)	LAB/FIELD TESTS
		(SP-SM) Sand, fine to coarse, with silt, dark gray		X		7 12 18	20.9 22.0	107	Ring
75			Sand Plug	X		10 21 45	24.2	101	Ring
80				X		10 12 50/5"	13.9	123	Ring
		(SM) Silty Sand, fine to coarse, with clay and gravel to 2", gray [Consolidated Sediment]	Very Hard Drilling						
85				X		50/4"	N.R.	N.R.	Ring
					X				
90		END OF BORING		X		50/3"	N.R.	N.R.	Ring
		NO REFUSAL, NO FILL, NO BEDROCK SLIGHT CAVING IN UPPER 10' GROUNDWATER AT 42.25'							
95									
100									

DRAFT

10331-3 15383-8.GPJ CHJ.GDT 9/10/15

CHJ

SLOPE STABILITY INVESTIGATION
13964 EL MONTE ROAD, LAKESIDE, CALIFORNIA

Job No. 15383-8

Enclosure B-2c

EXPLORATORY BORING NO. 3

Date Drilled: 8/18/15 Client: El Monte NP

Equipment: CME75 Truck Rig Driving Weight / Drop / Sampler Size: 140lbs./30in./2.0" O.D.

Surface Elevation(ft): 448 Logged by: VJR Measured Depth to Water(ft): 42.3

DEPTH (ft)	GRAPHIC LOG	VISUAL CLASSIFICATION	REMARKS	SAMPLES DRIVE	SAMPLES BULK	BLOWS/6 IN.	FIELD MOISTURE (%)	DRY UNIT WT. (pcf)	LAB/FIELD TESTS
		(SM) Silty Sand, fine, brown	Native	X		5 6 5			Pass #200, SPT
					▨		2.6		
5		(SP) Sand, fine to coarse, few gravel to 1/2", dark brown		X		2 2 3			Pass #200, SPT
10				X		2 2 2			Pass #200, SPT
					▨		1.9		
15				X		1 2 3			Pass #200, SPT
20				X		4 4 3			Pass #200, SPT
25		(ML) Sandy Silt, fine with medium, dark brown		X		3 3 4			Pass #200, SPT
30		(SP-SM) Sand, fine to coarse, with silt and few gravel to 1/2", light yellowish brown		X		3 5 6			Pass #200, SPT

DRAFT

10331-3 15383-8.GPJ CHJ.GDT 9/10/15

CHJ

SLOPE STABILITY INVESTIGATION
13964 EL MONTE ROAD, LAKESIDE, CALIFORNIA

Job No. 15383-8

Enclosure B-3a

EXPLORATORY BORING NO. 3

Date Drilled: 8/18/15 Client: El Monte NP

Equipment: CME75 Truck Rig Driving Weight / Drop / Sampler Size: 140lbs./30in./2.0" O.D.

Surface Elevation(ft): 448 Logged by: VJR Measured Depth to Water(ft): 42.3

DEPTH (ft)	GRAPHIC LOG	VISUAL CLASSIFICATION	REMARKS	SAMPLES DRIVE	SAMPLES BULK	BLOWS/6 IN.	FIELD MOISTURE (%)	DRY UNIT WT. (pcf)	LAB/FIELD TESTS
		(SP) Sand, fine to coarse, few gravel to 1/2", light yellowish brown		X		3 1 3			Pass #200, SPT
		(ML) Sandy Silt, fine, with clay, olive brown	Iron Oxide Staining						
40		(ML) Sandy Silt, fine to coarse, with clay and gravel to 1", dark grayish brown	Interbedded sand and silt lenses ▼ Groundwater	X		3 3 2			DS, Pass #200, SPT
45		(SM) Silty Sand, fine to medium with coarse, grayish brown		X		3 6 8			Pass #200, SPT
50			Interbedded coarse sand lenses	X		4 9 11			Pass #200, SPT
55				X		3 5 5			Pass #200, SPT
60		(SM) Silty Sand, fine with medium, black		X		3 5 5			Pass #200, SPT
65		(SP-SM) Sand, fine to coarse, with silt and gravel to 1/2", black		X		4 7 12			Pass #200, SPT

DRAFT

10331-3 15383-8.GPJ CHJ.GDT 9/10/15

CHJ

SLOPE STABILITY INVESTIGATION
13964 EL MONTE ROAD, LAKESIDE, CALIFORNIA

Job No. 15383-8

Enclosure B-3b

EXPLORATORY BORING NO. 3

Date Drilled: 8/18/15 Client: El Monte NP

Equipment: CME75 Truck Rig Driving Weight / Drop / Sampler Size: 140lbs./30in./2.0" O.D.

Surface Elevation(ft): 448 Logged by: VJR Measured Depth to Water(ft): 42.3

DEPTH (ft)	GRAPHIC LOG	VISUAL CLASSIFICATION	REMARKS	SAMPLES DRIVE	SAMPLES BULK	BLOWS/6 IN.	FIELD MOISTURE (%)	DRY UNIT WT. (pcf)	LAB/FIELD TESTS
		(SP-SM) Sand, fine to coarse, with silt and gravel to 1/2", black	Sand Plug	X		2 4 5			Pass #200, SPT
75				X		5 7 10			Pass #200, SPT
80				X		9 10 14			Pass #200, SPT
85				X		6 9 13			Pass #200, SPT
		(SM) Silty Sand, fine to coarse, with clay and gravel to 2", gray [Consolidated Sediment]	Very Hard Drilling						
90				X		39 43 25			Pass #200, SPT
				X		11 12 18			Pass #200, SPT
95		END OF BORING PRACTICAL REFUSAL ON HARD SOIL NO BEDROCK, NO FILL, SLIGHT CAVING GROUNDWATER AT 42.25'							
100									

DRAFT

10331-3 15383-8.GPJ CHJ.GDT 9/10/15

CHJ

SLOPE STABILITY INVESTIGATION
13964 EL MONTE ROAD, LAKESIDE, CALIFORNIA

Job No. 15383-8

Enclosure B-3c

EXPLORATORY BORING NO. 4

Date Drilled: 8/18/15 Client: El Monte NP

Equipment: CME75 Truck Rig Driving Weight / Drop / Sampler Size: 140lbs./30in./3.0" O.D.

Surface Elevation(ft): 443 Logged by: VJR Measured Depth to Water(ft): 36.7

DEPTH (ft)	GRAPHIC LOG	VISUAL CLASSIFICATION	REMARKS	SAMPLES DRIVE	SAMPLES BULK	BLOWS/6 IN.	FIELD MOISTURE (%)	DRY UNIT WT. (pcf)	LAB/FIELD TESTS
		(SM) Silty Sand, fine, brown	Native	X		9 15 19	4.1	108	Ring
					▨		4.8		
5		(SM) Silty Sand, fine to medium, dark yellowish brown		X		5 7 9	5.1	104	Ring
10				X		6 11 11	6.3	107	Ring
					▨		6.4		SA
15				X		4 5 6	4.3	99	DS, Ring
20		(SP-SM) Sand, fine to coarse, with silt, light yellowish brown		X		6 13 13	16.1	Dist.	Ring
		(ML) Sandy Silt, fine, few clay, brown							
25		(SP-SM) Sand, fine to coarse, with silt, light olive brown		X		5 8 12	1.7	Dist.	Ring
30				X		6 8 12	N.R.	N.R.	Ring

DRAFT

10331-3 15383-8.GPJ CHJ.GDT 9/10/15

CHJ

SLOPE STABILITY INVESTIGATION
13964 EL MONTE ROAD, LAKESIDE, CALIFORNIA

Job No. 15383-8 Enclosure B-4a

EXPLORATORY BORING NO. 4

Date Drilled: 8/18/15 Client: El Monte NP

Equipment: CME75 Truck Rig Driving Weight / Drop / Sampler Size: 140lbs./30in./3.0" O.D.

Surface Elevation(ft): 443 Logged by: VJR Measured Depth to Water(ft): 36.7

DEPTH (ft)	GRAPHIC LOG	VISUAL CLASSIFICATION	REMARKS	SAMPLES DRIVE	SAMPLES BULK	BLOWS/6 IN.	FIELD MOISTURE (%)	DRY UNIT WT. (pcf)	LAB/FIELD TESTS
		(SP-SM) Sand, fine to coarse, with silt, light olive brown	▼ Groundwater	X		7 8 11	23.2	97	Ring
40				X		3 6 9	20.2	100	Ring
45				X		3 4 9	N.R.	N.R.	Ring
50		(SP-SM) Sand, fine to coarse, with silt and gravel to 1", dark gray		X		5 11 19	14.6	117	Ring
55				X		4 18 20	13.6	116	Ring
60				X		3 12 13	16.6	110	Ring
65				X		7 17 46	17.2	115	Ring

DRAFT

10331-3 15383-8.GPJ CHJ.GDT 9/10/15

CHJ

SLOPE STABILITY INVESTIGATION
13964 EL MONTE ROAD, LAKESIDE, CALIFORNIA

Job No. 15383-8 Enclosure B-4b

EXPLORATORY BORING NO. 4

Date Drilled: 8/18/15 Client: El Monte NP

Equipment: CME75 Truck Rig Driving Weight / Drop / Sampler Size: 140lbs./30in./3.0" O.D.

Surface Elevation(ft): 443 Logged by: VJR Measured Depth to Water(ft): 36.7

DEPTH (ft)	GRAPHIC LOG	VISUAL CLASSIFICATION	REMARKS	SAMPLES DRIVE	SAMPLES BULK	BLOWS/6 IN.	FIELD MOISTURE (%)	DRY UNIT WT. (pcf)	LAB/FIELD TESTS
		(SP-SM) Sand, fine to coarse, with silt and gravel to 1", dark gray	Sand Plug	X		4 4 7	N.R.	N.R.	Ring
75				X		8 23 40	16.2	115	Ring
80			Sand Plug	X		9 12 50	9.9	126	Ring
		(SM) Silty Sand, fine to medium with coarse, with clay and gravel to 2", dark gray [Consolidated Sediment]	Very Hard Drilling						
85				X		50/4"	6.1	135	Ring
90		END OF BORING NO REFUSAL, NO FILL, NO BEDROCK SLIGHT CAVING IN UPPER 10' GROUNDWATER AT 36.67'		X		50	10.1	123	Ring
95									
100									

DRAFT

10331-3 15383-8.GPJ CHJ.GDT 9/10/15

CHJ

SLOPE STABILITY INVESTIGATION
13964 EL MONTE ROAD, LAKESIDE, CALIFORNIA

Job No. 15383-8

Enclosure B-4c

LOG OF TEST BORING NO. B- 5

Drilling Date(s): 01/22/98 Drilling Equipment: MOBILE B-57 Surface Elevation: ~475'

Logged By: KLS Method/Hole Size: HOLLOW STEM AUGER/8" Bottom Elevation: ~453'

Depth (feet)	Sample Type	Blow Count (/foot)	Dry Density (pcf)	Moisture Content (%)	Lab Tests	USCS	Graphic Log	MATERIAL DESCRIPTION
0						SM		TOPSOIL: silty sand, loose, moist, brown.
2						SW		ALLUVIUM (Qal): medium to coarse grained sand, loose, damp, gray brown to gray.
6	H	7	98	2.7	GS			
8								
10	B							
	H	13						:Becomes medium grained sand.
12								
14								
16	H	12	95	24.0	GS	SM-SP		(Qal): very silty fine grained micaceous sand, loose to medium dense, wet, gray brown.
18								:Becomes fine grained micaceous sand with silt.
20	H	16						
22								End of boring at -21 ft. No free water encountered.
24								

Drive Energy Data: Hammer Type CAT HEAD
Weight 140 lbs.
Drop 30 in.

Please refer to symbols and note limitations shown on "Explanation of Logs"

DRAFT

SHEPARDSON ENGINEERING ASSOCIATES INC.
Geotechnical Consultants: Engineers-Geologists

Date: May, 1998 | Project No.: 97157-01

Log of Test Boring No. B- 5
El Monte Golf Course

Plate B6 1 of 1

BL3 98

LOG OF TEST BORING NO. B- 6

Drilling Date(s): 01/22/98 Drilling Equipment: MOBILE B-57 Surface Elevation: ~469'

Logged By: KLS Method/Hole Size: HOLLOW STEM AUGER/8" Bottom Elevation: ~447'

Depth (feet)	Sample Type	Blow Count (/foot)	Dry Density (pcf)	Moisture Content (%)	Lab Tests	USCS	Graphic Log	MATERIAL DESCRIPTION
						SM		TOPSOIL: silty sand, loose, moist, brown.
						SM-SW		ALLUVIUM (Qal): fine grained micaceous sand to silty sand, loose, gray brown.
2								
						SW		c(Qal): fine to coarse grained sand, loose, damp, gray.
4								
6	H	9	105	4.6	GS			
8								
10	H	11						
12								
14								
16	H	14			GS			:Becomes medium to coarse grained sand.
18								
20	H	15						:Becomes fine to medium grained sand.
22								End of boring at -21 ft. No free water encountered.
24								

Drive Energy Data: Hammer Type CAT HEAD
Weight 140 lbs.
Drop 30 in.

DRAFT

Please refer to symbols and note limitations shown on "Explanation of Logs"

SHEPARDSON ENGINEERING ASSOCIATES INC.
Geotechnical Consultants: Engineers-Geologists

Date: May, 1998 | Project No.: 97157-01

Log of Test Boring No. B- 6
El Monte Golf Course

Plate B7
1 of 1

BL3 98

LOG OF TEST BORING NO. B- 7

Drilling Date(s): 01/22/98 Drilling Equipment: MOBILE B-57 Surface Elevation: ~465'

Logged By: KLS Method/Hole Size: HOLLOW STEM AUGER/8" Bottom Elevation: ~443'

Depth (feet)	Sample Type	Blow Count (/foot)	Dry Density (pcf)	Moisture Content (%)	Lab Tests	USCS	Graphic Log	MATERIAL DESCRIPTION
0						SW		ALLUVIUM: fine grained micaceous silty sand to sand, loose, moist to wet, gray brown to olive.
2								
4								
6	H	11			GS			:Becomes fine to coarse grained sand and drier.
8					GS			
10	B H	16						:Becomes damp.
12								
14								
16	H	10						:Becomes moist.
18								:Becomes fine to medium grained.
20								
	H	17						:Becomes very wet to saturated.
22								End of boring at -21 ft. Free intergranular moisture at bottom of boring, near the water table.
24								

Drive Energy Data: Hammer Type CAT HEAD
Weight 140 lbs.
Drop 30 in.

DRAFT

Please refer to symbols and note limitations shown on "Explanation of Logs"

SHEPARDSON ENGINEERING ASSOCIATES INC.
Geotechnical Consultants:
Engineers-Geologists

Date: May, 1998 Project No.: 97157-01

Log of Test Boring No. B- 7
El Monte Golf Course

Plate B8
1 of 1

BL3 98

LOG OF TEST BORING NO. B- 8

Drilling Date(s): 01/22/98 Drilling Equipment: MOBILE B-57 Surface Elevation: ~455'

Logged By: KLS Method/Hole Size: HOLLOW STEM AUGER/8" Bottom Elevation: ~433'

Depth (feet)	Sample Type	Blow Count (/foot)	Dry Density (pcf)	Moisture Content (%)	Lab Tests	USCS	Graphic Log	MATERIAL DESCRIPTION
0						SW		ALLUVIUM (Qal): medium to coarse grained sand, loose, medium dense, gray.
6	H	10	103	2.9	GS			:Occasional scattered small gravel.
10	H	15			GS			:Becomes fine to coarse grained sand.
16	H	12						:Water table measured at -15.4 ft.
20	H	11						:Becomes very coarse grained sand.

Drive Energy Data: Hammer Type CAT HEAD
Weight 140 lbs.
Drop 30 in.

Please refer to symbols and note limitations shown on "Explanation of Logs"

DRAFT

SHEPARDSON ENGINEERING ASSOCIATES INC.
Geotechnical Consultants: Engineers-Geologists

Date: May, 1998 | Project No.: 97157-01

Log of Test Boring No. B- 8
El Monte Golf Course

Plate B9 1 of 1

BL3 98

LOG OF TEST BORING NO. B- 9

Drilling Date(s): 01/23/98 Drilling Equipment: MOBILE B-57 Surface Elevation: ~457'

Logged By: BMH Method/Hole Size: HOLLOW STEM AUGER/8" Bottom Elevation: ~435'

Depth (feet)	Sample Type	Blow Count (/foot)	Dry Density (pcf)	Moisture Content (%)	Lab Tests	USCS	Graphic Log	MATERIAL DESCRIPTION
0						SW		ALLUVIUM (Qal): fine to coarse grained sand, loose, damp, light gray. Contains gravel at -1 ft.
2								: Layer of 1" gravels at -3 ft.
4								
6	H	13			GS			
8	B							
10	H	12						:Becomes moist.
12								: 1" diameter gravels present between -11 ft. and -12ft..
14								Becomes coarser grained, micaceous.
16	H	20			GS	SM-SW		(Qal): fine to medium grained sand to silty sand, medium dense to loose, wet to saturated, medium gray.
18								
20	H	14						▽ :Water standing at -22.8 ft..
22								End of boring at -21 ft. Water table at -22.8 ft.
24								

Drive Energy Data: Hammer Type CAT HEAD
Weight 140 lbs.
Drop 30 in.

Please refer to symbols and note limitations shown on "Explanation of Logs"

DRAFT

SHEPARDSON ENGINEERING ASSOCIATES INC.
Geotechnical Consultants: Engineers-Geologists

Date: May, 1998 | Project No.: 97157-01

Log of Test Boring No. B- 9
El Monte Golf Course

Plate B10 1 of 1

BL3 98

LOG OF TEST BORING NO. B-10

Drilling Date(s): 01/23/98 Drilling Equipment: MOBILE B-57 Surface Elevation: ~455'

Logged By: BMH Method/Hole Size: HOLLOW STEM AUGER/8" Bottom Elevation: ~433'

Depth (feet)	Sample Type	Blow Count (/foot)	Dry Density (pcf)	Moisture Content (%)	Lab Tests	USCS	Graphic Log	MATERIAL DESCRIPTION
0						SW		ALLUVIUM (Qal): fine to coarse grained sand, loose, damp to dry, light gray.
2								
4								:Scattered gravel at - 3 ft..
6	H	2			GS			:Becomes gray-tan.
8								
10	H	7			GS			
12						SM		(Qal): silty fine grained sand, loose, moist, medium dark brown.
14	B							
16	H	20				SW		(Qal): fine to coarse grained sand, loose, wet to saturated, gray. :Contains scattered gravel.
18								
20								▽ :Water table measured at -19 ft.
	H	8				ML		(Qal): sandy silt, soft, saturated, dark brown.
22								End of boring at -21 ft.. Water table at -19 ft.
24								

Drive Energy Data: Hammer Type CAT HEAD
Weight 140 lbs.
Drop 30 in.

Please refer to symbols and note limitations shown on "Explanation of Logs"

DRAFT

SHEPARDSON ENGINEERING ASSOCIATES INC.
Geotechnical Consultants: Engineers-Geologists

Date: June, 1998 | Project No.: 97157-01

Log of Test Boring No. B-10
El Monte Golf Course

Plate B11 1 of 1

BL3 98

LOG OF TEST BORING NO. B-11

Drilling Date(s): 01/23/98 Drilling Equipment: MOBILE B-57 Surface Elevation: ~453'

Logged By: BMHKLS Method/Hole Size: HOLLOW STEM AUGER/8" Bottom Elevation: ~431'

Depth (feet)	Sample Type	Blow Count (/foot)	Dry Density (pcf)	Moisture Content (%)	Lab Tests	USCS	Graphic Log	MATERIAL DESCRIPTION
0						SM-SW		ALLUVIUM (Qal): medium to coarse grained sand, loose, moist, yellow brown.
6	H	10	104	6.5	GS			:Becomes interlayered with silty sand.
10	H	7	94	4.2	GS			:Becomes light gray. Interlayered silty sand layers are 1" to 2" thick.
16	H	14						
18								▽ :Water table measured at -18.6 ft..
20	H	20						
21								End of boring at -21 ft.. Water table at -18.6 ft..

Drive Energy Data: Hammer Type CAT HEAD
Weight 140 lbs.
Drop 30 in.

Please refer to symbols and note limitations shown on "Explanation of Logs"

DRAFT

LOG OF TEST BORING NO. B-12

Drilling Date(s): 01/23/98 Drilling Equipment: MOBILE B-57 Surface Elevation: ~449'

Logged By: BMH Method/Hole Size: HOLLOW STEM AUGER/8" Bottom Elevation: ~427'

Depth (feet)	Sample Type	Blow Count (/foot)	Dry Density (pcf)	Moisture Content (%)	Lab Tests	USCS	Graphic Log	MATERIAL DESCRIPTION
0					GS	SW		ALLUVIUM (Qal): fine to coarse grained sand, loose, damp, light gray. Contains scattered 1" diameter gravel.
2	B							
4								
6	H	12						:Contains 1" size gravel between -5 ft. and -6 ft.
8								
10	H	8			GS			:Below -11 ft. contains thin layers or lenses of dark brown silt.
12								
14								
16	H	17						▽ :Water table measured at -16.8 ft.
18								
20	H	26						:Becomes coarse grained sand.
22								End of boring at -21 ft. Water table measured at -16.8 ft.
24								

Drive Energy Data: Hammer Type CAT HEAD
Weight 140 lbs.
Drop 30 in.

Please refer to symbols and note limitations shown on "Explanation of Logs"

DRAFT

SHEPARDSON ENGINEERING ASSOCIATES INC.
Geotechnical Consultants: Engineers-Geologists

Date: May, 1998 | Project No.: 97157-01

Log of Test Boring No. B-12
El Monte Golf Course

Plate B13 1 of 1

BL3 98

LOG OF TEST BORING NO. B-14

Drilling Date(s): 01/23/98 Drilling Equipment: MOBILE B-57 Surface Elevation: ~447'
Logged By: BMH Method/Hole Size: HOLLOW STEM AUGER/8" Bottom Elevation: ~425'

Depth (feet)	Sample Type	Blow Count (/foot)	Dry Density (pcf)	Moisture Content (%)	Lab Tests	USCS	Graphic Log	MATERIAL DESCRIPTION
0						SW		ALLUVIUM (Qal): fine to coarse grained sand, loose, damp, yellow brown.
2								
4								
6	H	6	103	2.2	GS			
8						SW		(Qal): fine to coarse grained micaceous sand, loose, damp to saturated, orange brown.
10	H	9	114	1.4	GS			:Becomes medium brown with scattered blebs of silt.
12								
14								
16	H	6						
18								▽ :Water table measured at -18.8 ft.
20	H	10						:Contains little to no silt.
22								End of boring at -21 ft. Water table at -18.8 ft.
24								

Drive Energy Data: Hammer Type CAT HEAD
Weight 140 lbs.
Drop 30 in.

Please refer to symbols and note limitations shown on "Explanation of Logs"

DRAFT

LOG OF TEST BORING NO. B-15

Drilling Date(s): 01/23/98 Drilling Equipment: MOBILE B-57 Surface Elevation: ~436'

Logged By: BMH Method/Hole Size: HOLLOW STEM AUGER/8" Bottom Elevation: ~414'

Depth (feet)	Sample Type	Blow Count (/foot)	Dry Density (pcf)	Moisture Content (%)	Lab Tests	USCS	Graphic Log	MATERIAL DESCRIPTION
0						SW		ALLUVIUM (Qal): fine to medium grained slightly silty sand, loose, medium brown.
4						SW		(Qal): medium to coarse grained sand, loose, moist, brownish gray to olive gray.
6	H	7			GS			
8	B							
10	H	13			GS			
14								
16	H	14				SM		(Qal): silty fine grained sand, loose, moist, olive gray.
18								:Contains some silt lenses.
20	H	9						Becomes wet.
21								End of boring at -21 ft. No free water encountered.
22								
24								

Drive Energy Data: Hammer Type CAT HEAD
Weight 140 lbs.
Drop 30 in.

Please refer to symbols and note limitations shown on "Explanation of Logs"

DRAFT

SHEPARDSON ENGINEERING ASSOCIATES INC.
Geotechnical Consultants: Engineers-Geologists

Date: May, 1998 | Project No.: 97157-01

Log of Test Boring No. B-15
El Monte Golf Course

Plate **B16** 1 of 1

BL3 98

LOG OF TEST BORING NO. B-16

Drilling Date(s): 01/26/98 Drilling Equipment: MOBILE B-57 Surface Elevation: ~447'

Logged By: BMH Method/Hole Size: HOLLOW STEM AUGER/8" Bottom Elevation: ~371'

Depth (feet)	Sample Type	Blow Count (/foot)	Dry Density (pcf)	Moisture Content (%)	Lab Tests	USCS	Graphic Log	MATERIAL DESCRIPTION
0						SM		TOPSOIL/ALLUVIUM (Qal): silty fine grained sand, loose, medium dense, silty sand.
4						SW		ALLUVIUM (Qal): fine to coarse grained sand, loose, dry, brown gray.
6	H	7			GS			
10	H	8			GS			
16	H	13						:Becomes coarser grained.
20	H	18						
26						SM-SW		▽(Qal): variable well graded to silty sand,loose to medium dense, wet to saturated, gray brown. :Water table measured at -28.2 ft.
32						SW		(Qal): fine to coarse grained sand, loose to medium dense, saturated, gray. Contains occasional small amounts of gravel.

Drive Energy Data: Hammer Type CAT HEAD
Weight 140 lbs.
Drop 30 in.

Please refer to symbols and note limitations shown on "Explanation of Logs"

DRAFT

LOG OF TEST BORING NO. B-16

Drilling Date(s): 01/26/98 Drilling Equipment: MOBILE B-57 Surface Elevation: ~447'
Logged By: BMH Method/Hole Size: HOLLOW STEM AUGER/8" Bottom Elevation: ~371'

Depth (feet)	Sample Type	Blow Count (/foot)	Dry Density (pcf)	Moisture Content (%)	Lab Tests	USCS	Graphic Log	MATERIAL DESCRIPTION
42								(Qal): fine to coarse-grained sand, loose to medium dense, saturated, gray. Contains occasional small amounts of gravel
44								
46								
48								(Qal): fine to coarse-grained sand, loose to medium dense, saturated, gray. Contains occasional small amounts of gravel
50								
52								
54								
56								
58								
60								
62								
64								
66								
68								
70								
72								
74								
76								End of boring at -75 ft. Water table measured at -28.2 ft.
78								

Drive Energy Data: Hammer Type CAT HEAD
Weight 140 lbs.
Drop 30 in.

Please refer to symbols and note limitations shown on "Explanation of Logs"

DRAFT

LOG OF TEST BORING NO. B-17

Drilling Date(s): 01/26/98 Drilling Equipment: MOBILE B-57 Surface Elevation: ~470'

Logged By: BMH Method/Hole Size: HOLLOW STEM AUGER/8" Bottom Elevation: ~393'

Depth (feet)	Sample Type	Blow Count (/foot)	Dry Density (pcf)	Moisture Content (%)	Lab Tests	USCS	Graphic Log	MATERIAL DESCRIPTION
2	B					SM		ALLUVIUM (Qal): silty fine grained sand, loose, moist, medium dense.
4		8	74	5.3	GS	SM		Qal: silty fine grained micaceous sand, loose, dry, medium brown. Contains organic fragments, porous.
6	H	10						
8						SM-ML		Qal: interbedded silt and sand, loose, dry, light gray to medium brown with orange staining, porous.
10	H	13			GS			
12						SM-SW		(Qal): clean sand with interbeds of silty sand, loose, dry, light gray.
14								
16	H	14				SW-SP		(Qal): medium to coarse grained sand, loose, dry, light gray.
18								:Becomes mostly fine grained sand, damp to moist.
20	H	15						
22								:Becomes fine to coarse grained sand, wet.
24								
26	H	18						
28								▽ :Water table measured at -27.6 ft.
30	SS	19						
32								
34								
36								
38								:Becomes medium gray.

Drive Energy Data: Hammer Type CAT HEAD
Weight 140 lbs.
Drop 30 in.

Please refer to symbols and note limitations shown on "Explanation of Logs"

DRAFT

SHEPARDSON ENGINEERING ASSOCIATES INC.
Geotechnical Consultants: Engineers-Geologists

Date: May, 1998 | Project No.: 97157-01

Log of Test Boring No. B-17
El Monte Golf Course

Plate B18
1 of 2

BL3 98

LOG OF TEST BORING NO. B-17

Drilling Date(s): 01/26/98 Drilling Equipment: MOBILE B-57 Surface Elevation: ~470'

Logged By: BMH Method/Hole Size: HOLLOW STEM AUGER/8" Bottom Elevation: ~393'

Depth (feet)	Sample Type	Blow Count (/foot)	Dry Density (pcf)	Moisture Content (%)	Lab Tests	USCS	Graphic Log	MATERIAL DESCRIPTION
42	SS	18						(Qal): medium to coarse-grained sand, medium dense, saturated, dry, light gray
50	SS	19						:Contains dark gray to black silt interbeds.
66	SS	20						:Laminated layers of fine to very fine grained sand, dark gray.
76	SS	47						End of boring at -76.5 ft. Water table measured at -27.6 ft.

Drive Energy Data: Hammer Type CAT HEAD
Weight 140 lbs.
Drop 30 in.

DRAFT

Please refer to symbols and note limitations shown on "Explanation of Logs"

LOG OF TEST BORING NO. B-18

Drilling Date(s): 01/28/98 Drilling Equipment: JEEP RIG Surface Elevation: ~437'

Logged By: BMH Method/Hole Size: FLIGHT AUGER/6" Bottom Elevation: ~415'

Depth (feet)	Sample Type	Blow Count (/foot)	Dry Density (pcf)	Moisture Content (%)	Lab Tests	USCS	Graphic Log	MATERIAL DESCRIPTION
0	B				GS	SM		TOPSOIL/ALLUVIUM ?: silty fine grained sand, loose, moist, medium to dark brown.
8	B					SW		ALLUVIUM: medium to coarse grained sand, loose, moist, yellow to brownish gray. Contains scattered 1" size gravel.
10					GS			
12	B							
16	B							
20								End of boring at -20 ft. No free water encountered.

Drive Energy Data: Hammer Type
Weight lbs.
Drop in.

Please refer to symbols and note limitations shown on "Explanation of Logs"

DRAFT

LOG OF TEST BORING NO. B-19

Drilling Date(s): 02/10/98 Drilling Equipment: ROTARY WASH Surface Elevation: ~457'

Logged By: BMH Method/Hole Size: WASH BORING/3.5" Bottom Elevation: ~347'

Depth (feet)	Sample Type	Blow Count (/foot)	Dry Density (pcf)	Moisture Content (%)	Lab Tests	USCS	Graphic Log	MATERIAL DESCRIPTION
2						SW		ALLUVIUM (Qal): welll-graded sand, fine to medium -grained, loose, humid, light gray
4						GM		Qal: gravelly sand, medium dense, moist, light gray, contains 1" rounded gravels
6	H	31	119	14.3		SW		Qal: well-graded sand, medium dense, moist, light gray; contains scattered 3/4" gravel
10	H	30	116	10.9				
14	H	44	113	14.1				
18								water table at 16.5 feet
20	H	16	112	18.2				: saturated, contains intermittent silt layers, medium stiff
24	SS	21						:well-graded sand, medium dense, saturated, medium gray, contains interlayered fine and coarse sand
28	SS	21						:1 to 4 inch layers of silt, to 32 feet
34	SS	20						:well-graded sand, minor amounts of silt and gravel, medium dense, saturated, light gray
38	SS	23						
48	SS	10						ALLUVIUM (Qal): well-graded sand, medium dense, saturated, medium gray
								:becomes loose

Drive Energy Data: Hammer Type Cable winch
Weight 140 lbs.
Drop 30 in.

Please refer to symbols and note limitations shown on "Explanation of Logs"

DRAFT

LOG OF TEST BORING NO. B-19

Drilling Date(s): 02/10/98 Drilling Equipment: ROTARY WASH Surface Elevation: ~457'

Logged By: BMH Method/Hole Size: WASH BORING/3.5" Bottom Elevation: ~347'

Depth (feet)	Sample Type	Blow Count (/foot)	Dry Density (pcf)	Moisture Content (%)	Lab Tests	USCS	Graphic Log	MATERIAL DESCRIPTION
60	SS	22						:medium dense
62								
64								
66								
68	SS	42						:medium-grained sand with silt, poorly graded, dense, saturated, dark gray
70								
72								
74								
76								
78	SS	15						:contains 1/2" gravel; well-graded but coarser
80								
82						GW		ALLUVIUM (Qal): well-graded sand, medium dense, saturated, dark gray
84								(Qal): sandy gravels, dense, saturated, medium gray
86								
88								
90								
92								:heavy gravels
94						CL		ALLUVIUM: :clay layer, soft, saturated, blue gray
96						GW-SW		(Qal): gravel and sand, dense, saturated, medium gray
98								
100						SM		DECOMPOSED GRANITE BEDROCK: silty sand, coarse, very dense, saturated, dark gray
102								
104								
106	SS	50 50/2"						
108								
110		50/2"						End of boring at 110.2 feet
112								
114								

Drive Energy Data: Hammer Type Cable winch
Weight 140 lbs.
Drop 30 in.

Please refer to symbols and note limitations shown on "Explanation of Logs"

DRAFT

LOG OF TEST BORING NO. B-21

Drilling Date(s): 02/18/98 Drilling Equipment: MOBILE B-61 Surface Elevation: ~466'

Logged By: BMH Method/Hole Size: HOLLOW STEM AUGER/8" Bottom Elevation: ~440'

Depth (feet)	Sample Type	Blow Count (/foot)	Dry Density (pcf)	Moisture Content (%)	Lab Tests	USCS	Graphic Log	MATERIAL DESCRIPTION
0						ML		ALLUVIUM(Qal): sandy silt, medium stiff, moist, dark brown
2								
4						SM-ML		Qal: sandy silt to silty sand, medium dense, moist, yellow brown and medium brown, porous
6	H	20	72	12.1	CN	SM		Qal: silty fine sand, medium dense, moist, medium gray and medium brown
8								
10						SW		Qal: well-graded sand, medium dense, moist, light gray
12								:gravelly layer to 13 feet
14								
16	SS	26						:becomes more coarse-grained
18								
20	SS	32				SP		Qal: poorly-graded fine sand, medium dense, moist, light gray
22								
24							▽	:water table encountered at 24.5 feet
26	SS	22						
28								End of boring at 26.5 feet

Remarks:

DRAFT

Please refer to symbols and note limitations shown on "Explanation of Logs"

LOG OF TEST BORING NO. B-24

Drilling Date(s): 02/20/98 Drilling Equipment: ROTARY WASH Surface Elevation: ~436'

Logged By: BMH Method/Hole Size: WASH BORING/3.5" Bottom Elevation: ~331'

Depth (feet)	Sample Type	Blow Count (/foot)	Dry Density (pcf)	Moisture Content (%)	Lab Tests	USCS	Graphic Log	MATERIAL DESCRIPTION
2-54						SW		ALLUVIUM (Qal): well graded sand, fine to coarse-grained, medium dense, moist, brownish-gray to light gray :contains thin silt layers :gravelly at 25 feet :silt layers at 37-38 feet :gravel layer at 42 to 43 feet

Drive Energy Data: Hammer Type Cable winch
Weight 140 lbs.
Drop 30 in.

Please refer to symbols and note limitations shown on "Explanation of Logs"

DRAFT

LOG OF TEST BORING NO. B-24

Drilling Date(s): 02/20/98 Drilling Equipment: ROTARY WASH Surface Elevation: ~436'

Logged By: BMH Method/Hole Size: WASH BORING/3.5" Bottom Elevation: ~331'

Depth (feet)	Sample Type	Blow Count (/foot)	Dry Density (pcf)	Moisture Content (%)	Lab Tests	USCS	Graphic Log	MATERIAL DESCRIPTION
58–68								ALLUVIUM (Qal): well graded sand, fine to coarse-grained, medium dense, moist, brownish-gray to light gray :silt layers
70–74						GW		Qal: sandy gravels, dense, saturated, gray
76–82						SW		Qal: well-graded sand
84–92						GW		Qal: Gravel and cobble in a sandy matrix; dense, saturated, gray :layer of sand or smaller gravels to 92 feet
94–104	SS	69				SM		DECOMPOSED GRANITE BEDROCK: silty sand, dense to very dense, saturated, yellow gray :hard rock veins or inclusions to 97.5 feet
106								End of boring at 105.5 feet

Drive Energy Data: Hammer Type Cable winch
Weight 140 lbs.
Drop 30 in.

Please refer to symbols and note limitations shown on "Explanation of Logs"

DRAFT

LOG OF TEST BORING NO. B-27

Drilling Date(s): 2/7/03 | Drilling Equipment: B-61 | Surface Elevation: ~465'

Logged By: BMH | Method/Hole Size: Hollow stem auger/8" | Bottom Elevation: ~435'

Depth (feet)	Sample Type	Blow Count (/foot)	Dry Density (pcf)	Moisture Content (%)	Lab Tests	USCS	Graphic Log	MATERIAL DESCRIPTION
0	B				MD DS	SW		**ALLUVIUM (Qal):** well-graded sand, medium to coarse-grained, medium dense, moist, medium brown to medium gray
2								
4	H	32	96	8.6				
6	H	16						
8								
10	SS	4						
12								
14								
16	SS	26						
18								
20	SS	25			GS			:cobble layer, approximately one foot thick
22								
24								
26	SS	50/6"				SM		**DECOMPOSED GRANITE (Kgr):** bedrock, silty fine to coarse sand, dense to very dense, moist, orange-gray
28								:groundwater at 28 feet
30	SS	50/2"						End of boring at 30.2 feet; boring backfilled with bentonite chips

Remarks:

DRAFT

Please refer to symbols and note limitations shown on "Explanation of Logs"

DATE DRILLED 2/24/11 BORING NO. B-2

GROUND ELEVATION 438' ± (MSL) SHEET 2 OF 5

METHOD OF DRILLING 8" Hollow-Stem Auger (Diedrich D-120) (Tri-County Drilling)

DRIVE WEIGHT 140 lbs. (Auto. Trip Hammer) DROP 30"

SAMPLED BY MBG LOGGED BY MBG REVIEWED BY GTF

DEPTH (feet)	SAMPLES (Bulk / Driven)	BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DESCRIPTION/INTERPRETATION
20		17				SP	ALLUVIUM: (Continued) Grayish brown, moist, medium dense, poorly-graded, fine to coarse SAND; few gravel.
25		12				SP-SM	Grayish brown, moist, medium dense, poorly-graded, fine to medium SAND with silt.
30		18				SM	Light brown, moist, medium dense, silty fine to medium SAND.
35		25					Fine to coarse, silty sand.
40							

DRAFT

Ninyo & Moore

BORING LOG

EL MONTE VALLEY MINING, RECLAMATION, AND GROUNDWATER RECHARGE PROJECT, LAKESIDE, CALIFORNIA

PROJECT NO.	DATE	FIGURE
106200005	7/11	A-4

DATE DRILLED 2/24/11 BORING NO. B-2

GROUND ELEVATION 438' ± (MSL) SHEET 3 OF 5

METHOD OF DRILLING 8" Hollow-Stem Auger (Diedrich D-120) (Tri-County Drilling)

DRIVE WEIGHT 140 lbs. (Auto. Trip Hammer) DROP 30"

SAMPLED BY MBG LOGGED BY MBG REVIEWED BY GTF

DEPTH (feet)	SAMPLES (Bulk / Driven)	BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DESCRIPTION/INTERPRETATION
40		8	▽			SM	ALLUVIUM: (Continued) Light brown, saturated, medium dense, silty fine to coarse SAND.
						SP	Light brown, saturated, very dense, poorly-graded, medium SAND.
45		67/10"					
						SW-SM	Light brown, saturated, medium dense, well-graded, fine to coarse SAND with silt; trace fine gravel.
50		18					
		25					Dense with fine gravel.
55							
60							

DRAFT

Ninyo & Moore

BORING LOG

EL MONTE VALLEY MINING, RECLAMATION, AND GROUNDWATER RECHARGE PROJECT, LAKESIDE, CALIFORNIA

PROJECT NO.	DATE	FIGURE
106200005	7/11	A-5

DATE DRILLED 2/24/11 BORING NO. B-2

GROUND ELEVATION 438' ± (MSL) SHEET 4 OF 5

METHOD OF DRILLING 8" Hollow-Stem Auger (Diedrich D-120) (Tri-County Drilling)

DRIVE WEIGHT 140 lbs. (Auto. Trip Hammer) DROP 30"

SAMPLED BY MBG LOGGED BY MBG REVIEWED BY GTF

DEPTH (feet)	SAMPLES (Bulk / Driven)	BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DESCRIPTION/INTERPRETATION
60		15				SW-SM	ALLUVIUM: (Continued) Light brown, saturated, medium dense, well-graded, fine to medium SAND with silt.
						SP-SM	Light brown, saturated, dense, poorly-graded, fine SAND with silt.
65		49					
						SW-SM	Gray, saturated, dense, well-graded, fine to medium SAND with silt.
70		21					
75		23					Dark gray; fine to coarse sand; trace fine gravel.
80							

DRAFT

Ninyo & Moore

BORING LOG

EL MONTE VALLEY MINING, RECLAMATION, AND GROUNDWATER RECHARGE PROJECT, LAKESIDE, CALIFORNIA

PROJECT NO.	DATE	FIGURE
106200005	7/11	A-6

DATE DRILLED 2/24/11 BORING NO. B-2

GROUND ELEVATION 438' ± (MSL) SHEET 5 OF 5

METHOD OF DRILLING 8" Hollow-Stem Auger (Diedrich D-120) (Tri-County Drilling)

DRIVE WEIGHT 140 lbs. (Auto. Trip Hammer) DROP 30"

SAMPLED BY MBG LOGGED BY MBG REVIEWED BY GTF

DEPTH (feet)	SAMPLES (Bulk / Driven)	BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DESCRIPTION/INTERPRETATION
80		25				SM	ALLUVIUM: (Continued) Brownish black, saturated, medium dense, silty fine SAND.
							Gray; very dense; fine to medium sand.
85		50/1"					Refusal to further drilling.
							Total Depth = 85.5 feet. Groundwater encountered at approximately 41 feet during drilling. Backfilled with approximately 30 cubic feet of bentonite grout shortly after drilling on 2/24/11. Note: Groundwater, though not encountered at the time of drilling, may rise to a higher level due to seasonal variations in precipitation and several other factors as discussed in the report.
90							
95							
100							

DRAFT

Ninyo & Moore

BORING LOG

EL MONTE VALLEY MINING, RECLAMATION, AND GROUNDWATER RECHARGE PROJECT, LAKESIDE, CALIFORNIA

PROJECT NO.	DATE	FIGURE
106200005	7/11	A-7

DATE DRILLED 3/11/11 BORING NO. B-3

GROUND ELEVATION 440' ± (MSL) SHEET 1 OF 4

METHOD OF DRILLING 8" Hollow-Stem Auger (Diedrich D-120) (Tri-County Drilling)

DRIVE WEIGHT 140 lbs. (Auto. Trip Hammer) DROP 30"

SAMPLED BY MBG LOGGED BY MBG REVIEWED BY GTF

DEPTH (feet)	SAMPLES (Bulk / Driven)	BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DESCRIPTION/INTERPRETATION
0						SP	ALLUVIUM: Gray, moist, loose, poorly-graded, fine to medium SAND; trace subangular gravel (up to ½ inch).
5		6					
						SM	Brown, moist, medium dense, silty fine SAND.
10		18					
						SW	Gray, moist, loose, well-graded, fine to coarse SAND.
15		12					
20							

DRAFT

Ninyo & Moore

BORING LOG

EL MONTE VALLEY MINING, RECLAMATION, AND GROUNDWATER RECHARGE PROJECT, LAKESIDE, CALIFORNIA

PROJECT NO.	DATE	FIGURE
106200005	7/11	A-8

DATE DRILLED 3/11/11 BORING NO. B-3

GROUND ELEVATION 440' ± (MSL) SHEET 2 OF 4

METHOD OF DRILLING 8" Hollow-Stem Auger (Diedrich D-120) (Tri-County Drilling)

DRIVE WEIGHT 140 lbs. (Auto. Trip Hammer) DROP 30"

SAMPLED BY MBG LOGGED BY MBG REVIEWED BY GTF

DEPTH (feet)	SAMPLES (Bulk / Driven)	BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DESCRIPTION/INTERPRETATION
20		14				SW-SM	ALLUVIUM: (Continued) Light brown, moist, medium dense, well-graded, fine to medium SAND with silt.
25		9				ML	Dark brown, moist, medium dense, fine sandy SILT.
						SM	Light brown, moist, medium dense, silty fine SAND.
30		28					
						ML	Dark brown, wet, loose, fine sandy SILT.
35		5					
			▽				Saturated.
40							

DRAFT

Ninyo & Moore

BORING LOG

EL MONTE VALLEY MINING, RECLAMATION, AND GROUNDWATER RECHARGE PROJECT, LAKESIDE, CALIFORNIA

PROJECT NO.	DATE	FIGURE
106200005	7/11	A-9

DATE DRILLED 3/11/11 BORING NO. B-3

GROUND ELEVATION 440' ± (MSL) SHEET 3 OF 4

METHOD OF DRILLING 8" Hollow-Stem Auger (Diedrich D-120) (Tri-County Drilling)

DRIVE WEIGHT 140 lbs. (Auto. Trip Hammer) DROP 30"

SAMPLED BY MBG LOGGED BY MBG REVIEWED BY GTF

DEPTH (feet)	SAMPLES (Bulk / Driven)	BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DESCRIPTION/INTERPRETATION
40		9				SM	ALLUVIUM: (Continued) Dark brown, saturated, medium dense, silty fine SAND; trace fine gravel.
45		26				SP-SM	Gray, saturated, medium dense, poorly-graded, fine to medium SAND with silt; few fine gravel.
50		30				SM	Dark brown, saturated, dense, silty fine to medium SAND.
55		26					Becomes finer.
60							

DRAFT

Ninyo & Moore

BORING LOG

EL MONTE VALLEY MINING, RECLAMATION, AND GROUNDWATER RECHARGE PROJECT, LAKESIDE, CALIFORNIA

PROJECT NO.	DATE	FIGURE
106200005	7/11	A-10

DATE DRILLED 3/11/11 BORING NO. B-3

GROUND ELEVATION 440' ± (MSL) SHEET 4 OF 4

METHOD OF DRILLING 8" Hollow-Stem Auger (Diedrich D-120) (Tri-County Drilling)

DRIVE WEIGHT 140 lbs. (Auto. Trip Hammer) DROP 30"

SAMPLED BY MBG LOGGED BY MBG REVIEWED BY GTF

DEPTH (feet)	SAMPLES Bulk	SAMPLES Driven	BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DESCRIPTION/INTERPRETATION
60		■	46			▒	SP	ALLUVIUM: (Continued) Brown, saturated, dense, poorly-graded, fine to medium SAND.
								Total Depth = 61.5 feet. Groundwater encountered at approximately 39 feet during drilling. Backfilled with approximately 21 cubic feet of bentonite grout on shortly after drilling on 3/11/11. Note: Groundwater may rise to a level higher than that measured in borehole due to seasonal variations in precipitation and several other factors as discussed in the report.
65								
70								
75								
80								

DRAFT

Ninyo & Moore

BORING LOG

EL MONTE VALLEY MINING, RECLAMATION, AND GROUNDWATER RECHARGE PROJECT, LAKESIDE, CALIFORNIA

PROJECT NO.	DATE	FIGURE
106200005	7/11	A-11

DATE DRILLED 3/11/11 and 3/14/11 BORING NO. B-4

GROUND ELEVATION 442' ± (MSL) SHEET 1 OF 4

METHOD OF DRILLING 8" Hollow-Stem Auger (Diedrich D-120) (Tri-County Drilling)

DRIVE WEIGHT 140 lbs. (Auto. Trip Hammer) DROP 30"

SAMPLED BY MBG LOGGED BY MBG REVIEWED BY GTF

DEPTH (feet)	SAMPLES (Bulk / Driven)	BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DESCRIPTION/INTERPRETATION
0						SP	ALLUVIUM: Light brown, moist, loose, poorly-graded, fine to medium SAND.
5		7					Loose to medium dense.
10		18					Gray; medium dense; fine to coarse sand.
15		25				SW-SM	Grayish brown, moist, dense, well graded, fine to medium SAND with silt; few coarse sand.
20							

DRAFT

Ninyo & Moore

BORING LOG

EL MONTE VALLEY MINING, RECLAMATION, AND GROUNDWATER RECHARGE PROJECT, LAKESIDE, CALIFORNIA

PROJECT NO.	DATE	FIGURE
106200005	7/11	A-12

DATE DRILLED 3/11/11 and 3/14/11 BORING NO. B-4

GROUND ELEVATION 442' ± (MSL) SHEET 2 OF 4

METHOD OF DRILLING 8" Hollow-Stem Auger (Diedrich D-120) (Tri-County Drilling)

DRIVE WEIGHT 140 lbs. (Auto. Trip Hammer) DROP 30"

SAMPLED BY MBG LOGGED BY MBG REVIEWED BY GTF

DEPTH (feet)	SAMPLES (Bulk / Driven)	BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DESCRIPTION/INTERPRETATION
20		17				SP-SM	ALLUVIUM: (Continued) Gray, moist, medium dense, poorly-graded, fine to coarse SAND; with few fine gravel.
25		25					
						SM	Dark brown, moist, medium dense, silty fine SAND.
30		9					Boring terminated on 3/11/11. Boring resumed on 3/14/11.
						ML	Dark brown, moist, medium dense, fine sandy SILT.
35		5	▽				Saturated; loose.
40							

DRAFT

Ninyo & Moore

BORING LOG

EL MONTE VALLEY MINING, RECLAMATION, AND GROUNDWATER RECHARGE PROJECT, LAKESIDE, CALIFORNIA

PROJECT NO.	DATE	FIGURE
106200005	7/11	A-13

DATE DRILLED 3/11/11 and 3/14/11 BORING NO. B-4

GROUND ELEVATION 442' ± (MSL) SHEET 3 OF 4

METHOD OF DRILLING 8" Hollow-Stem Auger (Diedrich D-120) (Tri-County Drilling)

DRIVE WEIGHT 140 lbs. (Auto. Trip Hammer) DROP 30"

SAMPLED BY MBG LOGGED BY MBG REVIEWED BY GTF

DEPTH (feet)	SAMPLES (Bulk / Driven)	BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DESCRIPTION/INTERPRETATION
40		21				SM	ALLUVIUM: (Continued) Brown, saturated, medium dense, silty fine to medium SAND.
45		17				SP-SM	Brown, saturated, medium dense, poorly-graded, fine to coarse SAND with silt.
50		29				SM	Brown, saturated, medium dense, silty fine to coarse SAND.
55		15				SW-SM	Brown, saturated, medium dense, well-graded, fine to coarse SAND with silt.
60							

DRAFT

Ninyo & Moore

BORING LOG

EL MONTE VALLEY MINING, RECLAMATION, AND GROUNDWATER RECHARGE PROJECT, LAKESIDE, CALIFORNIA

PROJECT NO.	DATE	FIGURE
106200005	7/11	A-14

DATE DRILLED 3/11/11 and 3/14/11 BORING NO. B-4

GROUND ELEVATION 442' ± (MSL) SHEET 4 OF 4

METHOD OF DRILLING 8" Hollow-Stem Auger (Diedrich D-120) (Tri-County Drilling)

DRIVE WEIGHT 140 lbs. (Auto. Trip Hammer) DROP 30"

SAMPLED BY MBG LOGGED BY MBG REVIEWED BY GTF

DEPTH (feet)	SAMPLES (Bulk / Driven)	BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DESCRIPTION/INTERPRETATION
60		77/9"	127			SP-SM	ALLUVIUM: (Continued) Grayish brown, saturated, very dense, poorly-graded, fine SAND with silt
							Total Depth = 61.5 feet. Groundwater encountered at approximately 35 feet during drilling. Backfilled with approximately 21 cubic feet of bentonite grout shortly after drilling on 3/14/11. Note: Groundwater may rise to a level higher than that measured in borehole due to seasonal variations in precipitation and several other factors as discussed in the report.
65							
70							
75							
80							

DRAFT

Ninyo & Moore

BORING LOG

EL MONTE VALLEY MINING, RECLAMATION, AND GROUNDWATER RECHARGE PROJECT, LAKESIDE, CALIFORNIA

PROJECT NO.	DATE	FIGURE
106200005	7/11	A-15

DATE DRILLED 3/14/11 BORING NO. B-5

GROUND ELEVATION 450' ± (MSL) SHEET 1 OF 4

METHOD OF DRILLING 8" Hollow-Stem Auger (Diedrich D-120) (Tri-County Drilling)

DRIVE WEIGHT 140 lbs. (Auto. Trip Hammer) DROP 30"

SAMPLED BY MBG LOGGED BY MBG REVIEWED BY GTF

DEPTH (feet)	SAMPLES (Bulk / Driven)	BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DESCRIPTION/INTERPRETATION
0						SM	ALLUVIUM: Dark brown, moist, loose, silty fine SAND; trace roots.
5		8				SP-SM	Grayish brown, moist, loose, poorly-graded, fine to medium SAND with silt.
10		5				SM	Dark brown, moist, loose, silty fine SAND.
15		16				SP-SM	Gray, moist, medium dense, poorly-graded, fine to medium SAND with silt; trace coarse sand.
20							

DRAFT

Ninyo & Moore

BORING LOG

EL MONTE VALLEY MINING, RECLAMATION, AND GROUNDWATER RECHARGE PROJECT, LAKESIDE, CALIFORNIA

PROJECT NO.	DATE	FIGURE
106200005	7/11	A-16

DATE DRILLED 3/14/11 BORING NO. B-5

GROUND ELEVATION 450' ± (MSL) SHEET 2 OF 4

METHOD OF DRILLING 8" Hollow-Stem Auger (Diedrich D-120) (Tri-County Drilling)

DRIVE WEIGHT 140 lbs. (Auto. Trip Hammer) DROP 30"

SAMPLED BY MBG LOGGED BY MBG REVIEWED BY GTF

DEPTH (feet)	SAMPLES (Bulk / Driven)	BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DESCRIPTION/INTERPRETATION
20		20				SP	ALLUVIUM: (Continued) Gray, moist, medium dense, poorly-graded, fine to medium SAND.
25		11				SW-SM	Gray, moist, medium dense, well-graded, fine to coarse SAND with silt; trace angular gravel.
30		7				ML	Dark brown, moist, loose to medium dense, fine sandy SILT.
35		16				SM	Dark brown, moist, medium dense, silty fine SAND.
40							

DRAFT

Ninyo & Moore

BORING LOG

EL MONTE VALLEY MINING, RECLAMATION, AND GROUNDWATER RECHARGE PROJECT, LAKESIDE, CALIFORNIA

PROJECT NO.	DATE	FIGURE
106200005	7/11	A-17

DATE DRILLED 3/14/11 BORING NO. B-5

GROUND ELEVATION 450' ± (MSL) SHEET 3 OF 4

METHOD OF DRILLING 8" Hollow-Stem Auger (Diedrich D-120) (Tri-County Drilling)

DRIVE WEIGHT 140 lbs. (Auto. Trip Hammer) DROP 30"

SAMPLED BY MBG LOGGED BY MBG REVIEWED BY GTF

DEPTH (feet)	SAMPLES (Bulk / Driven)	BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DESCRIPTION/INTERPRETATION
40		6	▽			ML	ALLUVIUM: (Continued) Dark brown, moist, loose, fine sandy SILT. Saturated.
45		20				SM	Dark brown, saturated, medium dense to dense, silty fine SAND.
50		22				SP-SM	Dark brown, saturated, medium dense, poorly-graded, fine SAND with silt.
55		23				SW-SM	Brown, saturated, dense, well-graded, fine to medium SAND with silt.
60							

DRAFT

Ninyo & Moore

BORING LOG

EL MONTE VALLEY MINING, RECLAMATION, AND GROUNDWATER RECHARGE PROJECT, LAKESIDE, CALIFORNIA

PROJECT NO.	DATE	FIGURE
106200005	7/11	A-18

DATE DRILLED 3/14/11 BORING NO. B-5

GROUND ELEVATION 450' ± (MSL) SHEET 4 OF 4

METHOD OF DRILLING 8" Hollow-Stem Auger (Diedrich D-120) (Tri-County Drilling)

DRIVE WEIGHT 140 lbs. (Auto. Trip Hammer) DROP 30"

SAMPLED BY MBG LOGGED BY MBG REVIEWED BY GTF

DEPTH (feet)	SAMPLES (Bulk / Driven)	BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DESCRIPTION/INTERPRETATION
60		39				SP-SM	ALLUVIUM: (Continued) Dark brown, saturated, medium dense, poorly-graded, fine to medium SAND with silt; trace coarse sand.
							Total Depth = 61.5 feet. Groundwater encountered at approximately 43 feet during drilling. Backfilled with approximately 21 cubic feet of bentonite grout shortly after drilling on 3/14/11. Note: Groundwater may rise to a level higher than that measured in borehole due to seasonal variations in precipitation and several other factors as discussed in the report.
65							
70							
75							
80							

DRAFT

Ninyo & Moore

BORING LOG

EL MONTE VALLEY MINING, RECLAMATION, AND GROUNDWATER RECHARGE PROJECT, LAKESIDE, CALIFORNIA

PROJECT NO.	DATE	FIGURE
106200005	7/11	A-19

DATE DRILLED 2/25/11 BORING NO. B-6

GROUND ELEVATION 455' ± (MSL) SHEET 1 OF 4

METHOD OF DRILLING 8" Hollow-Stem Auger (Diedrich D-120) (Tri-County Drilling)

DRIVE WEIGHT 140 lbs. (Auto. Trip Hammer) DROP 30"

SAMPLED BY MBG LOGGED BY MBG REVIEWED BY GTF

DEPTH (feet)	SAMPLES (Bulk / Driven)	BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DESCRIPTION/INTERPRETATION
0						SM	ALLUVIUM: Light brown, damp, loose, silty, fine to medium SAND.
						SW	Grayish brown, damp, loose, well-graded, medium to coarse SAND.
5		9					
						SM	Brown, moist, loose, silty SAND; trace roots.
10		12				SW-SM	Gray, damp, loose, well-graded, fine to medium SAND with silt.
						SP-SM	Gray and light brown, moist, medium dense, poorly-graded, fine to medium SAND with silt.
15		13					
20							

DRAFT

Ninyo & Moore

BORING LOG

EL MONTE VALLEY MINING, RECLAMATION, AND GROUNDWATER RECHARGE PROJECT, LAKESIDE, CALIFORNIA

PROJECT NO.	DATE	FIGURE
106200005	7/11	A-20

DATE DRILLED 2/25/11 BORING NO. B-6

GROUND ELEVATION 455' ± (MSL) SHEET 2 OF 4

METHOD OF DRILLING 8" Hollow-Stem Auger (Diedrich D-120) (Tri-County Drilling)

DRIVE WEIGHT 140 lbs. (Auto. Trip Hammer) DROP 30"

SAMPLED BY MBG LOGGED BY MBG REVIEWED BY GTF

DEPTH (feet)	SAMPLES (Bulk / Driven)	BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DESCRIPTION/INTERPRETATION
20		19				SW-SM	ALLUVIUM: (Continued) Dark brown, moist, medium dense, well-graded, fine to coarse SAND with silt and gravel.
25		20				SP-SM	Grayish brown, moist, medium dense to dense, poorly-graded, fine to medium SAND with silt.
30		16					Medium dense.
35		10	▽				Saturated.
40							

DRAFT

Ninyo & Moore

BORING LOG

EL MONTE VALLEY MINING, RECLAMATION, AND GROUNDWATER RECHARGE PROJECT, LAKESIDE, CALIFORNIA

PROJECT NO.	DATE	FIGURE
106200005	7/11	A-21

DATE DRILLED 2/25/11 BORING NO. B-6

GROUND ELEVATION 455' ± (MSL) SHEET 3 OF 4

METHOD OF DRILLING 8" Hollow-Stem Auger (Diedrich D-120) (Tri-County Drilling)

DRIVE WEIGHT 140 lbs. (Auto. Trip Hammer) DROP 30"

SAMPLED BY MBG LOGGED BY MBG REVIEWED BY GTF

DEPTH (feet)	SAMPLES (Bulk / Driven)	BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DESCRIPTION/INTERPRETATION
40		8				ML	ALLUVIUM: (Continued) Dark brown, saturated, loose, fine sandy SILT.
45		50/2"					Very dense.
							METAVOLCANIC ROCK: Dark brown, saturated, soft, weathered METAVOLCANIC ROCK.
50		50/2"					
55		50/5"					Light brown and gray.
60							

DRAFT

Ninyo & Moore

BORING LOG

EL MONTE VALLEY MINING, RECLAMATION, AND GROUNDWATER RECHARGE PROJECT, LAKESIDE, CALIFORNIA

PROJECT NO.	DATE	FIGURE
106200005	7/11	A-22

DATE DRILLED 2/25/11 BORING NO. B-6

GROUND ELEVATION 455' ± (MSL) SHEET 4 OF 4

METHOD OF DRILLING 8" Hollow-Stem Auger (Diedrich D-120) (Tri-County Drilling)

DRIVE WEIGHT 140 lbs. (Auto. Trip Hammer) DROP 30"

SAMPLED BY MBG LOGGED BY MBG REVIEWED BY GTF

DEPTH (feet)	SAMPLES (Bulk / Driven)	BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DESCRIPTION/INTERPRETATION
60		50/4"					METAVOLCANIC ROCK: (Continued) Light brown and gray, saturated, soft, weathered METAVOLCANIC ROCK. Total Depth = 60.3 feet. Groundwater encountered at approximately 35 feet during drilling. Backfilled with approximately 21 cubic feet of bentonite grout shortly after drilling on 2/25/11. Note: Groundwater may rise to a level higher than that measured in borehole due to seasonal variations in precipitation and several other factors as discussed in the report.
65							
70							
75							
80							

DRAFT

Ninyo & Moore

BORING LOG

EL MONTE VALLEY MINING, RECLAMATION, AND GROUNDWATER RECHARGE PROJECT, LAKESIDE, CALIFORNIA

PROJECT NO.	DATE	FIGURE
106200005	7/11	A-23

DATE DRILLED 3/1/11 BORING NO. B-7

GROUND ELEVATION 453' ± (MSL) SHEET 1 OF 5

METHOD OF DRILLING 8" Hollow-Stem Auger (Diedrich D-120) (Tri-County Drilling)

DRIVE WEIGHT 140 lbs. (Auto. Trip Hammer) DROP 30"

SAMPLED BY MBG LOGGED BY MBG REVIEWED BY GTF

DEPTH (feet)	SAMPLES (Bulk / Driven)	BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DESCRIPTION/INTERPRETATION
0						SM	ALLUVIUM: Brown, moist, loose, silty fine to medium SAND.
5		15				SP	Grayish brown, damp, medium dense, poorly-graded, fine to coarse SAND with fine gravel.
10		15				SP-SM	Light brown, moist, medium dense, poorly-graded, fine to medium SAND with silt; trace roots.
15		11				SW-SM	Gray to light brown, moist, medium dense, well-graded, fine to medium SAND with silt.
20							

DRAFT

Ninyo & Moore

BORING LOG

EL MONTE VALLEY MINING, RECLAMATION, AND GROUNDWATER RECHARGE PROJECT, LAKESIDE, CALIFORNIA

PROJECT NO.	DATE	FIGURE
106200005	7/11	A-24

DATE DRILLED 3/1/11 BORING NO. B-7

GROUND ELEVATION 453' ± (MSL) SHEET 2 OF 5

METHOD OF DRILLING 8" Hollow-Stem Auger (Diedrich D-120) (Tri-County Drilling)

DRIVE WEIGHT 140 lbs. (Auto. Trip Hammer) DROP 30"

SAMPLED BY MBG LOGGED BY MBG REVIEWED BY GTF

DEPTH (feet)	SAMPLES (Bulk / Driven)	BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DESCRIPTION/INTERPRETATION
20		18				SW-SM	ALLUVIUM: (Continued) Gray to light brown, moist, medium dense, well-graded, fine to coarse SAND with silt.
25		19					
30		17				SP-SM	Gray to light brown, saturated, medium dense, poorly-graded, fine to medium SAND with silt; micaceous
35		17				ML	Brown, saturated, medium dense, fine sandy SILT; micaceous.
40							

DRAFT

Ninyo & Moore

BORING LOG

EL MONTE VALLEY MINING, RECLAMATION, AND GROUNDWATER RECHARGE PROJECT, LAKESIDE, CALIFORNIA

PROJECT NO.	DATE	FIGURE
106200005	7/11	A-25

DATE DRILLED 3/1/11 BORING NO. B-7

GROUND ELEVATION 453' ± (MSL) SHEET 3 OF 5

METHOD OF DRILLING 8" Hollow-Stem Auger (Diedrich D-120) (Tri-County Drilling)

DRIVE WEIGHT 140 lbs. (Auto. Trip Hammer) DROP 30"

SAMPLED BY MBG LOGGED BY MBG REVIEWED BY GTF

DEPTH (feet)	SAMPLES (Bulk / Driven)	BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DESCRIPTION/INTERPRETATION
40						ML	ALLUVIUM: (Continued)
		25				SP-SM	Brown, saturated, medium dense, fine sandy SILT; micaceous. Brown, saturated, dense, poorly-graded, fine to medium SAND with silt.
45		22				SM	Brown, saturate, dense, silty fine SAND; micaceous.
						SP	Light brown, saturated, medium dense, poorly-graded, fine to coarse SAND.
50							
55		27				SW-SM	Light brown, saturated, dense, well-graded, fine to coarse SAND with silt.
60							

DRAFT

Ninyo & Moore

BORING LOG

EL MONTE VALLEY MINING, RECLAMATION, AND GROUNDWATER RECHARGE PROJECT, LAKESIDE, CALIFORNIA

PROJECT NO.	DATE	FIGURE
106200005	7/11	A-26

DATE DRILLED 3/1/11 BORING NO. B-7

GROUND ELEVATION 453' ± (MSL) SHEET 4 OF 5

METHOD OF DRILLING 8" Hollow-Stem Auger (Diedrich D-120) (Tri-County Drilling)

DRIVE WEIGHT 140 lbs. (Auto. Trip Hammer) DROP 30"

SAMPLED BY MBG LOGGED BY MBG REVIEWED BY GTF

DEPTH (feet)	SAMPLES (Bulk / Driven)	BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DESCRIPTION/INTERPRETATION
60		26				SM	ALLUVIUM: (Continued) Reddish brown, saturated, dense, silty fine to coarse SAND; few gravel.
						ML	Reddish brown, saturated, medium dense, fine sandy SILT.
65		19					
70		18				SM	Reddish brown, saturated, medium dense, silty fine to coarse SAND with fine gravel.
75		23					Dense; no gravel.
80							

DRAFT

Ninyo & Moore

BORING LOG

EL MONTE VALLEY MINING, RECLAMATION, AND GROUNDWATER RECHARGE PROJECT, LAKESIDE, CALIFORNIA

PROJECT NO.	DATE	FIGURE
106200005	7/11	A-27

DATE DRILLED 3/1/11 BORING NO. B-7

GROUND ELEVATION 453' ± (MSL) SHEET 5 OF 5

METHOD OF DRILLING 8" Hollow-Stem Auger (Diedrich D-120) (Tri-County Drilling)

DRIVE WEIGHT 140 lbs. (Auto. Trip Hammer) DROP 30"

SAMPLED BY MBG LOGGED BY MBG REVIEWED BY GTF

DEPTH (feet)	SAMPLES (Bulk / Driven)	BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DESCRIPTION/INTERPRETATION
80		89/11"				SM	ALLUVIUM: (Continued) Dark brown, saturated, very dense, silty fine to medium SAND; with fine gravel.
							METAVOLCANIC ROCK: Yellow and brown, saturated, soft, weathered METAVOLCANIC ROCK.
85		76					
							Total Depth = 86.5 feet. Groundwater encountered at approximately 30 feet during drilling. Backfilled with approximately 30 cubic feet of bentonite grout shortly after drilling on 3/1/11. Note: Groundwater may rise to a level higher than that measured in borehole due to seasonal variations in precipitation and several other factors as discussed in the report.
90							
95							
100							

DRAFT

Ninyo & Moore

BORING LOG

EL MONTE VALLEY MINING, RECLAMATION, AND GROUNDWATER RECHARGE PROJECT, LAKESIDE, CALIFORNIA

PROJECT NO.	DATE	FIGURE
106200005	7/11	A-28

DATE DRILLED 3/3/11 BORING NO. B-8

GROUND ELEVATION 456' ± (MSL) SHEET 1 OF 4

METHOD OF DRILLING 8" Hollow-Stem Auger (Diedrich D-120) (Tri-County Drilling)

DRIVE WEIGHT 140 lbs. (Auto. Trip Hammer) DROP 30"

SAMPLED BY MBG LOGGED BY MBG REVIEWED BY GTF

DEPTH (feet)	SAMPLES (Bulk / Driven)	BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DESCRIPTION/INTERPRETATION
0						SM	ALLUVIUM: Brown, moist, loose, silty fine SAND.
						SP	Gray, moist, medium dense, poorly-graded, fine to medium SAND; trace coarse sand and gravel (up to ½ inch).
5		22					
10		12				SP-SM	Gray, moist, medium dense, poorly-graded, fine to medium SAND with silt.
15		20					Medium dense to dense.
20							

DRAFT

Ninyo & Moore

BORING LOG

EL MONTE VALLEY MINING, RECLAMATION, AND GROUNDWATER RECHARGE PROJECT, LAKESIDE, CALIFORNIA

PROJECT NO.	DATE	FIGURE
106200005	7/11	A-29

DATE DRILLED 3/3/11 BORING NO. B-8

GROUND ELEVATION 456' ± (MSL) SHEET 2 OF 4

METHOD OF DRILLING 8" Hollow-Stem Auger (Diedrich D-120) (Tri-County Drilling)

DRIVE WEIGHT 140 lbs. (Auto. Trip Hammer) DROP 30"

SAMPLED BY MBG LOGGED BY MBG REVIEWED BY GTF

DEPTH (feet)	SAMPLES (Bulk / Driven)	BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DESCRIPTION/INTERPRETATION
20		27				SP	ALLUVIUM: (Continued) Gray, moist, medium dense, poorly-graded, fine to medium SAND. Reddish brown; fine to coarse sand.
						SM	Brown, wet, dense to very dense, silty fine SAND; with gravel.
25		36				SW	Gray, moist, very dense, well-graded, fine to coarse SAND with some gravel (up to 1 inch).
						ML	Reddish brown, wet, dense, fine sandy SILT; micaceous.
30		29					
35		51					
40							

DRAFT

Ninyo & Moore

BORING LOG

EL MONTE VALLEY MINING, RECLAMATION, AND GROUNDWATER RECHARGE PROJECT, LAKESIDE, CALIFORNIA

PROJECT NO.	DATE	FIGURE
106200005	7/11	A-30

DATE DRILLED 3/3/11 BORING NO. B-8

GROUND ELEVATION 456' ± (MSL) SHEET 3 OF 4

METHOD OF DRILLING 8" Hollow-Stem Auger (Diedrich D-120) (Tri-County Drilling)

DRIVE WEIGHT 140 lbs. (Auto. Trip Hammer) DROP 30"

SAMPLED BY MBG LOGGED BY MBG REVIEWED BY GTF

DEPTH (feet)	SAMPLES (Bulk / Driven)	BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DESCRIPTION/INTERPRETATION
40		15	▽			ML	ALLUVIUM: (Continued) Reddish brown, saturated, medium dense, fine sandy SILT.
45		27				SM	Grayish brown, saturated, dense, silty fine to coarse SAND. Trace gravel (up to ½ inch).
50		55					Reddish brown; silty fine sand.
55		79/8"					METAVOLCANIC ROCK: Dark gray, saturated, soft, weathered METAVOLCANIC ROCK.
60							

DRAFT

Ninyo & Moore

BORING LOG

EL MONTE VALLEY MINING, RECLAMATION, AND GROUNDWATER RECHARGE PROJECT, LAKESIDE, CALIFORNIA

PROJECT NO.	DATE	FIGURE
106200005	7/11	A-31

DATE DRILLED 3/3/11 BORING NO. B-8

GROUND ELEVATION 456' ± (MSL) SHEET 4 OF 4

METHOD OF DRILLING 8" Hollow-Stem Auger (Diedrich D-120) (Tri-County Drilling)

DRIVE WEIGHT 140 lbs. (Auto. Trip Hammer) DROP 30"

SAMPLED BY MBG LOGGED BY MBG REVIEWED BY GTF

DEPTH (feet)	SAMPLES Bulk	SAMPLES Driven	BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DESCRIPTION/INTERPRETATION
60			50/5"					METAVOLCANIC ROCK: (Continued) Dark gray, saturated, soft, weathered METAVOLCANIC ROCK.
								Total Depth = 61.0 feet. Groundwater encountered at approximately 40 feet during drilling. Backfilled with approximately 21 cubic feet of bentonite grout shortly after drilling on 3/3/11. Note: Groundwater may rise to a level higher than that measured in borehole due to seasonal variations in precipitation and several other factors as discussed in the report.
65								
70								
75								
80								

DRAFT

Ninyo & Moore

BORING LOG

EL MONTE VALLEY MINING, RECLAMATION, AND GROUNDWATER RECHARGE PROJECT, LAKESIDE, CALIFORNIA

PROJECT NO.	DATE	FIGURE
106200005	7/11	A-32

DATE DRILLED 3/2/11 BORING NO. B-9

GROUND ELEVATION 460' ± (MSL) SHEET 1 OF 4

METHOD OF DRILLING 8" Hollow-Stem Auger (Diedrich D-120) (Tri-County Drilling)

DRIVE WEIGHT 140 lbs. (Auto. Trip Hammer) DROP 30"

SAMPLED BY MBG LOGGED BY MBG REVIEWED BY GTF

DEPTH (feet)	SAMPLES (Bulk / Driven)	BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DESCRIPTION/INTERPRETATION
0						SP	ALLUVIUM: Brown, moist, loose, silty fine to medium SAND.
						SP	Gray, moist, medium dense, poorly-graded, fine to medium SAND; trace fine to coarse gravel.
5		18					
						SW-SM	Gray, moist, dense, well-graded, fine to coarse SAND with silt.
10		22					
15		16					Medium dense.
20							

DRAFT

Ninyo & Moore

BORING LOG

EL MONTE VALLEY MINING, RECLAMATION, AND GROUNDWATER RECHARGE PROJECT, LAKESIDE, CALIFORNIA

PROJECT NO.	DATE	FIGURE
106200005	7/11	A-33

DATE DRILLED 3/2/11 BORING NO. B-9

GROUND ELEVATION 460' ± (MSL) SHEET 2 OF 4

METHOD OF DRILLING 8" Hollow-Stem Auger (Diedrich D-120) (Tri-County Drilling)

DRIVE WEIGHT 140 lbs. (Auto. Trip Hammer) DROP 30"

SAMPLED BY MBG LOGGED BY MBG REVIEWED BY GTF

DEPTH (feet)	SAMPLES (Bulk / Driven)	BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DESCRIPTION/INTERPRETATION
20		6				ML	ALLUVIUM: (Continued) Dark brown, wet, loose, fine sandy SILT; micaceous.
25		17				SM	Grayish brown, moist, medium dense, silty, fine to medium SAND.
						SW-SM	Yellowish brown, dense, well-graded, fine to coarse SAND with silt.
30		24					
35		28	▽			SP-SM	Gray to dark brown, saturated, medium dense, poorly-graded, fine SAND with silt; micaceous.
						SW-SM	Gray, saturated, very dense, well-graded, fine to coarse SAND with silt.
40							

DRAFT

Ninyo & Moore

BORING LOG

EL MONTE VALLEY MINING, RECLAMATION, AND GROUNDWATER RECHARGE PROJECT, LAKESIDE, CALIFORNIA

PROJECT NO.	DATE	FIGURE
106200005	7/11	A-34

DATE DRILLED 3/2/11 BORING NO. B-9

GROUND ELEVATION 460' ± (MSL) SHEET 3 OF 4

METHOD OF DRILLING 8" Hollow-Stem Auger (Diedrich D-120) (Tri-County Drilling)

DRIVE WEIGHT 140 lbs. (Auto. Trip Hammer) DROP 30"

SAMPLED BY MBG LOGGED BY MBG REVIEWED BY GTF

DEPTH (feet)	SAMPLES (Bulk / Driven)	BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DESCRIPTION/INTERPRETATION
40		51				SW-SM	ALLUVIUM: (Continued) Gray, saturated, very dense, well-graded, fine to coarse SAND with silt; trace fine to coarse gravel.
45		23				SM	Reddish brown, saturated, dense, silty fine SAND; micaceous.
50		59				ML	Reddish brown, saturated, dense, fine sandy SILT.
55		31					
60							

DRAFT

Ninyo & Moore

BORING LOG

EL MONTE VALLEY MINING, RECLAMATION, AND GROUNDWATER RECHARGE PROJECT, LAKESIDE, CALIFORNIA

PROJECT NO.	DATE	FIGURE
106200005	7/11	A-35

DATE DRILLED 3/2/11 BORING NO. B-9

GROUND ELEVATION 460' ± (MSL) SHEET 4 OF 4

METHOD OF DRILLING 8" Hollow-Stem Auger (Diedrich D-120) (Tri-County Drilling)

DRIVE WEIGHT 140 lbs. (Auto. Trip Hammer) DROP 30"

SAMPLED BY MBG LOGGED BY MBG REVIEWED BY GTF

DEPTH (feet)	SAMPLES (Bulk / Driven)	BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DESCRIPTION/INTERPRETATION
60		18				ML	ALLUVIUM: (Continued) Reddish brown, saturated, medium dense, fine sandy SILT.
65		50/6"				SP-SM	Brown, saturated, very dense, poorly-graded, fine to medium SAND with silt; some fine to coarse gravel.
70		65				SM	Brown, saturated, dense, silty fine SAND.
75		53					METAVOLCANIC ROCK: Yellow and gray, saturated, soft, weathered METAVOLCANIC ROCK.
80							Total Depth = 76.5 feet. Groundwater encountered at approximately 35 feet during drilling. Backfilled with approximately 27 cubic feet of bentonite grout shortly after drilling on 3/2/11. Note: Groundwater may rise to a level higher than that measured in borehole due to seasonal variations in precipitation and several other factors as discussed in the report.

DRAFT

Ninyo & Moore

BORING LOG

EL MONTE VALLEY MINING, RECLAMATION, AND GROUNDWATER RECHARGE PROJECT, LAKESIDE, CALIFORNIA

PROJECT NO.	DATE	FIGURE
106200005	7/11	A-36

DATE DRILLED 3/9/11 - 3/10/11 BORING NO. B-10

GROUND ELEVATION 475' ± (MSL) SHEET 1 OF 4

METHOD OF DRILLING 8" Hollow-Stem Auger (Diedrich D-120) (Tri-County Drilling)

DRIVE WEIGHT 140 lbs. (Auto. Trip Hammer) DROP 30"

SAMPLED BY MBG LOGGED BY MBG REVIEWED BY GTF

DEPTH (feet)	SAMPLES (Bulk / Driven)	BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DESCRIPTION/INTERPRETATION
0						SM	ALLUVIUM: Grayish brown, moist, loose, silty fine SAND.
5		6					
10		16					Medium dense; few coarse sand.
						SW	Gray, moist, medium dense, well-graded, fine to coarse SAND.
						SM	Brown, moist, medium dense, silty fine SAND.
15		8				ML	Dark brown, moist, medium dense, fine sandy SILT.
20							

DRAFT

Ninyo & Moore

BORING LOG

EL MONTE VALLEY MINING, RECLAMATION, AND GROUNDWATER RECHARGE PROJECT, LAKESIDE, CALIFORNIA

PROJECT NO.	DATE	FIGURE
106200005	7/11	A-37

DATE DRILLED 3/9/11 - 3/10/11 BORING NO. B-10

GROUND ELEVATION 475' ± (MSL) SHEET 2 OF 4

METHOD OF DRILLING 8" Hollow-Stem Auger (Diedrich D-120) (Tri-County Drilling)

DRIVE WEIGHT 140 lbs. (Auto. Trip Hammer) DROP 30"

SAMPLED BY MBG LOGGED BY MBG REVIEWED BY GTF

DEPTH (feet)	SAMPLES (Bulk / Driven)	BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DESCRIPTION/INTERPRETATION
20		7				ML	ALLUVIUM: (Continued) Dark brown, moist, loose to medium dense, fine sandy SILT.
						SM	Light brown, moist, medium dense, silty fine SAND.
25		29					
30		21					Dense; trace medium to coarse sand. Boring terminated on 3/9/11. Boring resumed on 3/10/11.
35		16				SW-SM	Light brown, moist, medium dense, well-graded, fine to medium SAND with silt; little coarse sand.
						SM	Grayish brown, moist, medium dense, silty fine to coarse SAND.
40							

DRAFT

Ninyo & Moore

BORING LOG

EL MONTE VALLEY MINING, RECLAMATION, AND GROUNDWATER RECHARGE PROJECT, LAKESIDE, CALIFORNIA

PROJECT NO.	DATE	FIGURE
106200005	7/11	A-38

DATE DRILLED 3/9/11 - 3/10/11 BORING NO. B-10

GROUND ELEVATION 475' ± (MSL) SHEET 3 OF 4

METHOD OF DRILLING 8" Hollow-Stem Auger (Diedrich D-120) (Tri-County Drilling)

DRIVE WEIGHT 140 lbs. (Auto. Trip Hammer) DROP 30"

SAMPLED BY MBG LOGGED BY MBG REVIEWED BY GTF

DEPTH (feet)	SAMPLES (Bulk / Driven)	BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DESCRIPTION/INTERPRETATION
40		15				SM	ALLUVIUM: (Continued) Grayish brown to dark brown, wet, medium dense, silty fine SAND.
			▽				Brown, saturated, medium dense to dense, silty fine to medium SAND; trace coarse sand.
45		20					
50		26				SW-SM	Brown, saturated, dense, well-graded, fine to medium SAND with silt.
						SM	Dark brown, saturated, very dense, silty fine SAND; trace gravel (up to 1¼ inches).
55		50/3"					
60							

DRAFT

Ninyo & Moore

BORING LOG

EL MONTE VALLEY MINING, RECLAMATION, AND GROUNDWATER RECHARGE PROJECT, LAKESIDE, CALIFORNIA

PROJECT NO.	DATE	FIGURE
106200005	7/11	A-39

DATE DRILLED 3/9/11 - 3/10/11 BORING NO. B-10

GROUND ELEVATION 475' ± (MSL) SHEET 4 OF 4

METHOD OF DRILLING 8" Hollow-Stem Auger (Diedrich D-120) (Tri-County Drilling)

DRIVE WEIGHT 140 lbs. (Auto. Trip Hammer) DROP 30"

SAMPLED BY MBG LOGGED BY MBG REVIEWED BY GTF

DEPTH (feet)	SAMPLES (Bulk / Driven)	BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DESCRIPTION/INTERPRETATION
60		34				SM	ALLUVIUM: (Continued) Dark brown, saturated, very dense, silty fine SAND.
							Total Depth = 61.5 feet. Groundwater encountered at approximately 44 feet during drilling. Backfilled with approximately 21 cubic feet of bentonite grout shortly after drilling on 3/10/11. Note: Groundwater may rise to a level higher than that measured in borehole due to seasonal variations in precipitation and several other factors as discussed in the report.
65							
70							
75							
80							

DRAFT

Ninyo & Moore

BORING LOG

EL MONTE VALLEY MINING, RECLAMATION, AND GROUNDWATER RECHARGE PROJECT, LAKESIDE, CALIFORNIA

PROJECT NO.	DATE	FIGURE
106200005	7/11	A-40

DATE DRILLED 2/23/11 BORING NO. B-14

GROUND ELEVATION 431' ± (MSL) SHEET 1 OF 2

METHOD OF DRILLING 8" Hollow-Stem Auger (Diedrich D-120) (Tri-County Drilling)

DRIVE WEIGHT 140 lbs. (Auto. Trip Hammer) DROP 30"

SAMPLED BY MJB LOGGED BY MJB REVIEWED BY GTF

DEPTH (feet)	SAMPLES (Bulk / Driven)	BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DESCRIPTION/INTERPRETATION
0						SW	ALLUVIUM: Grayish and yellowish brown, damp, loose, well-graded, fine to medium SAND; trace silt; micaceous.
5		11	10.6	91.1			
10		7					Loose to medium dense; well-graded, fine to coarse SAND; fewer silt.
15		17	3.2	103.3			Dry to damp; medium dense.
20							

DRAFT

Ninyo & Moore

BORING LOG

EL MONTE VALLEY MINING, RECLAMATION, AND GROUNDWATER RECHARGE PROJECT, LAKESIDE, CALIFORNIA

PROJECT NO.	DATE	FIGURE
106200005	7/11	A-52

DATE DRILLED 2/23/11 BORING NO. B-14

GROUND ELEVATION 431' ± (MSL) SHEET 2 OF 2

METHOD OF DRILLING 8" Hollow-Stem Auger (Diedrich D-120) (Tri-County Drilling)

DRIVE WEIGHT 140 lbs. (Auto. Trip Hammer) DROP 30"

SAMPLED BY MJB LOGGED BY MJB REVIEWED BY GTF

DEPTH (feet)	SAMPLES (Bulk / Driven)	BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DESCRIPTION/INTERPRETATION
20		7				SM	ALLUVIUM: (Continued) Dark brown, damp to moist, loose to medium dense, silty fine SAND; micaceous.
						SW	Grayish brown, dry to damp, medium dense, well-graded, fine to coarse SAND; micaceous.
25		28	4.1	100.7			
							Total Depth = 26.5 feet. Groundwater not encountered. Backfilled with approximately 9 cubic feet of bentonite grout shortly after drilling on 2/23/11. Note: Groundwater, though not encountered at the time of drilling, may rise to a higher level due to seasonal variations in precipitation and several other factors as discussed in the report.
30							
35							
40							

DRAFT

Ninyo & Moore

BORING LOG

EL MONTE VALLEY MINING, RECLAMATION, AND GROUNDWATER RECHARGE PROJECT, LAKESIDE, CALIFORNIA

PROJECT NO.	DATE	FIGURE
106200005	7/11	A-53

DATE DRILLED 2/23/11 BORING NO. B-15

GROUND ELEVATION 436' ± (MSL) SHEET 1 OF 5

METHOD OF DRILLING 8" Hollow-Stem Auger (Diedrich D-120) (Tri-County Drilling)

DRIVE WEIGHT 140 lbs. (Auto. Trip Hammer) DROP 30"

SAMPLED BY MJB LOGGED BY MJB REVIEWED BY GTF

DEPTH (feet)	SAMPLES (Bulk / Driven)	BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DESCRIPTION/INTERPRETATION
0						ML	ALLUVIUM: Dark brown, damp, loose to medium dense, fine sandy SILT; scattered medium to coarse sand; micaceous.
10						SM	Dark brown, damp, loose to medium dense, silty fine SAND; scattered medium to coarse sand; micaceous.
20							

DRAFT

Ninyo & Moore

BORING LOG

EL MONTE VALLEY MINING, RECLAMATION, AND GROUNDWATER RECHARGE PROJECT, LAKESIDE, CALIFORNIA

PROJECT NO.	DATE	FIGURE
106200005	7/11	A-54

DATE DRILLED 2/23/11 BORING NO. B-15

GROUND ELEVATION 436' ± (MSL) SHEET 2 OF 5

METHOD OF DRILLING 8" Hollow-Stem Auger (Diedrich D-120) (Tri-County Drilling)

DRIVE WEIGHT 140 lbs. (Auto. Trip Hammer) DROP 30"

SAMPLED BY MJB LOGGED BY MJB REVIEWED BY GTF

DEPTH (feet)	SAMPLES (Bulk / Driven)	BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DESCRIPTION/INTERPRETATION
20						SM	ALLUVIUM: (Continued) Dark brown, damp, loose to medium dense, silty fine SAND; scattered medium to coarse sand; micaceous.
25							Few medium to coarse sand; fewer silt.
30							
35							
40							

DRAFT

Ninyo & Moore

BORING LOG

EL MONTE VALLEY MINING, RECLAMATION, AND GROUNDWATER RECHARGE PROJECT, LAKESIDE, CALIFORNIA

PROJECT NO.	DATE	FIGURE
106200005	7/11	A-55

DATE DRILLED 2/23/11 BORING NO. B-15

GROUND ELEVATION 436' ± (MSL) SHEET 3 OF 5

METHOD OF DRILLING 8" Hollow-Stem Auger (Diedrich D-120) (Tri-County Drilling)

DRIVE WEIGHT 140 lbs. (Auto. Trip Hammer) DROP 30"

SAMPLED BY MJB LOGGED BY MJB REVIEWED BY GTF

DEPTH (feet)	SAMPLES (Bulk / Driven)	BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DESCRIPTION/INTERPRETATION
40						SM	ALLUVIUM: (Continued) Brown, damp, medium dense, silty fine SAND; some medium to coarse sand; micaceous.
45			▽			SW	Grayish brown, saturated, medium dense to dense, well-graded, fine to coarse SAND; micaceous.
50							
55							
60							

DRAFT

Ninyo & Moore

BORING LOG

EL MONTE VALLEY MINING, RECLAMATION, AND GROUNDWATER RECHARGE PROJECT, LAKESIDE, CALIFORNIA

PROJECT NO.	DATE	FIGURE
106200005	7/11	A-56

DATE DRILLED 2/23/11 BORING NO. B-15

GROUND ELEVATION 436' ± (MSL) SHEET 4 OF 5

METHOD OF DRILLING 8" Hollow-Stem Auger (Diedrich D-120) (Tri-County Drilling)

DRIVE WEIGHT 140 lbs. (Auto. Trip Hammer) DROP 30"

SAMPLED BY MJB LOGGED BY MJB REVIEWED BY GTF

DEPTH (feet)	SAMPLES (Bulk / Driven)	BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DESCRIPTION/INTERPRETATION
60						SW-SM	ALLUVIUM: (Continued) Grayish brown, saturated, medium dense to dense, well-graded, fine to coarse SAND with silt; micaceous.
		20					
65		51					Dense.
70		21					
75		39					Medium dense.
						SW+GW	Gray to grayish brown, saturated, very dense, well-graded, fine to coarse SAND and GRAVEL; micaceous.
80							

DRAFT

Ninyo & Moore

BORING LOG

EL MONTE VALLEY MINING, RECLAMATION, AND GROUNDWATER RECHARGE PROJECT, LAKESIDE, CALIFORNIA

PROJECT NO.	DATE	FIGURE
106200005	7/11	A-57

DATE DRILLED 2/23/11 BORING NO. B-15

GROUND ELEVATION 436' ± (MSL) SHEET 5 OF 5

METHOD OF DRILLING 8" Hollow-Stem Auger (Diedrich D-120) (Tri-County Drilling)

DRIVE WEIGHT 140 lbs. (Auto. Trip Hammer) DROP 30"

SAMPLED BY MJB LOGGED BY MJB REVIEWED BY GTF

DEPTH (feet)	SAMPLES (Bulk / Driven)	BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DESCRIPTION/INTERPRETATION
80		38				SW+GW	ALLUVIUM: (Continued) Gray to grayish brown, saturated, very dense, well-graded, fine to coarse SAND and GRAVEL; micaceous.
						SP	Gray to grayish brown, saturated, very dense, poorly-graded, medium SAND; scattered gravel; micaceous.
85		50/4"					
90		50/4"				GP-GM	Gray, saturated, very dense, poorly-graded, fine to coarse GRAVEL with silt; some cobbles. Refusal to further drilling.
							Total Depth = 91.0 feet. Groundwater encountered at approximately 45 feet during drilling. Backfilled with approximately 32 cubic feet of bentonite grout shortly after drilling on 2/23/11. Note: Groundwater may rise to a level higher than that measured in borehole due to seasonal variations in precipitation and several other factors as discussed in the report.
95							
100							

DRAFT

Ninyo & Moore

BORING LOG

EL MONTE VALLEY MINING, RECLAMATION, AND GROUNDWATER RECHARGE PROJECT, LAKESIDE, CALIFORNIA

PROJECT NO.	DATE	FIGURE
106200005	7/11	A-58

DATE DRILLED 3/14/11 BORING NO. B-16

GROUND ELEVATION 444' ± (MSL) SHEET 1 OF 3

METHOD OF DRILLING 8" Hollow-Stem Auger (Diedrich D-120) (Tri-County Drilling)

DRIVE WEIGHT 140 lbs. (Auto. Trip Hammer) DROP 30"

SAMPLED BY MBG LOGGED BY MBG REVIEWED BY GTF

DEPTH (feet)	SAMPLES (Bulk / Driven)	BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DESCRIPTION/INTERPRETATION
0						SM	ALLUVIUM: Brown, moist, loose, silty fine SAND.
5		8					Dark brown; medium dense.
10		15					
15		4				SP	Gray, moist, loose, poorly-graded, fine SAND; some medium sand; trace coarse sand.
20							

DRAFT

Ninyo & Moore

BORING LOG

EL MONTE VALLEY MINING, RECLAMATION, AND GROUNDWATER RECHARGE PROJECT, LAKESIDE, CALIFORNIA

PROJECT NO.	DATE	FIGURE
106200005	7/11	A-59

DATE DRILLED 3/14/11 BORING NO. B-16

GROUND ELEVATION 444' ± (MSL) SHEET 2 OF 3

METHOD OF DRILLING 8" Hollow-Stem Auger (Diedrich D-120) (Tri-County Drilling)

DRIVE WEIGHT 140 lbs. (Auto. Trip Hammer) DROP 30"

SAMPLED BY MBG LOGGED BY MBG REVIEWED BY GTF

DEPTH (feet)	SAMPLES (Bulk / Driven)	BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DESCRIPTION/INTERPRETATION
20		12				SP-SM	ALLUVIUM: (Continued) Gray, damp, medium dense, fine sandy SILT; trace medium sand.
25		9				SM	Brown to gray, moist, medium dense, silty fine SAND.
						SP	Gray, moist, medium dense, poorly-graded, fine SAND.
30		16					
						SM	Gray to brown, moist, medium dense, silty fine SAND.
35		9					
							METAVOLCANIC ROCK: Yellow, moist, soft, weathered METAVOLCANIC ROCK.
40							

DRAFT

Ninyo & Moore

BORING LOG

EL MONTE VALLEY MINING, RECLAMATION, AND GROUNDWATER RECHARGE PROJECT, LAKESIDE, CALIFORNIA

PROJECT NO.	DATE	FIGURE
106200005	7/11	A-60

DATE DRILLED 3/14/11 BORING NO. B-16

GROUND ELEVATION 444' ± (MSL) SHEET 3 OF 3

METHOD OF DRILLING 8" Hollow-Stem Auger (Diedrich D-120) (Tri-County Drilling)

DRIVE WEIGHT 140 lbs. (Auto. Trip Hammer) DROP 30"

SAMPLED BY MBG LOGGED BY MBG REVIEWED BY GTF

DEPTH (feet)	SAMPLES (Bulk / Driven)	BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DESCRIPTION/INTERPRETATION
40		55					METAVOLCANIC ROCK: (Continued) Yellow, moist, soft, weathered METAVOLCANIC ROCK.
45		50/2"					Refusal to further drilling. Total Depth = 45.2 feet. Groundwater not encountered. Backfilled with approximately 16 cubic feet of bentonite grout shortly after drilling on 3/14/11. Note: Groundwater, though not encountered at the time of drilling, may rise to a higher level due to seasonal variations in precipitation and several other factors as discussed in the report.
50							
55							
60							

DRAFT

Ninyo & Moore

BORING LOG

EL MONTE VALLEY MINING, RECLAMATION, AND GROUNDWATER RECHARGE PROJECT, LAKESIDE, CALIFORNIA

PROJECT NO.	DATE	FIGURE
106200005	7/11	A-61

DATE DRILLED 2/25/11 BORING NO. B-17

GROUND ELEVATION 443' ± (MSL) SHEET 1 OF 2

METHOD OF DRILLING 8" Hollow-Stem Auger (Diedrich D-120) (Tri-County Drilling)

DRIVE WEIGHT 140 lbs. (Auto. Trip Hammer) DROP 30"

SAMPLED BY MBG LOGGED BY MBG REVIEWED BY GTF

DEPTH (feet)	SAMPLES (Bulk / Driven)	BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DESCRIPTION/INTERPRETATION
0						SM	ALLUVIUM: Grayish brown, damp, loose to medium dense, silty SAND.
						SW	Gray, dry to damp, loose, well-graded, fine to coarse SAND.
5	Driven	9	3.8	100.0			
						SM	Light brown, moist, medium dense, silty, fine to coarse SAND; trace roots.
10	Driven	14	15.2	97.4			
15	Driven	14	15.2	97.4			Brown.
20							

DRAFT

Ninyo & Moore

BORING LOG

EL MONTE VALLEY MINING, RECLAMATION, AND GROUNDWATER RECHARGE PROJECT, LAKESIDE, CALIFORNIA

PROJECT NO.	DATE	FIGURE
106200005	7/11	A-62

DATE DRILLED 2/25/11 BORING NO. B-17

GROUND ELEVATION 443' ± (MSL) SHEET 2 OF 2

METHOD OF DRILLING 8" Hollow-Stem Auger (Diedrich D-120) (Tri-County Drilling)

DRIVE WEIGHT 140 lbs. (Auto. Trip Hammer) DROP 30"

SAMPLED BY MBG LOGGED BY MBG REVIEWED BY GTF

DEPTH (feet)	SAMPLES (Bulk / Driven)	BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DESCRIPTION/INTERPRETATION
20		8				SM	ALLUVIUM: (Continued) Brown, moist, medium dense, silty fine to coarse SAND.
						SW	Gray, dry to damp, medium dense, well-graded, fine to medium SAND.
25		22	3.2	101.0		SM	Brown, moist, medium dense, silty SAND.
							Total Depth = 26.5 feet. Groundwater not encountered. Backfilled with approximately 9 cubic feet of bentonite grout shortly after drilling on 2/25/11. Note: Groundwater, though not encountered at the time of drilling, may rise to a higher level due to seasonal variations in precipitation and several other factors as discussed in the report.
30							
35							
40							

DRAFT

Ninyo & Moore

BORING LOG

EL MONTE VALLEY MINING, RECLAMATION, AND GROUNDWATER RECHARGE PROJECT, LAKESIDE, CALIFORNIA

PROJECT NO.	DATE	FIGURE
106200005	7/11	A-63

DATE DRILLED 3/10/11 - 3/11/11 BORING NO. B-19

GROUND ELEVATION 444' ± (MSL) SHEET 1 OF 3

METHOD OF DRILLING 8" Hollow-Stem Auger (Diedrich D-120) (Tri-County Drilling)

DRIVE WEIGHT 140 lbs. (Auto. Trip Hammer) DROP 30"

SAMPLED BY MBG LOGGED BY MBG REVIEWED BY GTF

DEPTH (feet)	SAMPLES (Bulk / Driven)	BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DESCRIPTION/INTERPRETATION
0						SW	ALLUVIUM: Light brown, moist, loose, well-graded, fine to coarse SAND.
5	Driven	20					Medium dense; trace gravel (up to ½ inch).
10	Driven	10				SW-SM	Gray, moist, medium dense, well-graded, fine to medium SAND with silt.
15	Driven	18					Silty fine sand; trace subangular gravel (up to ¾ inch).
20							

DRAFT

Ninyo & Moore

BORING LOG

EL MONTE VALLEY MINING, RECLAMATION, AND GROUNDWATER RECHARGE PROJECT, LAKESIDE, CALIFORNIA

PROJECT NO.	DATE	FIGURE
106200005	7/11	A-66

DATE DRILLED 3/10/11 - 3/11/11 BORING NO. B-19

GROUND ELEVATION 444' ± (MSL) SHEET 2 OF 3

METHOD OF DRILLING 8" Hollow-Stem Auger (Diedrich D-120) (Tri-County Drilling)

DRIVE WEIGHT 140 lbs. (Auto. Trip Hammer) DROP 30"

SAMPLED BY MBG LOGGED BY MBG REVIEWED BY GTF

DEPTH (feet)	SAMPLES (Bulk / Driven)	BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DESCRIPTION/INTERPRETATION
20		7				SM	ALLUVIUM: (Continued) Dark brown, moist, loose to medium dense, silty fine SAND.
25		27				SW-SM	Grayish brown, moist, medium dense, well-graded, fine to medium SAND with silt. Boring terminated on 3/10/11. Boring resumed on 3/11/11.
30		4				SM	Grayish brown, moist, loose, silty fine to medium SAND.
35		17	▽			SP	Grayish brown, saturated, medium dense, poorly-graded, fine to medium SAND.
40							

DRAFT

Ninyo & Moore

BORING LOG

EL MONTE VALLEY MINING, RECLAMATION, AND GROUNDWATER RECHARGE PROJECT, LAKESIDE, CALIFORNIA

PROJECT NO.	DATE	FIGURE
106200005	7/11	A-67

DATE DRILLED 3/10/11 - 3/11/11 BORING NO. B-19

GROUND ELEVATION 444' ± (MSL) SHEET 3 OF 3

METHOD OF DRILLING 8" Hollow-Stem Auger (Diedrich D-120) (Tri-County Drilling)

DRIVE WEIGHT 140 lbs. (Auto. Trip Hammer) DROP 30"

SAMPLED BY MBG LOGGED BY MBG REVIEWED BY GTF

DEPTH (feet)	SAMPLES (Bulk / Driven)	BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DESCRIPTION/INTERPRETATION
40		19				SP	ALLUVIUM: (Continued) Dark brown, saturated, medium dense, poorly-graded, fine to medium SAND; little coarse sand.
45		9				SM	Dark brown, saturated, medium dense, silty fine SAND.
50		10					Loose.
55		21					Dense.
		50/1"					Refusal on gravel and cobbles. Total Depth = 57.1 feet. Groundwater encountered at approximately 35 feet during drilling. Backfilled with approximately 20 cubic feet of bentonite grout shortly after drilling on 3/11/11. Note: Groundwater may rise to a level higher than that measured in borehole due to seasonal variations in precipitation and several other factors as discussed in the report.
60							

DRAFT

Ninyo & Moore

BORING LOG

EL MONTE VALLEY MINING, RECLAMATION, AND GROUNDWATER RECHARGE PROJECT, LAKESIDE, CALIFORNIA

PROJECT NO.	DATE	FIGURE
106200005	7/11	A-68

DATE DRILLED 3/10/11 BORING NO. B-20

GROUND ELEVATION 445' ± (MSL) SHEET 1 OF 2

METHOD OF DRILLING 8" Hollow-Stem Auger (Diedrich D-120) (Tri-County Drilling)

DRIVE WEIGHT 140 lbs. (Auto. Trip Hammer) DROP 30"

SAMPLED BY MBG LOGGED BY MBG REVIEWED BY GTF

DEPTH (feet)	SAMPLES (Bulk / Driven)	BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DESCRIPTION/INTERPRETATION
0						SM	ALLUVIUM: Light brown, moist, loose, silty fine to medium SAND.
5		10	7.0	95.3			Silty fine to coarse sand.
10		6					
15		22	6.2	101.4			Medium dense; silty fine sand.
20							

DRAFT

Ninyo & Moore

BORING LOG

EL MONTE VALLEY MINING, RECLAMATION, AND GROUNDWATER RECHARGE PROJECT, LAKESIDE, CALIFORNIA

PROJECT NO.	DATE	FIGURE
106200005	7/11	A-69

DATE DRILLED 3/10/11 BORING NO. B-20

GROUND ELEVATION 445' ± (MSL) SHEET 2 OF 2

METHOD OF DRILLING 8" Hollow-Stem Auger (Diedrich D-120) (Tri-County Drilling)

DRIVE WEIGHT 140 lbs. (Auto. Trip Hammer) DROP 30"

SAMPLED BY MBG LOGGED BY MBG REVIEWED BY GTF

DEPTH (feet)	SAMPLES (Bulk / Driven)	BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DESCRIPTION/INTERPRETATION
20		21				SM	ALLUVIUM: (Continued) Light brown, moist, dense, silty fine SAND.
						ML	Dark brown, moist, loose, fine sandy SILT; some fine to medium sand.
25		12					
							Total Depth = 26.5 feet. Groundwater not encountered. Backfilled with approximately 9 cubic feet of bentonite grout shortly after drilling on 3/10/11. Note: Groundwater, though not encountered at the time of drilling, may rise to a higher level due to seasonal variations in precipitation and several other factors as discussed in the report.
30							
35							
40							

DRAFT

Ninyo & Moore

BORING LOG

EL MONTE VALLEY MINING, RECLAMATION, AND GROUNDWATER RECHARGE PROJECT, LAKESIDE, CALIFORNIA

PROJECT NO.	DATE	FIGURE
106200005	7/11	A-70

DATE DRILLED 3/10/11 BORING NO. B-21

GROUND ELEVATION 450' ± (MSL) SHEET 1 OF 2

METHOD OF DRILLING 8" Hollow-Stem Auger (Diedrich D-120) (Tri-County Drilling)

DRIVE WEIGHT 140 lbs. (Auto. Trip Hammer) DROP 30"

SAMPLED BY MBG LOGGED BY MBG REVIEWED BY GTF

DEPTH (feet)	SAMPLES (Bulk / Driven)	BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DESCRIPTION/INTERPRETATION
0						SM	ALLUVIUM: Brown, moist, loose, silty fine SAND.
5							Trace coarse sand; trace roots.
10							Trace gravel (up to ¾ inch); micaceous.
15							Silty fine to medium sand; little coarse sand.
20							

DRAFT

Ninyo & Moore

BORING LOG

EL MONTE VALLEY MINING, RECLAMATION, AND GROUNDWATER RECHARGE PROJECT, LAKESIDE, CALIFORNIA

PROJECT NO.	DATE	FIGURE
106200005	7/11	A-71

DATE DRILLED 3/10/11 BORING NO. B-21

GROUND ELEVATION 450' ± (MSL) SHEET 2 OF 2

METHOD OF DRILLING 8" Hollow-Stem Auger (Diedrich D-120) (Tri-County Drilling)

DRIVE WEIGHT 140 lbs. (Auto. Trip Hammer) DROP 30"

SAMPLED BY MBG LOGGED BY MBG REVIEWED BY GTF

DEPTH (feet)	SAMPLES (Bulk / Driven)	BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DESCRIPTION/INTERPRETATION
20						SM	ALLUVIUM: (Continued) Brown, moist, loose to medium dense, silty fine SAND; trace roots.
25							METAVOLCANIC ROCK: Gray, dry, soft, weathered METAVOLCANIC ROCK.
30		50/4"					Refusal to further drilling. Total Depth = 30.3 feet. Groundwater not encountered. Backfilled with approximately 10 cubic feet of bentonite grout shortly after drilling on 3/10/11. Note: Groundwater, though not encountered at the time of drilling, may rise to a higher level due to seasonal variations in precipitation and several other factors as discussed in the report.
35							
40							

DRAFT

Ninyo & Moore

BORING LOG

EL MONTE VALLEY MINING, RECLAMATION, AND GROUNDWATER RECHARGE PROJECT, LAKESIDE, CALIFORNIA

PROJECT NO.	DATE	FIGURE
106200005	7/11	A-72

DATE DRILLED 2/24/11 BORING NO. B-22

GROUND ELEVATION 454' ± (MSL) SHEET 1 OF 2

METHOD OF DRILLING 8" Hollow-Stem Auger (Diedrich D-120) (Tri-County Drilling)

DRIVE WEIGHT 140 lbs. (Auto. Trip Hammer) DROP 30"

SAMPLED BY MBG LOGGED BY MBG REVIEWED BY GTF

DEPTH (feet)	SAMPLES (Bulk / Driven)	BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DESCRIPTION/INTERPRETATION
0						SM	ALLUVIUM: Brown, moist, loose, silty, fine to medium SAND.
						SW	Gray, moist, medium dense, well-graded, fine to coarse SAND.
5		18					
10		9					Loose.
15		24	3.6	103.7			Dry to damp; medium dense.
20							

DRAFT

Ninyo & Moore

BORING LOG

EL MONTE VALLEY MINING, RECLAMATION, AND GROUNDWATER RECHARGE PROJECT, LAKESIDE, CALIFORNIA

PROJECT NO.	DATE	FIGURE
106200005	7/11	A-73

DATE DRILLED 2/24/11 BORING NO. B-22

GROUND ELEVATION 454' ± (MSL) SHEET 2 OF 2

METHOD OF DRILLING 8" Hollow-Stem Auger (Diedrich D-120) (Tri-County Drilling)

DRIVE WEIGHT 140 lbs. (Auto. Trip Hammer) DROP 30"

SAMPLED BY MBG LOGGED BY MBG REVIEWED BY GTF

DEPTH (feet)	SAMPLES (Bulk / Driven)	BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DESCRIPTION/INTERPRETATION
20		18				ML	ALLUVIUM: (Continued) Gray to grayish brown, moist, medium dense, fine sandy SILT.
25		19				SC	Brown, moist, stiff, clayey fine SAND.
30							Total Depth = 26.5 feet. Groundwater not encountered. Backfilled with approximately 9 cubic feet of bentonite grout shortly after drilling on 2/24/11. Note: Groundwater, though not encountered at the time of drilling, may rise to a higher level due to seasonal variations in precipitation and several other factors as discussed in the report.
35							
40							

DRAFT

Ninyo & Moore

BORING LOG

EL MONTE VALLEY MINING, RECLAMATION, AND GROUNDWATER RECHARGE PROJECT, LAKESIDE, CALIFORNIA

PROJECT NO.	DATE	FIGURE
106200005	7/11	A-74

DATE DRILLED 2/28/11 and 3/1/11 BORING NO. B-23

GROUND ELEVATION 455' ± (MSL) SHEET 1 OF 5

METHOD OF DRILLING 8" Hollow-Stem Auger (Diedrich D-120) (Tri-County Drilling)

DRIVE WEIGHT 140 lbs. (Auto. Trip Hammer) DROP 30"

SAMPLED BY MBG LOGGED BY MBG REVIEWED BY GTF

DEPTH (feet)	SAMPLES (Bulk / Driven)	BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DESCRIPTION/INTERPRETATION
0						SM	ALLUVIUM: Brown, damp, loose, silty fine to medium SAND.
5							
10							
15							Medium dense; scattered coarse sand.
20							Micaceous.

DRAFT

Ninyo & Moore

BORING LOG

EL MONTE VALLEY MINING, RECLAMATION, AND GROUNDWATER RECHARGE PROJECT, LAKESIDE, CALIFORNIA

PROJECT NO.	DATE	FIGURE
106200005	7/11	A-75

DATE DRILLED 2/28/11 and 3/1/11 BORING NO. B-23

GROUND ELEVATION 455' ± (MSL) SHEET 2 OF 5

METHOD OF DRILLING 8" Hollow-Stem Auger (Diedrich D-120) (Tri-County Drilling)

DRIVE WEIGHT 140 lbs. (Auto. Trip Hammer) DROP 30"

SAMPLED BY MBG LOGGED BY MBG REVIEWED BY GTF

DEPTH (feet)	SAMPLES (Bulk / Driven)	BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DESCRIPTION/INTERPRETATION
20						SM	ALLUVIUM: (Continued) Brown, damp, medium dense, silty fine to medium SAND.
25							Scattered fine to coarse gravel.
30							
35			▽				Saturated.
40							

DRAFT

Ninyo & Moore

BORING LOG

EL MONTE VALLEY MINING, RECLAMATION, AND GROUNDWATER RECHARGE PROJECT, LAKESIDE, CALIFORNIA

PROJECT NO.	DATE	FIGURE
106200005	7/11	A-76

DATE DRILLED 2/28/11 and 3/1/11 BORING NO. B-23

GROUND ELEVATION 455' ± (MSL) SHEET 3 OF 5

METHOD OF DRILLING 8" Hollow-Stem Auger (Diedrich D-120) (Tri-County Drilling)

DRIVE WEIGHT 140 lbs. (Auto. Trip Hammer) DROP 30"

SAMPLED BY MBG LOGGED BY MBG REVIEWED BY GTF

DEPTH (feet)	SAMPLES (Bulk / Driven)	BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DESCRIPTION/INTERPRETATION
40						SM	ALLUVIUM: (Continued) Brown, saturated, medium dense, silty fine to medium SAND.
45							
50							
55							Dense.
60							

DRAFT

Ninyo & Moore

BORING LOG

EL MONTE VALLEY MINING, RECLAMATION, AND GROUNDWATER RECHARGE PROJECT, LAKESIDE, CALIFORNIA

PROJECT NO.	DATE	FIGURE
106200005	7/11	A-77

DATE DRILLED 2/28/11 and 3/1/11 BORING NO. B-23

GROUND ELEVATION 455' ± (MSL) SHEET 4 OF 5

METHOD OF DRILLING 8" Hollow-Stem Auger (Diedrich D-120) (Tri-County Drilling)

DRIVE WEIGHT 140 lbs. (Auto. Trip Hammer) DROP 30"

SAMPLED BY MBG LOGGED BY MBG REVIEWED BY GTF

DEPTH (feet)	SAMPLES (Bulk / Driven)	BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DESCRIPTION/INTERPRETATION
60		43				SP-SM	ALLUVIUM: (Continued) Brown to grayish brown, saturated, dense, poorly-graded, fine to medium SAND with silt.
65		41					Very dense; fine to coarse sand; scattered gravel; trace roots.
70		50				SW-SM	Brown to grayish brown, saturated, very dense, well-graded, fine to coarse SAND with silt.
75		34					Gray.
80							

DRAFT

Ninyo & Moore

BORING LOG

EL MONTE VALLEY MINING, RECLAMATION, AND GROUNDWATER RECHARGE PROJECT, LAKESIDE, CALIFORNIA

PROJECT NO.	DATE	FIGURE
106200005	7/11	A-78

DATE DRILLED 2/28/11 and 3/1/11 BORING NO. B-23

GROUND ELEVATION 455' ± (MSL) SHEET 5 OF 5

METHOD OF DRILLING 8" Hollow-Stem Auger (Diedrich D-120) (Tri-County Drilling)

DRIVE WEIGHT 140 lbs. (Auto. Trip Hammer) DROP 30"

SAMPLED BY MBG LOGGED BY MBG REVIEWED BY GTF

DEPTH (feet)	SAMPLES (Bulk / Driven)	BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DESCRIPTION/INTERPRETATION
80		59				SP	ALLUVIUM: (Continued) Gray, saturated, very dense, poorly-graded, fine to medium SAND. Boring terminated on 2/28/11. Boring resumed on 3/1/11.
85		61				SW-SM	Gray. saturated, very dense, well-graded, fine to coarse SAND with silt. Trace cobbles. Refusal to further drilling. Total Depth = 88.0 feet. Groundwater encountered at approximately 35 feet during drilling. Backfilled with approximately 31 cubic feet of bentonite grout shortly after drilling on 3/1/11. Note: Groundwater may rise to a level higher than that measured in borehole due to seasonal variations in precipitation and several other factors as discussed in the report.
90							
95							
100							

DRAFT

Ninyo & Moore

BORING LOG

EL MONTE VALLEY MINING, RECLAMATION, AND GROUNDWATER RECHARGE PROJECT, LAKESIDE, CALIFORNIA

PROJECT NO.	DATE	FIGURE
106200005	7/11	A-79

DATE DRILLED 3/3/11 BORING NO. B-24

GROUND ELEVATION 453' ± (MSL) SHEET 1 OF 5

METHOD OF DRILLING 8" Hollow-Stem Auger (Diedrich D-120) (Tri-County Drilling)

DRIVE WEIGHT 140 lbs. (Auto. Trip Hammer) DROP 30"

SAMPLED BY MBG LOGGED BY MBG REVIEWED BY GTF

DEPTH (feet)	SAMPLES (Bulk / Driven)	BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DESCRIPTION/INTERPRETATION
0						SP	ALLUVIUM: Light brown, damp, loose, poorly-graded, fine SAND.
5	Driven	35					Medium dense; trace gravel (up to ½ inch).
10						SM	Light brown, damp, medium dense, silty fine SAND; little coarse sand.
15							Moist; trace roots.
20							

DRAFT

Ninyo & Moore

BORING LOG

EL MONTE VALLEY MINING, RECLAMATION, AND GROUNDWATER RECHARGE PROJECT, LAKESIDE, CALIFORNIA

PROJECT NO.	DATE	FIGURE
106200005	7/11	A-80

DATE DRILLED 3/3/11 BORING NO. B-24

GROUND ELEVATION 453' ± (MSL) SHEET 2 OF 5

METHOD OF DRILLING 8" Hollow-Stem Auger (Diedrich D-120) (Tri-County Drilling)

DRIVE WEIGHT 140 lbs. (Auto. Trip Hammer) DROP 30"

SAMPLED BY MBG LOGGED BY MBG REVIEWED BY GTF

DEPTH (feet)	SAMPLES (Bulk / Driven)	BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DESCRIPTION/INTERPRETATION
20						SM	ALLUVIUM: (Continued) Light brown, moist, medium dense, silty fine SAND; little medium to coarse sand; trace gravel (up to ½ inch); trace roots.
25							Brown; wet.
30							Fine to medium sand; little coarse sand; trace roots. Dense.
35						SW	Brown, moist, dense, well-graded, fine to coarse SAND.
40							

DRAFT

Ninyo & Moore

BORING LOG

EL MONTE VALLEY MINING, RECLAMATION, AND GROUNDWATER RECHARGE PROJECT, LAKESIDE, CALIFORNIA

PROJECT NO.	DATE	FIGURE
106200005	7/11	A-81

DATE DRILLED 3/3/11 BORING NO. B-24

GROUND ELEVATION 453' ± (MSL) SHEET 3 OF 5

METHOD OF DRILLING 8" Hollow-Stem Auger (Diedrich D-120) (Tri-County Drilling)

DRIVE WEIGHT 140 lbs. (Auto. Trip Hammer) DROP 30"

SAMPLED BY MBG LOGGED BY MBG REVIEWED BY GTF

DEPTH (feet)	SAMPLES (Bulk / Driven)	BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DESCRIPTION/INTERPRETATION
40			▽			SW	ALLUVIUM: (Continued) Brown, saturated, dense, well-graded, fine to coarse SAND.
45							
50							
55							Grayish brown; micaceous.
60							Trace silt.

DRAFT

Ninyo & Moore

BORING LOG

EL MONTE VALLEY MINING, RECLAMATION, AND GROUNDWATER RECHARGE PROJECT, LAKESIDE, CALIFORNIA

PROJECT NO.	DATE	FIGURE
106200005	7/11	A-82

DATE DRILLED 3/3/11 BORING NO. B-24

GROUND ELEVATION 453' ± (MSL) SHEET 4 OF 5

METHOD OF DRILLING 8" Hollow-Stem Auger (Diedrich D-120) (Tri-County Drilling)

DRIVE WEIGHT 140 lbs. (Auto. Trip Hammer) DROP 30"

SAMPLED BY MBG LOGGED BY MBG REVIEWED BY GTF

DEPTH (feet)	SAMPLES (Bulk / Driven)	BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DESCRIPTION/INTERPRETATION
60						SM	ALLUVIUM: (Continued) Brown, saturated, medium dense, silty fine SAND.
		31					
65		13					
70		26					Dense.
75		14					Medium dense.
80							

DRAFT

Ninyo & Moore

BORING LOG

EL MONTE VALLEY MINING, RECLAMATION, AND GROUNDWATER RECHARGE PROJECT, LAKESIDE, CALIFORNIA

PROJECT NO.	DATE	FIGURE
106200005	7/11	A-83

DATE DRILLED 3/3/11 BORING NO. B-24

GROUND ELEVATION 453' ± (MSL) SHEET 5 OF 5

METHOD OF DRILLING 8" Hollow-Stem Auger (Diedrich D-120) (Tri-County Drilling)

DRIVE WEIGHT 140 lbs. (Auto. Trip Hammer) DROP 30"

SAMPLED BY MBG LOGGED BY MBG REVIEWED BY GTF

DEPTH (feet)	SAMPLES (Bulk / Driven)	BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DESCRIPTION/INTERPRETATION
80		12				SM	ALLUVIUM: (Continued) Brown, saturated, medium dense, silty fine SAND.
		22				SP-SM	Brown, saturated, medium dense, poorly-graded, fine SAND with silt. Refusal to further drilling. Total Depth = 87.0 feet. Groundwater encountered at approximately 40 feet during drilling. Backfilled with approximately 30 cubic feet of bentonite grout shortly after drilling on 3/3/11. Note: Groundwater may rise to a level higher than that measured in borehole due to seasonal variations in precipitation and several other factors as discussed in the report.
85							
90							
95							
100							

DRAFT

Ninyo & Moore

BORING LOG

EL MONTE VALLEY MINING, RECLAMATION, AND GROUNDWATER RECHARGE PROJECT, LAKESIDE, CALIFORNIA

PROJECT NO.	DATE	FIGURE
106200005	7/11	A-84

DATE DRILLED 3/4/11 BORING NO. B-25

GROUND ELEVATION 465' ± (MSL) SHEET 1 OF 2

METHOD OF DRILLING 8" Hollow-Stem Auger (Diedrich D-120) (Tri-County Drilling)

DRIVE WEIGHT 140 lbs. (Auto. Trip Hammer) DROP 30"

SAMPLED BY MBG LOGGED BY MBG REVIEWED BY GTF

DEPTH (feet)	SAMPLES (Bulk / Driven)	BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DESCRIPTION/INTERPRETATION
0						SM	ALLUVIUM: Gray, damp, loose, silty fine to medium SAND.
						SW-SM	Gray, damp, medium dense, well-graded, fine to coarse SAND with silt.
5	Driven	19	3.5	110.5			
10	Driven	16					
15	Driven	45	6.2	100.0			Dense.
20							

DRAFT

Ninyo & Moore

BORING LOG

EL MONTE VALLEY MINING, RECLAMATION, AND GROUNDWATER RECHARGE PROJECT, LAKESIDE, CALIFORNIA

PROJECT NO.	DATE	FIGURE
106200005	7/11	A-85

DATE DRILLED 3/4/11 BORING NO. B-25

GROUND ELEVATION 465' ± (MSL) SHEET 2 OF 2

METHOD OF DRILLING 8" Hollow-Stem Auger (Diedrich D-120) (Tri-County Drilling)

DRIVE WEIGHT 140 lbs. (Auto. Trip Hammer) DROP 30"

SAMPLED BY MBG LOGGED BY MBG REVIEWED BY GTF

DEPTH (feet)	SAMPLES (Bulk / Driven)	BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DESCRIPTION/INTERPRETATION
20		13				SM	ALLUVIUM: (Continued) Gray, damp, medium dense, silty fine SAND.
						ML	Brown, moist, medium dense, fine sandy SILT.
25		6					Loose.
							Total Depth = 26.5 feet. Groundwater not encountered. Backfilled with approximately 9 cubic feet of bentonite grout shortly after drilling on 3/4/11. Note: Groundwater, though not encountered at the time of drilling, may rise to a higher level due to seasonal variations in precipitation and several other factors as discussed in the report.
30							
35							
40							

DRAFT

Ninyo & Moore

BORING LOG

EL MONTE VALLEY MINING, RECLAMATION, AND GROUNDWATER RECHARGE PROJECT, LAKESIDE, CALIFORNIA

PROJECT NO.	DATE	FIGURE
106200005	7/11	A-86

DATE DRILLED 3/4/11 BORING NO. B-26

GROUND ELEVATION 469' ± (MSL) SHEET 1 OF 6

METHOD OF DRILLING 8" Hollow-Stem Auger (Diedrich D-120) (Tri-County Drilling)

DRIVE WEIGHT 140 lbs. (Auto. Trip Hammer) DROP 30"

SAMPLED BY MBG LOGGED BY MBG REVIEWED BY GTF

DEPTH (feet)	SAMPLES (Bulk / Driven)	BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DESCRIPTION/INTERPRETATION
0						ML	ALLUVIUM: Brown, moist, loose, fine sandy SILT.
5							
						SM	Brown, moist, loose to medium dense, silty fine SAND.
10							
15							Trace coarse sand.
20							

DRAFT

Ninyo & Moore

BORING LOG

EL MONTE VALLEY MINING, RECLAMATION, AND GROUNDWATER RECHARGE PROJECT, LAKESIDE, CALIFORNIA

PROJECT NO.	DATE	FIGURE
106200005	7/11	A-87

DATE DRILLED 3/4/11 BORING NO. B-26

GROUND ELEVATION 469' ± (MSL) SHEET 2 OF 6

METHOD OF DRILLING 8" Hollow-Stem Auger (Diedrich D-120) (Tri-County Drilling)

DRIVE WEIGHT 140 lbs. (Auto. Trip Hammer) DROP 30"

SAMPLED BY MBG LOGGED BY MBG REVIEWED BY GTF

DEPTH (feet)	SAMPLES (Bulk / Driven)	BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DESCRIPTION/INTERPRETATION
20						SM	ALLUVIUM: (Continued) Light brown, moist, loose to medium dense, silty fine SAND; few coarse sand.
							Medium dense.
25							Silty fine to medium sand.
30							Some coarse sand.
35							Silty fine to coarse sand.
40							

DRAFT

Ninyo & Moore

BORING LOG

EL MONTE VALLEY MINING, RECLAMATION, AND GROUNDWATER RECHARGE PROJECT, LAKESIDE, CALIFORNIA

PROJECT NO.	DATE	FIGURE
106200005	7/11	A-88

DATE DRILLED 3/4/11 BORING NO. B-26

GROUND ELEVATION 469' ± (MSL) SHEET 3 OF 6

METHOD OF DRILLING 8" Hollow-Stem Auger (Diedrich D-120) (Tri-County Drilling)

DRIVE WEIGHT 140 lbs. (Auto. Trip Hammer) DROP 30"

SAMPLED BY MBG LOGGED BY MBG REVIEWED BY GTF

DEPTH (feet)	SAMPLES (Bulk / Driven)	BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DESCRIPTION/INTERPRETATION
40						SM	ALLUVIUM: (Continued) Brown, wet, medium dense, silty fine to coarse SAND.
45			▽				Saturated; micaceous.
50							Trace gravel (up to ½ inch).
55							Silty fine sand; trace coarse sand.
						ML	Dark brown, saturated, dense, fine sandy SILT.
60							

DRAFT

Ninyo & Moore

BORING LOG

EL MONTE VALLEY MINING, RECLAMATION, AND GROUNDWATER RECHARGE PROJECT, LAKESIDE, CALIFORNIA

PROJECT NO.	DATE	FIGURE
106200005	7/11	A-89

DATE DRILLED 3/4/11 BORING NO. B-26

GROUND ELEVATION 469' ± (MSL) SHEET 4 OF 6

METHOD OF DRILLING 8" Hollow-Stem Auger (Diedrich D-120) (Tri-County Drilling)

DRIVE WEIGHT 140 lbs. (Auto. Trip Hammer) DROP 30"

SAMPLED BY MBG LOGGED BY MBG REVIEWED BY GTF

DEPTH (feet)	SAMPLES (Bulk / Driven)	BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DESCRIPTION/INTERPRETATION
60		20				SM	ALLUVIUM: (Continued) Dark brown, saturated, medium dense, silty fine SAND.
						SW	Dark gray, saturated, medium dense to dense, well-graded, fine to coarse SAND.
						SM	Grayish brown, saturated, dense, silty fine SAND.
65		23					
70		55				SW-SM	Grayish brown, saturated, dense, well-graded, fine to coarse SAND with silt.
75		42					Very dense; few gravel up to (1½ inch).
80							

DRAFT

Ninyo & Moore

BORING LOG

EL MONTE VALLEY MINING, RECLAMATION, AND GROUNDWATER RECHARGE PROJECT, LAKESIDE, CALIFORNIA

PROJECT NO.	DATE	FIGURE
106200005	7/11	A-90

DATE DRILLED 3/4/11 BORING NO. B-26

GROUND ELEVATION 469' ± (MSL) SHEET 5 OF 6

METHOD OF DRILLING 8" Hollow-Stem Auger (Diedrich D-120) (Tri-County Drilling)

DRIVE WEIGHT 140 lbs. (Auto. Trip Hammer) DROP 30"

SAMPLED BY MBG LOGGED BY MBG REVIEWED BY GTF

DEPTH (feet)	SAMPLES (Bulk / Driven)	BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DESCRIPTION/INTERPRETATION
80		38				SP-SM	ALLUVIUM: (Continued) Grayish brown, saturated, very dense, poorly-graded, fine to medium SAND with silt; micaceous.
85		50/4"				SW-SM	Gray, saturated, very dense, well-graded, fine to coarse SAND with silt.
90		78/10"				SM	Grayish brown, saturated, very dense, silty fine to medium SAND. Fine to coarse sand.
95		24					Dense. Dark brown; silty fine sand.
100							

DRAFT

Ninyo & Moore

BORING LOG

EL MONTE VALLEY MINING, RECLAMATION, AND GROUNDWATER RECHARGE PROJECT, LAKESIDE, CALIFORNIA

PROJECT NO.	DATE	FIGURE
106200005	7/11	A-91

DATE DRILLED 3/4/11 BORING NO. B-26

GROUND ELEVATION 469' ± (MSL) SHEET 6 OF 6

METHOD OF DRILLING 8" Hollow-Stem Auger (Diedrich D-120) (Tri-County Drilling)

DRIVE WEIGHT 140 lbs. (Auto. Trip Hammer) DROP 30"

SAMPLED BY MBG LOGGED BY MBG REVIEWED BY GTF

DEPTH (feet)	SAMPLES Bulk	SAMPLES Driven	BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DESCRIPTION/INTERPRETATION
100		■	50/3"			▒	SM	ALLUVIUM: (Continued) Dark brown, saturated, very dense, silty fine SAND; some gravel (up to 2 inches). Refusal to further drilling.
								Total Depth = 101.0 feet. Groundwater encountered at approximately 45 feet during drilling. Backfilled with approximately 35 cubic feet of bentonite grout shortly after drilling on 3/4/11. Note: Groundwater may rise to a level higher than that measured in borehole due to seasonal variations in precipitation and several other factors as discussed in the report.
105								
110								
115								
120								

DRAFT

Ninyo & Moore

BORING LOG

EL MONTE VALLEY MINING, RECLAMATION, AND GROUNDWATER RECHARGE PROJECT, LAKESIDE, CALIFORNIA

PROJECT NO.	DATE	FIGURE
106200005	7/11	A-92

DATE DRILLED 2/25/11 BORING NO. B-27

GROUND ELEVATION 477' ± (MSL) SHEET 1 OF 2

METHOD OF DRILLING 8" Hollow-Stem Auger (Diedrich D-120) (Tri-County Drilling)

DRIVE WEIGHT 140 lbs. (Auto. Trip Hammer) DROP 30"

SAMPLED BY MBG LOGGED BY MBG REVIEWED BY GTF

DEPTH (feet)	SAMPLES (Bulk / Driven)	BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DESCRIPTION/INTERPRETATION
0						SM	ALLUVIUM: Brown, damp, medium dense, silty SAND.
							Scattered gravel (up to 1 inch).
5		52	6.0	121.2			Dense; trace gravel (up to 1 inch).
10		20					Medium dense to dense; trace roots; few gravel.
15		34					Medium dense.
20							

DRAFT

Ninyo & Moore

BORING LOG

EL MONTE VALLEY MINING, RECLAMATION, AND GROUNDWATER RECHARGE PROJECT, LAKESIDE, CALIFORNIA

PROJECT NO.	DATE	FIGURE
106200005	7/11	A-93

DATE DRILLED 2/25/11 BORING NO. B-27

GROUND ELEVATION 477' ± (MSL) SHEET 2 OF 2

METHOD OF DRILLING 8" Hollow-Stem Auger (Diedrich D-120) (Tri-County Drilling)

DRIVE WEIGHT 140 lbs. (Auto. Trip Hammer) DROP 30"

SAMPLED BY MBG LOGGED BY MBG REVIEWED BY GTF

DEPTH (feet)	SAMPLES (Bulk / Driven)	BLOWS/FOOT	MOISTURE (%)	DRY DENSITY (PCF)	SYMBOL	CLASSIFICATION U.S.C.S.	DESCRIPTION/INTERPRETATION
20		24	3.1	103.1		SW	ALLUVIUM: (Continued) Gray, dry to damp, medium dense, well-graded, fine to coarse SAND.
25		22				SM	Grayish brown, damp, dense, silty fine to coarse SAND.
30							Total Depth = 26.5 feet. Groundwater not encountered. Backfilled with approximately 9 cubic feet of bentonite grout shortly after drilling on 2/25/11. Note: Groundwater, though not encountered at the time of drilling, may rise to a higher level due to seasonal variations in precipitation and several other factors as discussed in the report.
35							
40							

DRAFT

Ninyo & Moore

BORING LOG

EL MONTE VALLEY MINING, RECLAMATION, AND GROUNDWATER RECHARGE PROJECT, LAKESIDE, CALIFORNIA

PROJECT NO.	DATE	FIGURE
106200005	7/11	A-94

APPENDIX C

LABORATORY TEST RESULTS

DRAFT



Cobbles & Boulders	Gravel		Sand			Silt	Clay
	Coarse	Fine	Coarse	Medium	Fine		

	Sample No.	Gravel	Sand	Fines	Clay	D_{10}	D_{30}	D_{50}	D_{60}	C_u	C_c
●	1B (10 - 13 ft)	6.5	83.8	9.8		0.0768	0.275	0.565	0.798	10.4	1.2
	(SW-SM) Well-graded sand with silt, fine to coarse										
■	2C (20 - 22 ft)		66.2	33.8			0.070	0.099	0.118		
	(SM) Silty sand, fine										
◆	4B (10 - 13 ft)	1.3	69.0	29.8			0.075	0.132	0.179		
	(SM) Silty sand, fine to medium										

DRAFT

PARTICLE SIZE DISTRIBUTION (ASTM D422)

Project:	Slope Stability Investigation				
Location:	13964 El MOnte Road, Lakeside, California				
Job Number:	15383-8	Engineer:	fy	Enclosure:	C-1

G:\2015\15383-8 El Monte NP - EM Sand Mine - Lakeside\lab\LabSuite_15383-3.csv
LabSuite© Version 4.0.3.26. Developed by Fred Yi, PhD, PE, GE Copyright© 2002 - 2015 GeoAdvanced™. All rights reserved _Commercial Copy Prepared at 9/2/2015 15:03:27

FINES CONTENT (ASTM C117)

Boring No.	3	3	3	3	3
Depth (ft)	0 - 5	5 - 25	25 - 30	30 - 35	35 - 40
Original Dry Mass	189.9	195.8	165.4	197.2	153.1
Dry Mass after Washing	122.1	189.3	78.9	190.2	48.1
Fine Contents (%)	35.7	3.3	52.3	3.5	68.6
Classification	SM	SP	ML	SP	ML
Boring No.	3	3	3	3	3
Depth (ft)	40 - 45	45 - 60	60 - 65	65 - 87	87 - 95
Original Dry Mass	158.7	158.2	151.2	168.8	166
Dry Mass after Washing	76.7	118.6	90.9	156.8	129.7
Fine Contents (%)	51.7	25.0	39.9	7.1	21.9
Classification	ML	SM	SM	SP-SM	SM

DRAFT

Copyright© 2002 - 2015 GeoAdvanced™. All rights reserved _Commercial Copy



DRAFT

	Boring No.	Depth (ft)	γ_d (pcf)	w (%)	C_{pk} (psf)	ϕ_{pk} (°)	C_{rs} (psf)	ϕ_{rs} (°)
●	1	20	108.0	2.1	134.0	36.8	57.5	33.6
	(SP-SM) Sand, fine to coarse / Undisturbed							
■	1	90	116.0	18.6	362.2	40.7	229.9	36.2
	(SM) Silty sand, fine to coarse / Undisturbed							

DIRECT SHEAR TESTS (ASTM D3080)

Project:	Slope Stability Investigation				
Location:	13964 El MOnte Road, Lakeside, California				
Job Number:	15383-8	Engineer:	fy	Enclosure:	C-3

G:\2015\15383-8 El Monte NP - EM Sand Mine - Lakeside\lab\LabSuite_15383-3.csv

LabSuite© Version 4.0.3.26. Developed by Fred Yi, PhD, PE, GE Copyright© 2002 - 2015 GeoAdvanced™. All rights reserved _Commercial Copy



DRAFT

	Boring No.	Depth (ft)	γ_d (pcf)	w (%)	C_{pk} (psf)	ϕ_{pk} (°)	C_{rs} (psf)	ϕ_{rs} (°)
●	2	45	100.0	21.0	198.7	32.9	144.4	30.2
	(SP-SM) Sand, fine to coarse / Undisturbed							
■	2	60	91.0	30.5	245.1	31.7	107.4	29.9
	(SM) Silty sand, fine to medium / Undisturbed							

DIRECT SHEAR TESTS (ASTM D3080)

Project:	Slope Stability Investigation				
Location:	13964 El MOnte Road, Lakeside, California				
Job Number:	15383-8	Engineer:	fy	Enclosure:	C-4

G:\2015\15383-8 El Monte NP - EM Sand Mine - Lakeside\lab\LabSuite_15383-3.csv

LabSuite© Version 4.0.3.26. Developed by Fred Yi, PhD, PE, GE Copyright© 2002 - 2015 GeoAdvanced™. All rights reserved _Commercial Copy
Prepared at 9/2/2015 15:03:27



DRAFT

	Boring No.	Depth (ft)	γ_d (pcf)	w (%)	C_{pk} (psf)	ϕ_{pk} (°)	C_{rs} (psf)	ϕ_{rs} (°)
●	3	40	92.0	28.0	214.2	29.8	250.0	28.1
	(ML) Sandy silt, fine / Remolded (RC=80%)							
■	4	15	99.0	4.3	117.0	30.0	108.6	30.1
	(SM) Silty sand, fine to medium / Undisturbed							

DIRECT SHEAR TESTS (ASTM D3080)

Project:	Slope Stability Investigation				
Location:	13964 El MOnte Road, Lakeside, California				
Job Number:	15383-8	Engineer:	fy	Enclosure:	C-5

G:\2015\15383-8 El Monte NP - EM Sand Mine - Lakeside\lab\LabSuite_15383-3.csv

LabSuite© Version 4.0.3.26. Developed by Fred Yi, PhD, PE, GE Copyright© 2002 - 2015 GeoAdvanced™. All rights reserved _Commercial Copy
Prepared at 9/2/2015 15:03:27





DRAFT

	Boring No.	Depth (ft)	USCS	γ_d (pcf)	w (%)	C_{pk} (psf)	ϕ_{pk} (°)	C_{rs} (psf)	ϕ_{rs} (°)
●	1	20	(SP-SM) Sand, fine to coarse / Undisturbed	108.0	2.1	134.0	36.8	57.5	33.6

CHJ Consultants

DIRECT SHEAR TESTS (ASTM D3080)

Project:	Slope Stability Investigation				
Location:	13964 El MOnte Road, Lakeside, California				
Job Number:	15383-8	Engineer:	fy	Enclosure:	C-6

G:\2015\15383-8 El Monte NP - EM Sand Mine - Lakeside\lab\LabSuite_15383-3.csv

LabSuite© Version 4.0.3.26. Developed by Fred Yi, PhD, PE, GE
Copyright© 2002 - 2015 GeoAdvanced™. All rights reserved _Commercial Copy
Prepared at 9/2/2015 15:03:27





DRAFT

	Boring No.	Depth (ft)	USCS	γ_d (pcf)	w (%)	C_{pk} (psf)	ϕ_{pk} (°)	C_{rs} (psf)	ϕ_{rs} (°)
●	1	90	(SM) Silty sand, fine to coarse / Undisturbed	116.0	18.6	362.2	40.7	229.9	36.2

CHJ Consultants

DIRECT SHEAR TESTS (ASTM D3080)

Project:	Slope Stability Investigation				
Location:	13964 El MOnte Road, Lakeside, California				
Job Number:	15383-8	Engineer:	fy	Enclosure:	C-7

G:\2015\15383-8 El Monte NP - EM Sand Mine - Lakeside\lab\LabSuite_15383-3.csv

LabSuite© Version 4.0.3.26. Developed by Fred Yi, PhD, PE, GE

Copyright© 2002 - 2015 GeoAdvanced™. All rights reserved _Commercial Copy

Prepared at 9/2/2015 15:03:27





DRAFT

	Boring No.	Depth (ft)	USCS	γ_d (pcf)	w (%)	C_{pk} (psf)	ϕ_{pk} (°)	C_{rs} (psf)	ϕ_{rs} (°)
●	2	45	(SP-SM) Sand, fine to coarse / Undisturbed	100.0	21.0	198.7	32.9	144.4	30.2

CHJ Consultants

DIRECT SHEAR TESTS (ASTM D3080)

Project:	Slope Stability Investigation				
Location:	13964 El MOnte Road, Lakeside, California				
Job Number:	15383-8	Engineer:	fy	Enclosure:	C-8

G:\2015\15383-8 El Monte NP - EM Sand Mine - Lakeside\lab\LabSuite_15383-3.csv

LabSuite© Version 4.0.3.26. Developed by Fred Yi, PhD, PE, GE
Copyright© 2002 - 2015 GeoAdvanced™. All rights reserved _Commercial Copy
Prepared at 9/2/2015 15:03:27





DRAFT

	Boring No.	Depth (ft)	USCS	γ_d (pcf)	w (%)	C_{pk} (psf)	ϕ_{pk} (°)	C_{rs} (psf)	ϕ_{rs} (°)
●	2	60	(SM) Silty sand, fine to medium / Undisturbed	91.0	30.5	245.1	31.7	107.4	29.9

CHJ Consultants

DIRECT SHEAR TESTS (ASTM D3080)

Project:	Slope Stability Investigation				
Location:	13964 El MOnte Road, Lakeside, California				
Job Number:	15383-8	Engineer:	fy	Enclosure:	C-9

G:\2015\15383-8 El Monte NP - EM Sand Mine - Lakeside\lab\LabSuite_15383-3.csv

LabSuite© Version 4.0.3.26. Developed by Fred Yi, PhD, PE, GE
Copyright© 2002 - 2015 GeoAdvanced™. All rights reserved _Commercial Copy
Prepared at 9/2/2015 15:03:27





DRAFT

	Boring No.	Depth (ft)	USCS	γ_d (pcf)	w (%)	C_{pk} (psf)	ϕ_{pk} (°)	C_{rs} (psf)	ϕ_{rs} (°)
●	3	40	(ML) Sandy silt, fine / Remolded (RC=80%)	92.0	28.0	214.2	29.8	250.0	28.1

CHJ Consultants

DIRECT SHEAR TESTS (ASTM D3080)

Project:	Slope Stability Investigation				
Location:	13964 El MOnte Road, Lakeside, California				
Job Number:	15383-8	Engineer:	fy	Enclosure:	C-10

G:\2015\15383-8 El Monte NP - EM Sand Mine - Lakeside\lab\LabSuite_15383-3.csv

LabSuite© Version 4.0.3.26. Developed by Fred Yi, PhD, PE, GE
Copyright© 2002 - 2015 GeoAdvanced™. All rights reserved _Commercial Copy
Prepared at 9/2/2015 15:03:27





DRAFT

	Boring No.	Depth (ft)	USCS	γ_d (pcf)	w (%)	C_{pk} (psf)	ϕ_{pk} (°)	C_{rs} (psf)	ϕ_{rs} (°)
●	4	15	(SM) Silty sand, fine to medium / Undisturbed	99.0	4.3	117.0	30.0	108.6	30.1

CHJ Consultants

DIRECT SHEAR TESTS (ASTM D3080)

Project:	Slope Stability Investigation				
Location:	13964 El MOnte Road, Lakeside, California				
Job Number:	15383-8	Engineer:	fy	Enclosure:	C-11

G:\2015\15383-8 El Monte NP - EM Sand Mine - Lakeside\lab\LabSuite_15383-3.csv

Copyright© 2002 - 2015 GeoAdvanced™. All rights reserved _Commercial Copy



DRAFT

Boring No.		Depth (ft)	Soil/Sample Type	γ_d (pcf)	MC(%)	C (psf)	φ(°)
●	2	10	(MH) Elastic silt	51	73.0	822	28
■	3	20	(MH) Elastic silt	57	71.6	336	35
▲	3	45	(MH) Elastic silt	56	69.9	120	34

C.H.J. Incorporated

DIRECT SHEAR TEST

Project:	Proposed Amended Reclamation of CalPortland Colton Cement Plant		
Location:	Colton, California		
Job No.:	11691-3	Enclosure:	

Copyright© C.H.J. Incorporated 2005 - 2011. All right reserved



DRAFT

Boring No.		Depth (ft)	Soil/Sample Type	γ_d (pcf)	MC (%)	C_{peak} (psf)	φ_{peak} (°)	C_{res} (psf)	φ_{res} (°)
	2	10	(MH) Elastic silt, CKD	51.0	73.0	1344	38	822	28

C.H.J. Incorporated

DIRECT SHEAR TEST

Project:	Proposed Amended Reclamation of CalPortland Colton Cement Plant		
Location	Colton, California		
Job Number	11691-3	Enclosure	

CHJ® LabSuite ver3.06. Programmed by Fred Yi, PhD, PE

Copyright© C.H.J. Incorporated 2005 - 2011. All right reserved

Prepared at 12/13/2011



DRAFT

Boring No.	Depth (ft)	Soil/Sample Type	γ_d (pcf)	MC (%)	C_{peak} (psf)	φ_{peak} (°)	C_{res} (psf)	φ_{res} (°)
3	20	(MH) Elastic silt, CKD	57.0	71.6	660	44	336	35

C.H.J. Incorporated

DIRECT SHEAR TEST

Project:	Proposed Amended Reclamation of CalPortland Colton Cement Plant		
Location	Colton, California		
Job Number	11691-3	Enclosure	C-13

CHJ® LabSuite ver3.06. Programmed by Fred Yi, PhD, PE

Copyright© C.H.J. Incorporated 2005 - 2011. All right reserved

Prepared at 12/13/2011



DRAFT

Boring No.	Depth (ft)	Soil/Sample Type	γ_d (pcf)	MC (%)	C_{peak} (psf)	φ_{peak} (°)	C_{res} (psf)	φ_{res} (°)
3	45	(MH) Elastic silt, CKD	56.0	69.9	396	33	120	34

C.H.J. Incorporated

DIRECT SHEAR TEST

Project:	Proposed Amended Reclamation of CalPortland Colton Cement Plant		
Location	Colton, California		
Job Number	11691-3	Enclosure	C-17

Copyright© C.H.J. Incorporated 2005 - 2011. All right reserved

APPENDIX D

GLOBAL STABILITY CALCULATIONS

DRAFT



Material Name	Color	Unit Weight (lbs/ft3)	Strength Type	Cohesion (psf)	Phi (deg)	Water Surface	Ru
alluvium		115	Mohr-Coulomb	40	34	None	0

DRAFT

SLIDEINTERPRET 6.038

Project	El Monte Sand		
Analysis Description	Reclamation Slope Geometry		
Drawn By CHJ	*Author* JMc	*Scale* 1:200	
File Name Proposed Recl Slope Geometry.slim	*Date* January 2016	*Enclosure* D-1.1	

Safety Factor
0.00
0.25
0.50
0.75
1.00
1.25
1.50
1.75
2.00
2.25
2.50
2.75
3.00
3.25
3.50
3.75
4.00
4.25
4.50
4.75
5.00
5.25
5.50
5.75
6.00+

Global Minimums
Method: spencer
FS: 1.733650
Center: 17.470, 189.886
Radius: 90.151
Left Slip Surface Endpoint: 10.572, 100.000
Right Slip Surface Endpoint: 74.418, 120.000
Resisting Moment=2.19734e+006 lb-ft
Driving Moment=1.26746e+006 lb-ft
Resisting Horizontal Force=23002.5 lb
Driving Horizontal Force=13268.3 lb
Total Slice Area=298.621 ft2

0.12

1.73

20 ft
18°
10 ft
18°
20 ft

Material Name	Color	Unit Weight (lbs/ft3)	Strength Type	Cohesion (psf)	Phi (deg)	Water Surface	Ru
alluvium		115	Mohr-Coulomb	40	34	None	0

DRAFT

135
120
105
90
75
60
-30 -15 0 15 30 45 60 75 90 105 120 135 150 165 180 195 210

SLIDEINTERPRET 6.038

Project	El Monte Sand		
Analysis Description	Reclamation Slope Geometry		
Drawn By	CHJ	Author	JMc
File Name	Proposed Recl Slope Geometry seis.slim	Date	January 2016
Scale	1:200		
Enclosure	D-1.2		



Material Name	Color	Unit Weight (lbs/ft3)	Strength Type	Cohesion (psf)	Phi (deg)	Water Surface	Ru
alluvium		115	Mohr-Coulomb	40	34	Water Surface	

DRAFT

SLIDEINTERPRET 6.038

Project	El Monte Sand		
Analysis Description	Reclamation Slope Geometry		
Drawn By	CHJ	Author	JMc
File Name	Proposed Recl Slope Geometry flooded420.slim	Date	January 2016
Scale	1:200		
Enclosure	D-1.3		

D:	4	ft
z_w:	4	ft
γ:	99	pcf
γ_w:	62.4	pcf
slope, α	26.5	°
Friction Angle, Φ'	30	°
Cohesion, c'	117	psf
Factor of Safety, F:	1.17	



$$F = \frac{c' + [\gamma D - \gamma_w z_w]\cos^2\alpha \tan\phi'}{\gamma D \sin\alpha \cos\alpha}$$

DRAFT

CHJ Consultants

Surficial Stability Analysis

Project:	El Monte Sand Reclamation Slopes		
Location:	Lakeside Area, San Diego County		
Job Number:	15383-8	Enclosure:	D-2

APPENDIX E

GEOTECHNICAL CALCULATIONS

DRAFT



SM-ML | ML-SM | SM

SP | ML | SP-SM

Earthquake & Groundwater Information:
Magnitude = 6.2
Max. Acceleration = 0.35 g
Project GW = 34 ft
Maximum Settlement = 6.22 in
Settlement at Bottom of Footing = 6.22 in

Liquefaction: Idriss & Boulanger (2008)
Settl.: [dry] Pradel (1998); [sat] Idriss & Boulanger (2008)
Lateral spreading: Idriss & Boulanger (2008)
M correction: [Sand] Boulanger & Idriss(2004)
σv correction: Idriss & Boulanger (2008)
Stress reduction: Idriss & Boulanger (2008)

CHJ Consultants

Seismic Settlement Potential - SPT Data

Project:	Slope Stability Investigation				
Location:	13964 El MOnte Road, Lakeside, California				
Job Number:	15383-3	Boring No.:	B-3	Enclosure:	

G:\2015\15383-8 El Monte NP - EM Sand Mine - Lakeside\liq\GeoSuite_15383-3_B-3.csv

GeoSuite© Version 2.4.0.3. Developed by Fred Yi, PhD, PE, GE
Copyright© 2002 - 2015 GeoAdvanced™. All rights reserved _Commercial Copy
Prepared at 9/9/2015 10:31:23